



User documentation

Nicolas KIELBASIEWICZ, Eric LUNÉVILLE

February 9, 2024



Contents

1	Introduction	1
1.1	What XLIfe++ is	1
1.2	How to download XLIfe++	1
1.2.1	How XLIfe++ sources are organized	2
1.2.2	How XLIfe++ binaries are organized	2
1.3	Requirements	2
1.3.1	Extensions	2
1.3.2	Installation requirements	3
1.4	Main installation and usage process, with CMAKE	3
1.4.1	Configuration step	4
1.4.2	How to set compilers	4
1.4.3	How to set external dependencies	5
1.4.4	Installing binaries	8
1.4.5	Compilation of a program using XLIfe++	9
1.4.6	Example	12
1.5	Alternative installation and usage procedure, without cmake	15
1.5.1	Installation process	15
1.5.2	Compilation of a program using XLIfe++	16
1.6	Alternative installation and usage process, with DOCKER	17
1.7	Writing a program using XLIfe++	18
1.8	License	18
1.9	Credits	18
2	Getting started	20
2.1	The variational approach	20
2.2	How does it work ?	21
3	Examples	23
3.1	1D problems	23
3.1.1	Dirichlet condition	23
3.1.2	Robin condition	24
3.2	Laplace Problems	26
3.2.1	Neumann condition	26
3.2.2	Dirichlet condition	28
3.2.3	Periodic condition	29
3.2.4	Transmission condition	31
3.2.5	Average condition	33
3.3	Eigenvalues and eigenvectors of Laplace operator	34
3.4	Discontinuous Galerkin method for 2D Dirichlet problem	35
3.5	Mixed formulation	37
3.5.1	Laplace problem using P0 and Raviart-Thomas elements	37
3.5.2	2D Stokes problem	39
3.6	Fictitious domain method	41
3.7	Maxwell equations using Nedelec elements	43

3.7.1	2D Maxwell equations	43
3.7.2	3D Maxwell equations	45
3.7.3	3D Maxwell equations in a half waveguide using PML	48
3.8	3D Helmholtz problem using single layer potential integral equation	51
3.9	2D Helmholtz problem coupling FEM and integral representation	53
3.10	2D Helmholtz problem coupling FEM and BEM	56
3.11	3D Maxwell problem using EFIE	60
3.12	2D Elasticity problem	63
3.13	2D Bilaplacian problem	64
3.14	Solving wave equation	66
4	XLiFE++ written in C++	69
4.1	Instruction sequence	69
4.2	Variables	69
4.3	Basic operations	70
4.4	if, switch, for and while	70
4.5	In/out operations	72
4.6	Using standard functions	73
4.7	Use of classes	73
4.8	Understanding memory usage	74
4.9	Main user's classes of XLiFE++	74
5	Initialization and global variables	76
5.1	The init function	76
5.2	Managing your own options	76
5.3	Using XLiFE++ with global parameters	77
5.3.1	Global constants and objects	77
5.3.2	Multi-threading	78
5.3.3	The verbosity	78
6	Mesh definition	79
6.1	Defining geometries	79
6.1.1	Segments	81
6.1.2	Elliptic and circular arcs	82
6.1.3	Parametrized arcs	84
6.1.4	Spline arcs	85
6.1.5	Polygons and polygon-likes	88
6.1.6	Ellipses and disks	92
6.1.7	Parametrized surface	95
6.1.8	Spline surface	97
6.1.9	Polyhedra and polyhedron-likes	98
6.1.10	Ellipsoids and balls	105
6.1.11	Trunks and trunk-likes	109
6.1.12	Definition of a geometry from its boundary	118
6.1.13	Combining geometries	120
6.2	Transformations on geometries	122
6.2.1	Canonical transformations	122
6.2.2	Composition of transformations	125
6.2.3	Applying transformations	125
6.3	Extrusion of geometries	127
6.3.1	How to apply an extrusion ?	127
6.3.2	How to define names of lateral domains of an extrusion ?	129

6.3.3	Example: definition of a conesphere	129
6.4	Defining a mesh from a geometry	130
6.4.1	Structured internal meshing tools: structured generator	132
6.4.2	Unstructured internal meshing tools: subdivision generator	134
6.4.3	Meshing tool with nested call to GMSH: gmsh generator	146
6.5	Open Cascade extension	150
6.6	Extrude a mesh	153
6.7	Split mesh element	155
6.8	Loading a mesh from a file	155
6.9	Transformations on meshes	156
6.10	Using geometrical domain	157
6.10.1	Retrieving domains	158
6.10.2	Dealing with normals of a domain	158
6.10.3	Map of domains	160
6.10.4	Assign properties to domains	161
6.10.5	Create domain of sides	161
6.10.6	Set operation on domain	162
6.10.7	Cracking a domain	162
6.10.8	Having statistics about the mesh quality of a domain	165
6.10.9	Summary of domain operations	166
6.11	Dealing with parametrizations of geometrical domains	166
6.12	A full example with periodic cavities	167
7	Defining the problem	169
7.1	Domains, spaces, unknowns and test functions	169
7.1.1	Domains and finite element spaces	169
7.1.2	Spectral spaces	171
7.1.3	Unknowns and test functions	173
7.1.4	Dealing with collections	174
7.2	Forms	174
7.2.1	Operators on unknowns	175
7.2.2	Operators on kernel	177
7.2.3	Available standard kernels	178
7.2.4	Tensor kernel	178
7.2.5	Interpolated function in operator	179
7.2.6	Additional operation in operator	179
7.2.7	Integration method	181
7.2.8	Integral calculation tools	186
7.2.9	Define bilinear form involving unknowns on different meshes	188
7.2.10	Dealing with non-standard bilinear form - advanced usage -	189
7.3	Essential conditions	190
8	Solving the problem	193
8.1	Algebraic representation	193
8.1.1	Representing linear and bilinear forms	193
8.1.2	Dealing with essential conditions	195
8.1.3	Delay computation	196
8.1.4	TermVector in details	196
8.1.5	TermMatrix in details	203
8.1.6	HMatrix	207
8.1.7	Projector	212
8.2	Linear Solvers	215

8.2.1	Direct solvers	216
8.2.2	Iterative solvers	217
8.3	Eigen solvers	220
8.3.1	How to call an eigen solver ?	220
8.3.2	Results	221
8.3.3	Calling sequence	222
8.3.4	Advanced usage of ARPACK	230
9	Post-processing and outputs	239
9.1	Integral representation	239
9.1.1	Direct method	239
9.1.2	Matrix method	240
9.1.3	Kernel interpolation method	241
9.2	Output functions	242
9.2.1	Print objects	242
9.2.2	Export TermMatrix and TermVector	242
9.3	Graphical exploitation	244
A	External libraries	249
A.1	How to install BLAS and LAPACK libraries	249
A.2	How to install UMFPACK library	249
A.3	How to install ARPACK library	250
A.4	How to install MinGW 64 bits on WINDOWS	250
B	Utility types in details	251
B.1	String, Strings	251
B.2	Int, Dimen, Number, Numbers	252
B.3	Real, Complex and Reals	252
B.4	Angle unit	253
B.5	Point	253
B.6	Vector	255
B.7	Matrix	257
B.8	Parameters	259
B.8.1	The Parameter object	259
B.8.2	The Parameters object: list of Parameter	260
B.9	Function	261
B.9.1	User function and object function	261
B.9.2	Advanced user	266
B.10	Kernel	267
B.10.1	User kernels	267
B.10.2	Dealing with normal vectors	271
B.10.3	Tensor kernel	271
B.11	Tabular	273
B.12	SymbolicFunction	274
B.13	Parametrization	275
B.14	Splines	278
B.14.1	C2 spline	278
B.14.2	Catmull-Rom spline	280
B.14.3	Bézier curve	282
B.14.4	B-Spline	284
B.14.5	Spline surface (nurbs)	287
B.15	Timer	289

B.16 Memory	289
B.17 Mathematical resources	290
B.17.1 Random generators	290
B.17.2 Gauss formulae	291
B.17.3 Exact solutions	291
B.17.4 Special functions	292
B.17.5 Computation of polynomial roots	294
B.17.6 Basic quadrature methods and FFT	294
B.17.7 ODE solvers	295
C CMAKE tutorial	298
C.1 On the command line	298
C.2 Through GUI applications	298
C.3 CMAKE options and cache entries	299
C.3.1 On the command line	299
C.3.2 Through GUI applications	299



Preface

XLIFE++ is the heir of 2 main finite elements library developed in POEMS laboratory, namely MELINA (and its C++ avatar MELINA++) and MONTJOIE, respectively developed since 1989 and 2003. It is a C++ high level library devoted to extended finite elements methods. Writing programs using XLIFE++ needs only basic knowledge of C++ language, so that it can be used to teach finite elements methods, but it is quite perfect for research activities.

XLIFE++ is self-consistent. It provides advanced mesh tools, with refinement methods, has every kind of elements (including pyramids) needed by finite elements methods, boundary elements methods or discontinuous galerkin methods, direct/iterative solvers and eigen solvers. Next to this, it provides also a wide range of interfaces to well-known libraries or software programs, such that UMFPACK, ARPACK++, and an advanced interface to the mesh generator GMSH, so that you can do everything needed in a single program.

This documentation is dedicated to students at Master level, to engineers and researchers at any level, in so far as partial differential equations are concerned.

1.1 What XLIfe++ is

Partial differential equations (PDE hereafter) are the core of modeling. A wide range of problems in Physics, Mechanics, Engineering, Mathematics, Health, Finance are modeled by PDEs.

XLIfe++ is a C++ library designed to solve these equations numerically. It is a free extended library based on finite elements methods. It is an autonomous library, providing everything you need for solving such problems, including interfaces to specific external libraries or softwares, such as GMSH, ARPACK++, UMFPACK, ...

What does XLIfe++ do ?

- Problem description (real or complex, scalar or vector) by their variational formulations, with full access to the internal vectors or matrices;
- Multi-variables, multi-equations, 1D, 2D and 3D, linear or non linear coupled systems;
- Easy geometric input by composite description , to build meshes thanks to GMSH;
- Easy automatic mesh generation on elementary geometries, based on refinement methods;
- Very high level user-friendly typed input language with full algebra of analytic and finite elements functions. Your main program will be very similar to the mathematical formulation;
- A wide range of finite elements : segments, triangles, quadrangles, hexahedra, tetrahedra, prisms and pyramids
- A wide set of internal linear direct and iterative solvers (LU, Cholesky, BiCG, BiCGStab, CG, CGS, GMRES, QMR, SOR, SSOR, ...) and internal eigenvalues and eigenvectors solvers, plus additional interfaces to external solvers (ARPACK, UMFPACK,...);
- A full documentation suite : source documentation (online or inside sources), user documentation (PDF), developer documentation (PDF);
- A parallel version using OpenMP.

1.2 How to download XLIfe++

XLIfe++ is downloadable at the following url <http://uma.ensta-paris.fr/soft/XLIfe++/>. You can download releases and snapshots of either the source code or binaries. Snapshots are supposed to be generated automatically very often.

There are 2 kinds of archives (snapshots or releases):

1. a "source" archive that contains all XLIfe++ source files and tex/PDF documentation;
2. a "api" archive that contains only source documentation generated by DOXYGEN

1.2.1 How XLiFE++ sources are organized

XLiFE++ sources are organized with several directories, described as follows for the main ones:

- bin** contains the `xlifepp_project_setup.exe` for Windows and the user scripts `xlifepp.sh` and `xlifepp.bat`. This will be explained later.
- doc** contains the present user guide, the developer guide (also in PDF) and other specific documentations extracted from the present user guide, such as a tutorial, an install documentation, and explanations about examples.
- etc** contains a lot of stuff such as templates for installation, the multilingual files, ...
- examples** contains example files ready to compile and use.
- ext** contains source files for external dependencies, such as ARPACK++, EIGEN, AMOS libraries
- src** contains all C++ sources of the XLiFE++ library
- tests** contains all unitary and system tests to check your installation
- lib** will contain the static libraries of XLiFE++, after the compilation step.
- usr** contains the user files to write and compile a C++ program using XLiFE++

You also have a very important file `CMakeLists.txt`, that is the CMAKE compilation script.

1.2.2 How XLiFE++ binaries are organized

XLiFE++ binaries are organized with several directories, described as follows for the main ones:

- bin** contains the `xlifepp_project_setup.exe` for Windows and the user scripts `xlifepp.sh` and `xlifepp.bat`. This will be explained later.
- etc** contains a lot of stuff such as templates for installation, the multilingual files, ...
- share/doc** contains the present user guide, the developer guide (also in PDF) and other specific documentations extracted from the present user guide, such as a tutorial, an install documentation, and explanations about examples.
- share/examples** contains example files ready to compile and use.
- ext** contains source files for external dependencies, such as ARPACK++, EIGEN, AMOS libraries
- tests** contains all unitary and system tests to check your installation
- lib** contains the static libraries of XLiFE++.

You also have a very important file `CMakeLists.txt`, that is the CMAKE compilation script.

1.3 Requirements

1.3.1 Extensions

To use XLiFE++ full capabilities, you may need some external libraries to activate extensions:

- The main mesh engine needs GMSH (<http://gmsh.info>). It is not a strong dependency insofar as you just have to tell XLiFE++ where GMSH binary is.
- To use it as eigen solver, XLiFE++ provides its own ARPACK distribution (<http://www.caam.rice.edu/software/ARPACK/>). This internal distribution is patched to work with recent compilers, but you may prefer using another distribution. See section A.3 for details and recommendations.

- To use it as direct solver, you may install UMFPACK (<http://faculty.cse.tamu.edu/davis/suitesparse.html>). See section A.2 for details and recommendations.
- To use it as GPU solver, you may install MAGMA (<http://icl.cs.utk.edu/magma/>).
- To visualize solutions of your programs using XLIFE++, you may install GMSH (<http://geuz.org/gmsh>), PARAVIEW (<http://www.paraview.org>), MATLAB (<https://fr.mathworks.com>) or OCTAVE (<https://sourceforge.net/projects/octave/files/>).



XLIFE++ provides 2 external libraries: EIGEN (<http://eigen.tuxfamily.org/>, essentially for SVD, and AMOS (<http://www.netlib.org/amos/>) for Bessel/Hankel functions with complex arguments.

1.3.2 Installation requirements

Basically, XLIFE++ compilation depends on the cross-platform builder CMAKE, available at <http://cmake.org>. To know how to install and use XLIFE++ this way, please read section 1.4.

For UNIX systems, you can use an alternative installation procedure that does not require CMAKE. To know how to install and use XLIFE++ this way, please read section 1.5.

Another way to install XLIFE++ is to download a DOCKER container (like a virtual machine containing everything to build and run XLIFE++). It is cross-platform. To know how to install and use XLIFE++ this way, please read section 1.6.

Of course, you need a C++ compiler. To install a proper 64bits compiler on WINDOWS, see section A.4.

1.4 Main installation and usage process, with CMAKE

You download XLIFE++ from its website <http://uma.ensta-paris.fr/soft/XLiFE++/>.

- Either you download XLIFE++ sources: you have to unzip the archive at any place you choose in the filesystem. Then, you follow configuration procedure by setting at least a C++ compiler, paths to GMSH and PARAVIEW and eventually paths to external libraries BLAS, LAPACK, ARPACK and UMFPACK. When done, you will have to compile XLIFE++ source code.
- Or you download XLIFE++ binaries: you will have to run the installer if you are on WINDOWS (see section 1.4.4), or follow the configuration procedure with cmake by setting a C++ compiler, paths to GMSH and PARAVIEW, and eventually paths to external libraries BLAS, LAPACK, ARPACK and UMFPACK libraries. In following sections, you will be guided on which options you may use or not as far as sources or binaries are concerned.



If you want to use clang++ as a compiler, please download dedicated clang++ binaries, as they are necessarily generated without OPENMP activated.



If you need to learn how to use cmake, please go to Appendix C. Keep in mind that running CMAKE several times is not a problem. Indeed, as far as external dependencies are concerned, CMAKE is supposed to find a wide range of possible configurations, but not every time of course!

1.4.1 Configuration step



In the following, we will consider CMAKE used in command-line mode, from a build directory directly inside sources so that the path to CMakeLists.txt file is ..
Cache entries that will be explained can be set directly through GUI applications.

The default build configuration is to use EIGEN and AMOS libraries, as they are provided directly by XLIFE++, and multi-threading with OPENMP, if the compiler is compatible with it (for instance, clang++ on MAC OS is not).

```
cmake ..
```

As explained in Appendix C, you can specify a generator with option -G, namely the native makefile or the IDE file you want. The default generator is "Unix Makefiles" on LINUX and MAC OS computers, and "MinGW Makefiles" on WINDOWS, but it can have a wide range of possible values. To know what you can do, please consult CMAKE help. For instance, if you want to generate a CodeBlocks project on LINUX computer, you may choose *Codeblocks - Unix Makefiles*

```
cmake .. [-G <generator_name>]
```

In the following, we will focus on cache entries you may have to set.



When CMAKE is running, it stores values of cache entries in a cache file CMakeCache.txt in the *build directory*. As a result, when you run again CMAKE, you are not forced to give already given options.

1.4.2 How to set compilers

By default, CMAKE consider each directory defined in your paths environment variables to find compilers, and select the first compiler found. Nevertheless, you may select another compiler. To do so, you need 2 CMAKE cache entries:

CMAKE_CXX_COMPILER to set the C++ compiler

CMAKE_Fortran_COMPILER to set the Fortran compiler (necessary to AMOS compilation, and eventually to ARPACK compilation if you choose provided source distribution). Please notice the spelling, as CMAKE is case-sensitive !!

```
cmake .. -DCMAKE_CXX_COMPILER=g++-7 -DCMAKE_Fortran_COMPILER=gfortran-7 [other_options]
```

If you want to configure XLIFE++ in Debug mode (or another one, you may use the following entry :

CMAKE_BUILD_TYPE Default value is "Release". Other possible values are "Debug", "RelWithDebInfo", ...

```
cmake .. -DCMAKE_CXX_COMPILER=g++-7 -DCMAKE_Fortran_COMPILER=gfortran-7 -DCMAKE_BUILD_TYPE=Debug  
[other_options]
```

When you look at the CMAKE log, you are supposed to read that the rightful compiler is used with the rightful build type, and that activated dependencies are found and used and that deactivated dependencies are not used.

1.4.3 How to set external dependencies



In the following, [general_entries] refers to options introduced in subsection 1.4.2

To activate all dependencies, you can type the following:

```
cmake .. [general_entries] -DXLIFEPP_DEPS=ENABLE_ALL
```

XLIFEPP_DEPS Default value is "DEFAULT". Other possible values are "ENABLE_ALL" or "DISABLE_ALL".



For XLIFE++ binaries, this option is used to generate them, so you don't have to use it.



When you use CMAKE GUI application, option **XLIFEPP_DEPS** is useless, as the list of specific options discussed in the following warning are displayed as checkboxes.

For every external dependency, CMAKE searches files in standard environment paths and in specific paths defined in CMAKE configuration script. So if external dependencies are installed by package managers, CMAKE will find them.

If it is not the case, or if the library found is not the one you want to use, you can tell CMAKE where to find them, as we will see in the following.



If you don't want to activate every external dependency, but only some of them, you may use a subset of the following options (default behavior in bold):

XLIFEPP_ENABLE_ARPACK To enable/disable use of ARPACK. Possible values are ON or **OFF**.

XLIFEPP_ENABLE_UMFPACK To enable/disable use of UMFPACK. Possible values are ON or **OFF**.

XLIFEPP_ENABLE_AMOS To enable/disable use of AMOS. Possible values are **ON** or OFF.

XLIFEPP_ENABLE_OMP To enable/disable use of OPENMP. Possible values are **ON** or OFF.

XLIFEPP_ENABLE_EIGEN To enable/disable use of EIGEN. Possible values are ON or OFF. Default is the same as **XLIFEPP_ENABLE_OMP**, as EIGEN needs OPENMP.

XLIFEPP_ENABLE_MAGMA To enable/disable use of MAGMA. Possible values are ON or **OFF**.

Configuring paths to GMSH and PARAVIEW executables



In the following, [general_entries] refers to options introduced in subsection 1.4.2 and [deps_entries] refers to other options introduced since subsection 1.4.3

To set the full path to GMSH executable, you can type the following:

```
cmake .. [general_entries] [deps_entries] -DXLIFEPP_GMSH_EXECUTABLE=path/to/gmsh/executable
```

To set the full path to PARAVIEW executable, you can type the following:

```
cmake .. [general_entries] [deps_entries]
-DXLIFEPP_PARAVIEW_EXECUTABLE=path/to/paraview/executable
```



You have to set the full path to GMSH/PARAVIEW executables and not applications. Executables are inside applications. If application names are Gmsh.app and paraview.app and are located in the *Applications* directory, GMSH and PARAVIEW will be correctly detected.

Configuring dependency on BLAS and LAPACK libraries



In the following, [general_entries] refers to options introduced in subsection 1.4.2 and [deps_entries] refers to others options introduced since subsection 1.4.3

To tell to CMAKE where to find BLAS library, you just have to set the directory containing the BLAS library, with the option **XLIFEPP_BLAS_LIB_DIR**:

```
cmake .. [general_entries] [deps_entries] -DXLIFEPP_BLAS_LIB_DIR=path/to/blas/library/directory
```

To tell to CMAKE where to find LAPACK library, you just have to set the directory containing the LAPACK library, with the option **XLIFEPP_LAPACK_LIB_DIR**:

```
cmake .. [general_entries] [deps_entries]
-DXLIFEPP_LAPACK_LIB_DIR=path/to/lapack/library/directory
```



Setting the directory is sufficient only if the BLAS library name is standard, such as libblas.a, libblas.so, libblas.dylib, libblas.dll, blas.lib, ... (the same goes for LAPACK) If it is not the case, it means that BLAS/LAPACK is not installed properly (for instance with a version number as a suffix). Prefer using options **XLIFEPP_BLAS_LIB** and **XLIFEPP_LAPACK_LIB** instead, to set the full path to BLAS and LAPACK libraries



If you downloaded binary libraries provided by the XLIFE++ website, as recommended in subsection 1.3.1, it will be something like (if you downloaded 64bits binaries):

```
cmake .. [general_entries] [deps_entries] -DXLIFEPP_BLAS_LIB_DIR="C:/\ldots/lapack-3.5.0_64"
-DXLIFEPP_LAPACK_LIB_DIR="C:/\ldots/lapack-3.5.0_64"
```



When using clang++, you have to set the path to FORTRAN library, as clang++ is not able to find it by itself (contrary to gcc, as gcc and FORTRAN library are in the same distribution). To do so, you just have to use the option **XLIFEPP_FORTRAN_LIB_DIR**:

```
cmake .. [general_entries] [deps_entries]
-DXLIFEPP_FORTRAN_LIB_DIR=path/to/gfortran/library/directory
```



Setting the directory is sufficient only if the FORTRAN library name is standard, such as libgfortran.a, libgfortran.so, libgfortran.dylib, libgfortran.dll, gfortran.lib, ... If it is not the case, it means that FORTRAN is not installed properly (for instance with a version number as a suffix). Prefer using option **XLIFEPP_FORTRAN_LIB** instead, to set the full path to FORTRAN library

Configuring dependency on ARPACK library



In the following, [general_entries] refers to options introduced in subsection 1.4.2 and [deps_entries] refers to others options introduced since subsection 1.4.3

First of all, you have to choose if you want to use the internal ARPACK distribution of XLIFE++, or an external one. Of course, the one provided by XLIFE++ is detected automatically. To select the rightful mode, you have to set the option:

XLIFEPP_SYSTEM_ARPACK To choose an external distribution of ARPACK or the one provided by XLIFE++. Possible values are ON or OFF. Default is OFF, to use the distribution provided by XLIFE++

If you choose to use an external distribution of ARPACK, you now have to tell CMAKE where to find ARPACK library. To do so, you just have to set the directory containing the ARPACK library, with the option **XLIFEPP_ARPACK_LIB_DIR**:

```
cmake .. [general_entries] [deps_entries] -DXLIFEPP_BLAS_LIB_DIR=path/to/blas/library/directory
```



Setting the directory is sufficient only if the ARPACK library name is standard, such as libarpack.a, libarpack.so, libarpack.dylib, libarpack.dll, arpack.lib, ... If it is not the case, it means that ARPACK is not installed properly (for instance with a version number as a suffix). Prefer using option **XLIFEPP_ARPACK_LIB** instead, to set the full path to ARPACK library



If you downloaded binary libraries provided by the XLIFE++ website, as recommended in subsection 1.3.1, it will be something like (if you downloaded 64bits binaries):

```
cmake .. [general_entries] [deps_entries]
-DXLIFEPP_ARPACK_LIB_DIR="C:/\ldots/ARPACK_64/lib_mingw64"
```



When using clang++, you have to set the path to FORTRAN library, as clang++ is not able to find it by itself (contrary to gcc, as gcc and FORTRAN library are in the same distribution). To do so, you just have to use the option **XLIFEPP_FORTRAN_LIB_DIR**:

```
cmake .. [general_entries] [deps_entries]
-DXLIFEPP_FORTRAN_LIB_DIR=path/to/gfortran/library/directory
```



Setting the directory is sufficient only if the FORTRAN library name is standard, such as libgfortran.a, libgfortran.so, libgfortran.dylib, libgfortran.dll, gfortran.lib, ... If it is not the case, it means that FORTRAN is not installed properly (for instance with a version number as a suffix). Prefer using option **XLIFEPP_FORTRAN_LIB** instead, to set the full path to FORTRAN library

Configuring dependency on SUITESPARSE/ UMFPACK libraries



In the following, [general_entries] refers to options introduced in subsection 1.4.2 and [deps_entries] refers to others options introduced since subsection 1.4.3

UMFPACK is a part of SUITESPARSE distribution (that also contains amd, colamd, camd, ccolamd, cholmod, metis, and suitesparseconfig, ...).

To tell to CMAKE where to find UMFPACK library/SUITESPARSE distribution, you just have to set the home directory containing the SUITESPARSE distribution, with the option

XLIFEPP_SUITESPARSE_HOME_DIR:

```
cmake .. [general_entries] [deps_entries]
-DXLIFEPP_SUITESPARSE_HOME_DIR=path/to/suitesparse/home/directory
```



If you downloaded binary libraries provided by the XLIFE++ website, as recommended in subsection 1.3.1, it will be something like (if you downloaded 64bits binaries):

```
cmake .. [general_entries] [deps_entries]
-DXLIFEPP_SUITESPARSE_HOME_DIR="C:/\ldots/SuiteSparse_64"
```



When using `clang++`, you have to set the path to FORTRAN library, as `clang++` is not able to find it by itself (contrary to `gcc`, as `gcc` and FORTRAN library are in the same distribution). To do so, you just have to use the option **`XLIFEPP_FORTRAN_LIB_DIR`**:

```
cmake .. [general_entries] [deps_entries]
-DXLIFEPP_FORTRAN_LIB_DIR=path/to/gfortran/library/directory
```



Setting the directory is sufficient only if the FORTRAN library name is standard, such as `libgfortran.a`, `libgfortran.so`, `libgfortran.dylib`, `libgfortran.dll`, `gfortran.lib`, ... If it is not the case, it means that FORTRAN is not installed properly (for instance with a version number as a suffix). Prefer using option **`XLIFEPP_FORTRAN_LIB`** instead, to set the full path to FORTRAN library



If setting **`XLIFEPP_SUITESPARSE_HOME_DIR`** is not enough to find every library of SUITESPARSE distribution, you can use specific options of the form:

`XLIFEPP_XXX_INCLUDE_DIR` to specify the XXX header, where XXX can be AMD, COLAMD, CAMD, CCOLAMD, CHOLMOD, METIS, SUITESPARSECONFIG or UMFPACK.

`XLIFEPP_XXX_LIB_DIR` to specify the XXX library, where XXX can be AMD, COLAMD, CAMD, CCOLAMD, CHOLMOD, METIS, SUITESPARSE (only on MAC OS), SUITESPARSECONFIG or UMFPACK.

Setting the directories is sufficient only if the SUITESPARSE library names are standard, such as `libamd.a`, `libamd.so`, `libamd.dylib`, `libamd.dll`, `amd.lib`, ... (the same goes for the other libraries) If it is not the case, it means that SUITESPARSE is not installed properly (for instance with a version number as a suffix). Prefer using option **`XLIFEPP_XXX_LIB`** instead, to set the full path to SUITESPARSE libraries, where XXX can be AMD, COLAMD, CAMD, CCOLAMD, CHOLMOD, METIS, SUITESPARSE (only on MAC OS), SUITESPARSECONFIG or UMFPACK.

Configuring dependency on MAGMA library



In the following, `[general_entries]` refers to options introduced in subsection 1.4.2 and `[deps_entries]` refers to others options introduced since subsection 1.4.3

To tell to CMAKE where to find MAGMA library, you just have to set the directory containing the MAGMA library, with the option **`XLIFEPP_MAGMA_LIB_DIR`** and the directory containing the MAGMA header files, with the option **`XLIFEPP_MAGMA_INCLUDE_DIR`**:

```
cmake .. [general_entries] [deps_entries] -DXLIFEPP_MAGMA_LIB_DIR=path/to/magma/library/directory
-DXLIFEPP_MAGMA_INCLUDE_DIR=path/to/magma/include/directory
```

1.4.4 Installing binaries

LINUX

XLiFE++ provides packages for Debian/Ubuntu (.deb) and Fedora (.rpm).

For Debian/Ubuntu/Mint, you just have to run the following command:

```
sudo dpkg -i xlifepp-binaries-...-64bits.deb
```

For Red Hat/OpenSUSE/Fedora, you just have to run the following command:

```
sudo rpm -i xlifepp-binaries-...-64bits.rpm
```

When the install process is done, you just have to add `/usr/local/xlifepp/bin` in your PATH.

MAC OS

XLiFE++ provides a .dmg file, that works like an archive of the XLiFE++ binaries. So you have to open the .dmg file, then you copy the whole content where you want to copy it, let's say `xlifepp_dir`. Then, you have to run CMAKE on `xlifepp_dir` and configure every dependency as explained in subsection 1.4.3.


When the install process is done, you just have to add `xlifepp_dir/bin` in your PATH.

WINDOWS


When downloading binaries under WINDOWS, you just have to run the installer. To do so, administrator elevation is required. If a previous distribution of XLiFE++ is installed in the folder you choose, the installer can remove it itself. Furthermore, it is highly recommended to install every component.

Now, in the bin subdirectory of the XLiFE++ install directory, you will find `xlifepp_configure.exe`. To run it, administrator elevation is required.

1. First, you have to set the folder containing XLiFE++.



2. As mentioned in the banner, a C++ compiler, CMAKE and GMSH have to be installed on your computer and defined in the WINDOWS PATH¹ system environment variable. An EDI such as CODEBLOCKS and PARAVIEW are not mandatory but highly recommended. Click on the Configure button.



3. When everything is OK, message "Configuration complete" is displayed. To compile your own program, you can click on the New project button or run `xlifepp_new_project.exe`. See section 1.4.5

1.4.5 Compilation of a program using XLiFE++

The manual way

This way supposes that you know where XLiFE++ is installed.

¹A simple tool to edit the window path is WINDOWS PATH EDITOR (<https://rix0rrr.github.io/WindowsPathEditor/>) if you have an older version of WINDOWS

1. You create your working directory,
2. You copy the main.cpp file into your working directory,
3. You copy the CMakeLists.txt file from the build directory (the directory in which you ran installation process) into your working directory,
4. You run CMAKE on the CMakeLists.txt file to get your makefile or files for your IDE project (Eclipse, XCode, CodeBlocks, Visual C++, ...),
5. You can now edit the main.cpp file to write your program and enjoy compilation with XLiFE++.

The command-line way

This way is possible to make easier the manual way. In the bin directory of XLiFE++, you have shell script called `xlifepp.sh` for macOS and Linux, and a batch script called `xlifepp.bat`. You can define a shortcut on it wherever you want.

Here is the list of options of both scripts:

USAGE:

```
xlifepp.sh --build [--interactive] [(--generate|--no-generate)]
xlifepp.sh --build --non-interactive [(--generate|--no-generate)]
                                [--compiler <compiler>] [--directory <dir>]
                                [--generator-name <generator>]
                                [--build-type <build-type>]
                                [(--with-omp|--without-omp)]

xlifepp.sh --help
xlifepp.sh --version
```

MAIN OPTIONS:

<code>--build, -b</code>	copy cmake files and eventually sample of main file and run cmake on it to prepare your so-called project directory. This is the default
<code>--generate, -g</code>	generate the project. Used with <code>--build</code> option. This is the default.
<code>--help, -help, -h</code>	show the current help
<code>--interactive, -i</code>	run xlifepp in interactive mode. Used with <code>--build</code> option. This is the default
<code>--non-interactive, -noi</code>	run xlifepp in non interactive mode. Used with <code>--build</code> option
<code>--no-generate, -nog</code>	prevent generation of your project. You will do it yourself.
<code>--version, -v</code>	print version number of XLiFE++ and its date
<code>--verbose-level <value>, -vl <value></code>	set the verbose level. Default value is 1

OPTIONS FOR BUILD IN NON INTERACTIVE MODE:

<code>--build-type <value>, -bt <value></code>	set cmake build type (Debug, Release, \ldots).
<code>--cxx-compiler <value>, -cxx <value></code>	set the C++ compiler to use.
<code>--directory <dir></code>	set the directory where you want to build

```

-d <dir>                your project
--generator-name <name>, set the cmake generator.
-gn <name>
-f <filename>,          copy <filename> as a main file for the user
--main-file <filename>  project.
-nof,                  do not copy the sample main.cpp file. This is
--no-main-file          the default.
--info-dir, -id         set the directory where the info.txt file is
--with-omp, -omp         activates OpenMP mode
--without-omp, -nomp     deactivates OpenMP mode

```

The graphical way on MAC OS

This way is possible to make easier the manual way and more pleasant than the command-line way. On the website, you have a GUI application called **xlifcpp-qt** for macOS, (Windows and Linux will come soon). You can define a shortcut on it wherever you want.




Figure 1.1: The "Configuration" tab of xlifepp-qt application





Figure 1.2: The "Use" tab of xlifepp-qt application


This application is a graphical user interface to the first 3 steps of the manual way.

The graphical way on WINDOWS


1. You run the generator `xlifcpp_new_project.exe` located in the bin subdirectory of the XLiFE++ install directory. The XLiFE++ folder should be correct but you can fix it if necessary.



2. You select the folder in which you will write your program using XLIfe++. If it already exists, the generator asks you to clean it or not. This window gives some information about XLIfe++: the compiler used to generate it, if the library supports omp and the debug/release status. You should use a compatible compiler with this library. If the default C++ compiler found on your computer is not compatible, you can select another one by clicking on the use compiler folder button.



3. Select the type of your project. For the moment only CodeBlocks-MinGW and Makefile are working but CODEBLOCKS is highly recommended! Select a main file from the proposed list. This main fill will be copied in your application folder. Be care, if you choose "none", no main file will be copied and the generator will fail if there is no main file in your application folder. This option is only useful if you want to keep an existing main file in your application folder! Click on the Generate button and wait:



4. When everything is complete, you can either exit the tool or run the program that opens the generated project (CODEBLOCKS in the example) by clicking on the run button.

1.4.6 Example

Here follows an example showing how to install and use XLIfe++ with command line tools described in the previous sections. The character ~ denotes the home directory of the user. The commands are numbered

starting from 1 ; each number is preceded by the name of the current working directory.

We first decompress the archive in a new directory (renamed xlifepp), create a build directory and launch the creation of the libraries:

```
~ (1) tar xf ~/Downloads/xlifepp-sources-v2.0.1-2018-05-09.tbz
~ (2) mv xlifepp-sources-v2.0.1-2018-05-09 xlifepp
~ (3) cd ~/xlifepp
~/xlifepp (4) mkdir build
~/xlifepp (5) cd build
~/xlifepp/build (6) cmake .. -DXLIFEPP_ENABLE_ARPACK=ON -DXLIFEPP_ENABLE_UMFPACK=ON
-- The CXX compiler identification is AppleClang 9.1.0.9020039
.
. (text intentionally removed)
.
-- Build files have been written to: ~/xlifepp/build
~/xlifepp/build (7) make libs
Scanning dependencies of target xlifepp_form
[ 0%] Building CXX object CMakeFiles/xlifepp_form.dir/src/form/BilinearForm.cpp.o
.
. (text intentionally removed)
.
[100%] Built target libs
~/xlifepp/build (8)
```

Now, we can create an executable file. To do that, we choose to create a test directory and to compile one of the examples present in this documentation:

```
~/xlifepp/build (8) mkdir /tmp/test
~/xlifepp/build (9) cd /tmp/test
/tmp/test (10) ~/xlifepp/bin/xlifepp.sh
*****
*           xlifepp           *
*****
Project directory (default is current directory):

/tmp/test exists
The following generators are available on this platform:
1 -> Unix Makefiles
2 -> Ninja
3 -> Xcode
4 -> CodeBlocks - Ninja
5 -> CodeBlocks - Unix Makefiles
6 -> CodeLite - Ninja
7 -> CodeLite - Unix Makefiles
8 -> Sublime Text 2 - Ninja
9 -> Sublime Text 2 - Unix Makefiles
10 -> Kate - Ninja
11 -> Kate - Unix Makefiles
12 -> Eclipse CDT4 - Ninja
13 -> Eclipse CDT4 - Unix Makefiles
14 -> KDevelop3
15 -> KDevelop3 - Unix Makefiles
Your choice (default is 1): 1
The following compilers are available:
1 -> clang++-4.2.1
The following main files are available:
1 -> main.cpp
```

```

2 -> elasticity2dP1.cpp
3 -> helmholtz2d-Dirichlet_single_layer.cpp
4 -> helmholtz2dP1-DtN_scalar.cpp
5 -> helmholtz2dP1-cg.cpp
6 -> helmholtz2d_FEM_BEM.cpp
7 -> helmholtz2d_FE_IR.cpp
8 -> helmholtz3d-Dirichlet_single_layer.cpp
9 -> laplace1dGL60-eigen.cpp
10 -> laplace1dP1.cpp
11 -> laplace1dP10Robin.cpp
12 -> laplace2dP0_RT1.cpp
13 -> laplace2dP1-average.cpp
14 -> laplace2dP1-dirichlet.cpp
15 -> laplace2dP1-periodic.cpp
16 -> laplace2dP1-Neumann.cpp
17 -> laplace2dP2-eigen.cpp
18 -> laplace2dP2-transmission.cpp
19 -> maxwell12dN1.cpp
20 -> maxwell13D_EFIE.cpp
21 -> wave_2d_leap-frog.cpp
Your choice (default is 1): 14
Copying laplace2dP1-dirichlet.cpp
Cleaning CMake build files
You can use:
1 -> sequential
The following build types are available
1 -> Release
Copying CMakeLists.txt
-- The CXX compiler identification is AppleClang 9.1.0.9020039
-- Check for working CXX compiler: /usr/bin/clang++
-- Check for working CXX compiler: /usr/bin/clang++ -- works
-- Detecting CXX compiler ABI info
-- Detecting CXX compiler ABI info - done
-- Detecting CXX compile features
-- Detecting CXX compile features - done
-- OpenMP is not used
-- XLiFE++ was compiled with clang++-4.2.1
-- XLiFE++ was compiled without OpenMP
-- XLiFE++ was compiled in Release mode
-- XLiFE++ libraries found !
-- Arpack is used
-- Umfpack is used
-- LAPACK is used
-- BLAS is used
-- AMOS is used
-- Magma is not used
-- Metis is not used
-- MPI is not used
-- Configuring done
-- Generating done
-- Build files have been written to: /tmp/test
/tmp/test (11) make
Scanning dependencies of target checklock
[ 0%] Built target checklock
Scanning dependencies of target exec-x86_64-darwin-clang++-4.2.1-Release
[ 50%] Building CXX object CMakeFiles/exec-x86_64-darwin-clang++-4.2.1-Release.dir/laplace2dP1-dirichlet.cpp.o
[100%] Linking CXX executable exec-x86_64-darwin-clang++-4.2.1-Release

```

```

\ \ / / / ( ) / _ _ \ _ _
\ / / / | | / \ / \ | | _ | |
/ \ / _ | / / // _ _ | _ _ |
/_ \ \ _ _ _ / \ / \ _ _ / | | | |

```

```

computing FE term intg_Omega grad(u) | grad(v), using 1 threads : done
reducing FE term A using pseudo reduction method
TermMatrix A computed, size 400 X 400 : SuTermMatrix A_u_v : block (v, u) -> matrix 400 X 400
of real scalar in symmetric_compressed sparse (csr,csc) (1521 coefficients)

```

The result file `U_LD_Omega.vtu` can then be displayed using `PARAVIEW`.

1.5.1 Installation process

- Download the archive (release or snapshot containing the sources) from <http://uma.ensta-paris.fr/soft/XLiFE++/?module=main&action=dl>
- Decompress the archive where the software is expected to be installed in the filesystem. This can be in the user's home or at system-wide level, in which case administrator rights will be necessary. Let's denote by `$XLDIR` the directory containing the files.
- Open a terminal and type in the command:

```
bash $XLDIR/etc/installLibs
```

This will create a single library in the `$XLDIR/lib` directory.

The installation requires a C++ compiler. The C++ compiler to use can be imposed by the mean of the environment variable `CPPCMP` before calling the script `installLibs` (see details in the file `$XLDIR/etc/installLibs.README`). By default, its name is `g++`, which is the GNU compiler generally used under Linux ; under MAC OS, this will make use of the native compiler shipped with Xcode, but the GNU compiler may be used as well.

The FORTRAN library is needed if ARPACK is used. Thus, the name of the Fortran compiler, from which is deduced the name of the Fortran library, can also be imposed by the mean of the environment variable FCMP. By default, its name is gfortran.

The installation process conforms to the following rules:

1. if they are not found in the filesystem, LAPACK and BLAS are not installed, neither any third party software,
2. UMFPACK and ARPACK libraries present on the system are used first and foremost,
3. if ARPACK has not been found in the system and if a FORTRAN compiler is available, the ARPACK library is built locally,
4. if UMFPACK has not been found in the system, SUITESPARSE libraries are built locally.

Some options may be used to alter the default configuration:

- noAmo prevents XLiFE++ to use AMOS library (computation of Bessel functions),
- noArp prevents XLiFE++ to use ARPACK library,
- noOmp prevents XLiFE++ to use OPENMP capabilities,
- noUmf prevents XLiFE++ to use UMFPACK (SUITESPARSE) libraries.

Thus, in case of trouble, the installation script may be relaunched with one or more of these options. Using all the options leads to the standalone installation of XLiFE++, which is perfectly allowed. The complete calling sequence is then:

```
bash $XLDIR/etc/installLibs [-noAmo] [-noArp] [-noOmp] [-noUmf]
```

Finally, the details of the installation are recorded in the file \$XLDIR/installLibs.log.

1.5.2 Compilation of a program using XLiFE++

To use XLiFE++:

1. Create a new directory to gather all the source files related to the problem to be solved.
2. In this directory, create the source files. This can be done with any text editor. One of them (only) should be a valid "XLiFE++ main file" (see section 1.7). For example, start by copying one of the files present in \$XLDIR/examples.

3. In a terminal, change to this directory and type in the command:

```
$XLDIR/etc/xlmake
```

This will compile all the C++ source files contained in the current working directory (valid extension are standard ones .c++, .cpp, .cc, .C, .cxx) and create the corresponding executable file, named xlifepexec.

4. Launch the execution of the program by typing in:

```
./xlifepexec
```

The files produced during the execution are created in the current directory.



To improve comfort, one can make a link to the script xlmake in the working directory, as suggested in the commentary inside the script:

```
ln -s $XLDIR/etc/xlmake .
```

or add \$XLDIR/etc to the PATH environment variable. In both cases, the command typed in at step 3. above would then reduce to:

```
xlmake
```



If OPENMP is used, it may be useful to adjust the number of threads to the problem size. Indeed, by default all threads available are used, which may be completely counter productive for example for a small problem size and a large number of threads. The number of threads to use can be modified at program level, generally in the main function, or at system level, by setting the environment variable OMP_NUM_THREADS before the execution is launched, e.g. with a Bourne shell:

```
export OMP_NUM_THREADS=2 ; ./xlifepexec
```

or with a C shell:

```
setenv OMP_NUM_THREADS 2 ; ./xlifepexec
```

1.6 Alternative installation and usage process, with DOCKER

This procedure allows to get a pre-installed version of the libraries which are gathered in a so-called DOCKER container.

This first requires the installation of the DOCKER application, which can be downloaded from:

<https://www.docker.com/products/overview>

Once this is done:

- Download the XLIFE++ image (use `sudo docker` on linux system):

```
docker pull pnavaro/xlifep
```

- Create a workspace directory, for example:

```
mkdir $HOME/my-xlifep-project
```

- Run the container with interactive mode and share the directory created above with the `/home/work` container directory:

```
docker run -it --rm -v $HOME/my-xlifep-project:/home/work pnavaro/xlifep
```

This allows the files created in the internal `/home/work` directory of the container to be stored in the `$HOME/my-xlifep-project` directory of the true filesystem, making them available after Docker is stopped.

- Everything is now ready to use XLIFE++ as explained in subsection 1.5.2 above, for example:

```
xlifep.sh
```

```
make
```

```
./exec-x86_64-linux-g++-5-Release
```

The files produced during the execution are in the directory `$HOME/my-xlifep-project` shared with running DOCKER, and are then available for postprocessing.



The DOCKER application requires WINDOWS 10, or MAC OS 10.10 and higher. For older OSes, you have to download DOCKER TOOLBOX instead. See https://docs.docker.com/toolbox/toolbox_install_windows/ for WINDOWS or https://docs.docker.com/toolbox/toolbox_install_mac/ for MAC OS.

1.7 Writing a program using XLIFE++

All the XLIFE++ library is defined in the namespace ***xlifcpp***. Then the users, if they refer to library objects, have to add once in their programs the command `using namespace xlifcpp;`. Besides, they have to use the "super" header file ***xlifcpp.h*** only in the main. A main program looks like, for instance:

```
#include "xlifcpp.h"
using namespace xlifcpp;

int main()
{
    init(_lang=en); // mandatory initialization of xlifcpp
    \ldots
}
```

Please see chapter 5 for a full description of command line options and of the `init` function and a full description of how to manage user options.



If the users have additional source files using XLIFE++ elements, they cannot include the "super" header file ***xlifcpp.h*** because of global variable definitions. Instead, they will include the "super" header file ***xlifcpp-libs.h*** that includes every XLIFE++ header except the one containing the definition of global variables.

1.8 License

XLIFE++ is copyright (C) 2010-2022 by E. Lunéville and N. Kielbasiewicz and is distributed under the terms of the GNU General Public License (GPL) (Version 3 or later, see <https://www.gnu.org/licenses/gpl-3.0.en.html>). This means that everyone is free to use XLIFE++ and to redistribute it on a free basis. XLIFE++ is not in the public domain; it is copyrighted and there are restrictions on its distribution. You cannot integrate XLIFE++ (in full or in parts) in any closed-source software you plan to distribute (commercially or not). If you want to integrate parts of XLIFE++ into a closed-source software, or want to sell a modified closed-source version of XLIFE++, you will need to obtain a different license. Please contact us directly for more information.

The developers do not assume any responsibility in the numerical results obtained using the XLIFE++ library and are not responsible of bugs.

1.9 Credits

The XLIFE++ library has been mainly developed by E. Lunéville and N. Kielbasiewicz of POEMS lab (UMR 7231, CNRS-ENSTA Paris-INRIA). Some parts are inherited from MELINA++ library developed by D. Martin (IRMAR lab, Rennes University, now retired) and E. Lunéville. Other contributors are :

- Y. Lafranche (IRMAR lab), mesh tools using subdivision algorithms, wrapper to ARPACK
- C. Chambeyron (POEMS lab), iterative solvers, unitary tests, PhD students' support
- M.H N'Guyen (POEMS lab), eigen solvers and OpenMP implementation
- N. Salles (POEMS lab), boundary element methods
- L. Pesudo (POEMS lab), boundary element methods and HF coupling
- P. Navaro (IRMAR lab), continuous integration
- E. Darrigrand-Lacarrieu (IRMAR lab), fast multipole methods

- E. Peillon (POEMS lab), evolution of (bi)linear forms

2.1 The variational approach

Before learning in details what XLIFE++ is able to do, let us explain the basics with an example, the **Helmholtz** equation:

For a given function $f(x, y)$, find a function $u(x, y)$ satisfying

$$\begin{cases} -\Delta u(x, y) + u(x, y) = f(x, y) & \forall (x, y) \in \Omega \\ \frac{\partial u}{\partial n}(x, y) = 0 & \forall (x, y) \in \partial\Omega \end{cases} \quad (2.1)$$

To solve this problem by a finite element method, XLIFE++ is based on its variational formulation: find $u \in H^1(\Omega)$ such that $\forall v \in H^1(\Omega)$

$$\int_{\Omega} \nabla u \cdot \nabla v \, dx \, dy - \int_{\Omega} u v \, dx \, dy = \int_{\Omega} f v \, dx \, dy. \quad (2.2)$$

All the mathematical objects involved in the variational formulation are described in XLIFE++. The following program solves the Helmholtz problem with $f(x, y) = \cos \pi x \cos \pi y$ and Ω is the unit square.

```

1 #include "xlife++.h"
2 using namespace xlifepp;
3
4 Real cosxcosy(const Point& P, Parameters& pa = defaultParameters)
5 {
6     Real x=P(1), y=P(2);
7     return cos(pi_ * x) * cos(pi_ * y);
8 }
9
10 int main(int argc, char** argv)
11 {
12     init(_lang=fr); // mandatory initialization of xlifepp
13     SquareGeo sq(_origin=Point(0.,0.), _length=1, _nnodes=11);
14     Mesh mesh2d(sq, triangle, 1, structured);
15     Domain omega = mesh2d.domain("Omega");
16     Space Vk(_domain=omega, _interpolation=P1, _name="Vk", _optimizeNumbering);
17     Unknown u(Vk, "u");
18     TestFunction v(u, "v");
19     BilinearForm auv = intg(omega, grad(u) | grad(v)) + intg(omega, u * v);
20     LinearForm fv=intg(omega, cosxcosy * v);
21     TermMatrix A(auv, "a(u,v)");
22     TermVector B(fv, "f(v)");
23     TermVector X0(u, omega, 1., "X0");
24     TermVector U = cgSolve(A, B, X0, _name="U");
25     saveToFile("U", U, vtU);
26     return 0;
27 }

```

Please notice how close to the Mathematics, XLIFE++ input language is.

2.2 How does it work ?

This first example shows how XLiFE++ executes all the usual steps required by the **Finite Element Method**. Let us walk through them one by one.

line 12: Every program using XLiFE++ begins by a call to the `init` function, taking up to 4 key/value arguments but only 2 are relevant for users:

`_verbose` integer to set the verbose level. Default value is 1.

`_lang` enum to set the language for print and log messages. Possible values are *en* for English, *fr* for French, *de* for German, or *es* for Spanish. Default value is *en*.

Furthermore, the `init` function loads functionalities linked to the trace of where such messages come from. If this function is not called, XLiFE++ cannot work !!!

```
init(_lang=fr); // mandatory initialization of xlifepp
```

See chapter 5 to learn how to define command line options or options files specific to your program and how to use them.

lines 13-14: The mesh will be generated on the unit square geometry with 11 nodes per edge. Arguments of a geometry are given with a key/value system. `_origin` is the bottom left front vertex of `SquareGeo`. Next, we specify the mesh element type (here triangle), the mesh element order (here 1), the mesh tool (here structured). The main mesh tools are 'structured' for simple geometries (rectangle, cube, ...) and 'gmsh' for general geometries. See chapter 6 for more examples of mesh definitions.

```
SquareGeo sq(_origin=Point(0.,0.), _length=1, _nnodes=11);
Mesh mesh2d(sq, triangle, 1, structured);
```

line 15: The main domain, named "Omega" in the mesh, is defined.

```
Domain omega = mesh2d.domain("Omega");
```

line 16: A finite element space is generally a space of polynomial functions on elements, triangles here only. Here sp is defined as the space of continuous functions which are affine on each triangle T_k of the domain Ω , usually named V_h . The dimension of such a space is finite, so we can define a basis.

$$sp(\Omega, P1) = \left\{ w(x, y) \text{ such that } \exists (w_1, \dots, w_N) \in \mathbb{R}^N, w(x, y) = \sum_{i=1}^N w_i \varphi_i(x, y) \right\}$$

where N is the space dimension, i.e. the number of nodes (the number of vertices here).

Currently, XLiFE++ implements the following Lagrange elements : P_k on segment, triangle and tetrahedron, Q^k on quadrangle and hexahedron, O_k on prism and pyramid (see section 6.4 for more details). Other non Lagrange elements are also available.

```
Space Vk(_domain=omega, _interpolation=P1, _name="Vk", _optimizeNumbering);
```

lines 17-20: The unknown u here is an approximation of the solution of the problem. v is declared as test function. This comes from the variational formulation of Equation 2.1 : multiplying both sides of equation and integrating over Ω , we obtain :

$$-\int_{\Omega} v \Delta u dx dy + \int_{\Omega} v u dx dy = \int_{\Omega} v f dx dy$$

Then, using Green's formula, the problem is converted into finding u such that :

$$a(u, v) = \int_{\Omega} \nabla u \cdot \nabla v dx dy + \int_{\Omega} u v dx dy = \int_{\Omega} f v dx dy = l(v) \quad (2.3)$$

The 4 next lines in the program declare u and v and define the forms a and l .

```
Unknown u(Vk, "u");
TestFunction v(u, "v");
BilinearForm auv = intg(omega, grad(u) | grad(v)) + intg(omega, u * v);
LinearForm fv=intg(omega, cosxcosy * v);
```

Please notice that:

- The test function is defined from the unknown. The reason is that the test function is dual to the unknown. Through the unknown, v is also defined on the same space.
- The right-hand side needs the definition of the function f . Such function can be defined as a classical C++ function, but with a particular prototype. In this example, f (i.e. $\cos x \cos y$) is a scalar function. So it takes 2 arguments : the first one is a `Point`, containing coordinates x and y . The second one is optional and contains parameters to use inside the function. Here, the `Parameters` object is not used. At last, as a scalar function, it returns a `Real`, but it should be a `Complex` or a real/complex vector (`Reals`, `Complexes`).

```
Real cosxcosy(const Point& P, Parameters& pa = defaultParameters)
{
    Real x=P(1), y=P(2);
    return cos(pi_ * x) * cos(pi_ * y);
}
```

lines 21-22: The previous definitions are a description of the variational form. Now, we have to build the matrix and the right-hand side vector which are the algebraic representations of the linear forms in the finite element space. This is done by the first 2 following lines.

```
TermMatrix A(auv, "a(u,v)");
TermVector B(fv, "f(v)");
```

lines 23-24: Once Matrix and vector being assembled, you can now choose the solver you want. Here, a conjugate gradient solver is used with an initial guess vector equal to the constant vector 1.

XLIFE++ offers you a various choice of direct or iterative solvers:

- LU , LDU , LL^t , LDL^t , LDL^* factorizations
- BICG, BiCGStab, CG, CGS, GMRES, QMR, Sor, SSor, solvers
- internal eigen solver
- interfaces to external packages such as UMFPACK, ARPACK

See chapter 8 for more details.

```
TermVector X0(u, omega, 1., "X0");
TermVector U = cgSolve(A, B, X0, _name="U");
```

line 25: To save the solution, XLIFE++ provides an export to Paraview format file (vtu).

```
saveToFile("U", U, vtu);
```

line 26: This is the end of the program. A "main" function always ends with this line.

```
return 0;
```

3.1 1D problems

Solving 1D problems is sometimes regarded to be out of interest. Anyway, most of existing FE software programs do not handle this case. But in fact, 1D problems are of interest, often as a part of more complex problems. Thus, XLIFE++ deals with 1D problems.

3.1.1 Dirichlet condition

As a first example, we show how to solve the very simple problem, involving Dirichlet conditions:

$$\begin{cases} -u'' = f & \text{in } \Omega =]0, 1[\\ u(0) = u(1) = 0 \end{cases}$$

Its variational formulation is

$$\left| \begin{array}{l} \text{Find } u \in V = \{v \in L^2(\Omega), v' \in L^2(\Omega), u(0) = u(1) = 0\} \text{ such that} \\ \int_0^1 u'(x) v'(x) dx = \int_0^1 f(x) v(x) dx \quad \forall v \in V. \end{array} \right.$$

The following main program corresponds to solving this problem with $f(x) = 1$ using P1 Lagrange element (100 elements):

```
#include "xlife++.h"
using namespace xlifepp;

Real f(const Point& P, Parameters& pa = defaultParameters)
{return -1.;}

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en); // mandatory initialization of xlifepp

    // mesh and domains
    Strings sn("x=0", "x=1");
    Segment seg(_xmin=0, _xmax=1, _nnodes=101, _domain_name="Omega", _side_names=sn);
    Mesh meshld(seg, 1, structured, "P1-mesh");
    Domain omega = meshld.domain("Omega");
    Domain sigmaL = meshld.domain("x=0"), sigmaR = meshld.domain("x=1");

    // space, unknowns, and test functions
    Space Vh(_domain=omega, _interpolation=P1, _name="Vh");
    Unknown u(Vh, _name="u");
    TestFunction v(u, _name="v");

    // define problem
    BilinearForm a = intg(omega, grad(u) | grad(v));
    LinearForm lf = intg(omega, f*v);
    EssentialConditions ecs = (u|sigmaL = 0) & (u|sigmaR = 0);

    // compute matrix and rhs
    TermMatrix A(a, ecs, _name="A");
```

```

TermVector F(lf, _name="F");

// solve linear system and save solution
TermVector U=directSolve(A, F);
saveToFile("U_1d", U, vtu);
return 0;
}

```

The following figure shows a graphical representation of the solution using PARAVIEW:




Figure 3.1: Solution of the Laplace 1D problem on the unit segment $[0, 1]$

3.1.2 Robin condition

The second example shows that XLIFE++ can also handle non homogeneous Neumann conditions or Robin-Fourier conditions. This problem also involve a Dirichlet condition. Given three real functions f_Ω , α and f_N , the problem is:

$$\begin{cases} -u'' + u = f_\Omega & \text{in } \Omega =]a, b[\\ u(a) = 0 \\ u'(b) + \alpha(b) u(b) = f_N(b) \end{cases}$$

Its variational formulation is:

$$\left| \begin{array}{l} \text{Find } u \in V = \{v \in L^2(\Omega), v' \in L^2(\Omega), u(a) = 0\} \text{ such that} \\ \int_a^b u'(x) v'(x) dx + \int_a^b u(x) v(x) dx + \alpha(b) u(b) = \int_a^b f(x) v(x) dx + f_N(b), \quad \forall v \in V. \end{array} \right.$$

$\alpha(b)u(b)$ can be interpreted as $\int_{\{b\}} \alpha(\gamma)u(\gamma) v(\gamma) d\gamma$ and $f_N(b)$ can be interpreted as $\int_{\{b\}} f_N(\gamma) v(\gamma) d\gamma$ where γ is the variable over the side domain here reduced to a point. This allows to handle these conditions in a uniform syntactic way by defining linear forms as shown in the previous examples.

The following main program corresponds to solving this problem with $\alpha(x) = \frac{7}{2}x^2 - 8x$ using the P10 Lagrange element over the interval $]a, b[= \left]0, \frac{13}{4}\pi\right[$ using 4 elements ; the functions $f_\Omega(x) = 2 \sin(x)$ and $f_N(x) = \cos(x) + \alpha(x) \sin(x)$ are chosen so that the solution is $\sin(x)$:

```

#include "xlife++.h"
using namespace xlifepp;

/*

```

```

Test problem:
    -u'' + u = fOm    on the domain Om = [a, b]
    u(a) = 0
    u'(b) + alpha(b) u(b) = fN(b)
*/

Real fctEx (const Point& P, Parameters& pa = defaultParameters)
{ return sin(P[0]); }

Real fctOm (const Point& P, Parameters& pa = defaultParameters)
{ return 2 * sin(P[0]); }

Real alpha (const Point& P, Parameters& pa = defaultParameters)
{ return 3.5*P[0]*P[0] - 8*P[0]; }

Real fctfN (const Point& P, Parameters& pa = defaultParameters)
{ return cos(P[0]) + (3.5*P[0]*P[0] - 8*P[0]) * sin(P[0]); }

int main(int argc, char** argv) {
    init(argc, argv, _lang=en); // mandatory initialization of xlifepp

    // Mesh and domains
    Strings sidenames("x=a", "x=b");
    Segment seg(_xmin=0., _xmax=3.25*pi_, _nnodes=5, _domain_name="Omega", _side_names=sidenames);
    Mesh meshld(seg, 1, structured);
    meshld.printInfo();
    Domain Omega = meshld.domain("Omega");
    Domain xA = meshld.domain("x=a");
    Domain xB = meshld.domain("x=b");

    // Space and unknowns
    Space Vh(_domain=Omega, _FE_type=Lagrange, _order=10, _name="Vh");
    Unknown u(Vh, _name="u");
    TestFunction v(u, _name="v");

    // Bilinear forms
    BilinearForm gugv = intg(Omega, grad(u)|grad(v)), uv = intg(Omega, u*v);
    BilinearForm aluv = intg(xB, alpha*u*v);
    LinearForm fOm = intg(Omega, fctOm*v), fN = intg(xB, fctfN*v);

    // Terms with essential conditions
    EssentialConditions ecs = (u|xA = 0);
    TermMatrix A(gugv + uv + aluv, ecs, _name="A");
    TermVector F(fOm + fN, _name="F");

    // Solve linear system and save solution
    TermVector U = directSolve(A, F);
    saveToFile("U", U, matlab);

    // Compare with exact solution
    TermVector Uex(u, Omega, fctEx, _name="Uex");
    theCout << "||U-Uex|| inf = " << norminf(U-Uex) << endl;
    return 0;
}

```

The following figure shows a graphical representation of the solution using OCTAVE (see section 9.3):




Figure 3.2: Solution of the Laplace 1D problem with Dirichlet and Robin conditions

The left figure shows the interpolation nodes which form a uniform distribution of points. This is the default behavior.

Comparing the exact solution U_{ex} with the computed one U , at the interpolation abscissae, leads to $\|U - U_{ex}\|_{\infty} = 4.44278 \times 10^{-10}$, value which is currently printed by the program.

By adding `_FE_subtype=GaussLobatto` to the `Space` constructor, one can toggle to the Gauss-Lobatto abscissae which are more suitable with higher interpolation degrees. With this example, choosing these abscissae leads to a better approximation: we then get $\|U - U_{ex}\|_{\infty} = 2.55367 \times 10^{-11}$.

3.2 Laplace Problems

We investigate here problems involving Laplacian operator in a 2D bounded domain, say Ω :

$$-\Delta u + a u = f \quad \text{in } \Omega \quad (a = -k^2 \text{ for Helmholtz equation})$$

and various essential conditions (Dirichlet, transmission, quasi periodic, average condition).

3.2.1 Neumann condition

First, let us consider the case of the homogeneous Neumann condition on $\partial\Omega$, the boundary of Ω :

$$\frac{\partial u}{\partial n} = 0 \quad \text{on } \partial\Omega.$$

The variational formulation we deal with is

$$\left| \begin{array}{l} \text{find } u \in V = \{v \in L^2(\Omega), \nabla v \in (L^2(\Omega))^2\} \text{ such that} \\ \int_{\Omega} \nabla u \cdot \nabla v + a \int_{\Omega} u v = \int_{\Omega} f v \quad \forall v \in V. \end{array} \right.$$

The following main program corresponds to solving this problem on unity square $\Omega =]0, 1[\times]0, 1[$ with $f(x) = \cos \pi x \cos \pi y$ using P1 Lagrange element (20x20 elements):

```
#include "xlife++.h"
using namespace xlifepp;

Real cosx2(const Point& P, Parameters& pa = defaultParameters)
{
    Real x=P(1), y=P(2);
    return cos(pi_ * x) * cos(pi_ * y);
}
```

```

}

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en);

    // mesh square
    SquareGeo sq(_origin=Point(0., 0.), _length=1, _nnodes=21);
    Mesh mesh2d(sq, triangle, 1, structured);
    Domain omega = mesh2d.domain("Omega");

    // build space and unknown
    Space Vk(_domain=omega, _interpolation=P1, _name="Vk");
    Unknown u(Vk, _name="u");
    TestFunction v(u, _name="v");

    // define variational formulation
    BilinearForm auv = intg(omega, grad(u) | grad(v)) + intg(omega, u * v);
    LinearForm fv=intg(omega, cosx2 * v);

    // compute matrix and right hand side
    TermMatrix A(auv, _name="a(u, v)");
    TermVector B(fv, _name="f(v)");

    // LLt factorize and solve
    TermMatrix LD;
    IdltFactorize(A, LD);
    TermVector U = factSolve(LD, B);

    saveToFile("U_LN", U, vtU);
    return 0;
}

```




Figure 3.3: Solution of the Laplace 2D problem with Neumann condition on the square $[0, 1]^2$

Solving this problem with P2 Lagrange interpolation should be the same except the line defining the space:

```

Space Vh(_domain=omega, _interpolation=P2, _name="Vh", _optimizeNumbering);

```

Solving this problem in a 3D domain should be the same except the line defining the mesh and the right-hand side function. For instance, on the unity cube, the mesh construction command using GMSH tool is:

```

Real f(const Point& P, Parameters& pa = defaultParameters)
{
    Real x=P(1), y=P(2), z=P(3);

```

```

    return cos(pi*x) * cos(pi*y) * cos(pi*z);
}
\ldots
Mesh mesh(Cube(_origin=Point(0.,0.,0.), _length=1, _nnodes=10), tetrahedron, 1, _gmsht, "P1 mesh");
\ldots

```




Figure 3.4: Solution of the Laplace 3D problem with Neumann condition on the unit cube $[0, 1]^3$

3.2.2 Dirichlet condition

Let us consider now the case of non homogeneous Dirichlet condition on the boundaries $x = 0$ (Σ^-) and $x = 1$ (Σ^+):

$$u = 1 \text{ on } \Sigma^- \cup \Sigma^+.$$

The variational formulation is now ($a = 0$)

$$\left| \begin{array}{l} \text{find } u \in V = \{v \in L^2(\Omega), \nabla v \in (L^2(\Omega))^2\} \text{ such that} \\ \int_{\Omega} \nabla u \cdot \nabla v = \int_{\Omega} f v \quad \forall v \in V, v = 0 \text{ on } \Sigma^- \cup \Sigma^+ \\ u = 1 \quad \text{on } \Sigma^- \cup \Sigma^+ \end{array} \right.$$

Its approximation by P1 Lagrange finite element is implemented in XLIFE++ as follows:

```

#include "xlife++.h"
using namespace xlifepp;

Real f(const Point& P, Parameters& pa = defaultParameters)
{return -8.;}

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en); // mandatory initialization of xlifepp

    // create mesh of square
    Strings sn("y=0", "x=1", "y=1", "x=0");
    SquareGeo sq(_origin=Point(0., 0.), _length=1, _nnodes=20, _domain_name="Omega",
        _side_names=sn);
    Mesh mesh2d(sq, triangle, 1, structured);
    Domain omega=mesh2d.domain("Omega");
    Domain sigmaM=mesh2d.domain("x=0"), sigmaP=mesh2d.domain("x=1");

    // create interpolation

```

```

Space V(_domain=omega, _interpolation=P1, _name="V");
Unknown u(V, _name="u");
TestFunction v(u, _name="v");

// create bilinear form, linear form and their algebraic representation
BilinearForm auv=intg(omega, grad(u) | grad(v));
LinearForm fv=intg(omega, f*v);
EssentialConditions ecs= (u|sigmaM = 1) & (u|sigmaP = 1);
TermMatrix A(auv, ecs, _name="A");
TermVector B(fv, _name="B");

// solve linear system AX=B
TermVector U=directSolve(A, B);
saveToFile("U_LD", U, vtu);
return 0;
}

```




Figure 3.5: Solution of the Laplace 2D problem with Dirichlet condition on the unit square $[0, 1]^2$

Note how easy is to take into account essential conditions. Only two lines has to be modified!

3.2.3 Periodic condition

Now we consider the Laplace problem on the unit square $\Omega =]0, 1[\times]0, 1[$ equipped with Dirichlet condition on and periodic condition:

$$\begin{cases} -\Delta u = f & \text{in } \Omega \\ u|_{\Gamma^-} = 0 \text{ and } u|_{\Gamma^+} = 0 \\ u|_{\Sigma^-} = u|_{\Sigma^+} \text{ and } \partial_x u|_{\Sigma^-} = \partial_x u|_{\Sigma^+} \end{cases}$$

and its variational formulation in $V = \{v \in H^1(\Omega), u|_{\Gamma} = 0 \text{ and } u|_{\Sigma^-} = u|_{\Sigma^+}\}$:

$$\left| \begin{array}{l} \text{find } u \in V \text{ such that} \\ \int_{\Omega} \nabla u \cdot \nabla v = \int_{\Omega} f v \quad \forall v \in V. \end{array} \right.$$

Its approximation by P^2 Lagrange finite element is implemented in XLiFE++ as follows:

```

#include "xlife++.h"
using namespace xlifepp;

Real f(const Point& P, Parameters& pa = defaultParameters)
{
    Real x=P(1), y=P(2);
    return (4*pi_*pi_*y*(y-1)-2)*sin(2*pi_*x);
}

Vector<Real> mapPM(const Point& P, Parameters& pa = defaultParameters)
{
    Vector<Real> Q(P);
    Q(1)-=1;
    return Q;
}

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en); // mandatory initialization of xlifepp

    // mesh square
    Strings sn("y=0", "x=1", "y=1", "x=0");
    SquareGeo sq(_origin=Point(0., 0.), _length=1, _nnodes=20, _domain_name="Omega",
        _side_names=sn);
    Mesh mesh2d(sq, triangle, 1, structured);
    Domain omega=mesh2d.domain("Omega");
    Domain sigmaM=mesh2d.domain("x=0"), sigmaP=mesh2d.domain("x=1");
    Domain gammaM=mesh2d.domain("y=0"), gammaP=mesh2d.domain("y=1");
    defineMap(sigmaP, sigmaM, mapPM); // useful to periodic condition

    // create P2 Lagrange interpolation
    Space V(_domain=omega, _interpolation=P2, _name="V");
    Unknown u(V, _name="u");
    TestFunction v(u, _name="v");

    // create bilinear form and linear form
    BilinearForm auv=intg(omega, grad(u)|grad(v));
    LinearForm fv=intg(omega, f*v);
    EssentialConditions ecs = (u|gammaM = 0) & (u|gammaP = 0)
        & ((u|sigmaP) - (u|sigmaM) = 0); // EssentialConditions ecs
    TermMatrix A(auv, ecs, _name="A");
    TermVector B(fv, _name="B");

    // solve linear system AX=F using factorization
    TermVector U=directSolve(A, B);
    saveToFile("U_LP", U, vtu);

    // Solving eigen problem intg(omega, grad(u)|grad(v))=lambda intg(omega, u*v) with ecs
    BilinearForm uv=intg(omega, u*v);
    TermMatrix Ae(auv, ecs, _reduction=ReductionMethod(_pseudoReduction, 0., 1000.), _name="Ae");
    TermMatrix Me(uv, ecs, _reduction=ReductionMethod(_pseudoReduction, 0., 1.), _name="Me");
    EigenElements eigs=eigenSolve(Ae, Me, _nev=10, _which="SM");
    Complex l1=eigs.value(1); // first eigen value
    TermVector e1=eigs.vector(1); // first eigen vector, "eliminated" components are not up to
    date
    e1.applyEssentialConditions(ecs); // update "eliminated" components of e1
    eigs.applyEssentialConditions(ecs); // update "eliminated" components of all eigen vectors

    return 0;
}

```

Note that at corners, periodic condition and Dirichlet condition are redundant. When executing, the following

warning message is thrown

```
Constraints::reduceConstraints() : in essential conditions
  Dirichlet condition u = 0 on y=0
  Dirichlet condition u = 0 on y=1
  periodic condition u|x=1 - u|x=0 = 0
2 redundant constraint row(s) detected and eliminated
```





Figure 3.6: Solution of the Laplace 2D problem with periodic condition on the unit square $[0, 1]^2$

3.2.4 Transmission condition



We turn to the Laplace problem with transmission condition:

$$\begin{cases} -\Delta u^- = f & \text{in } \Omega^- \\ -\Delta u^+ = f & \text{in } \Omega^+ \\ u|_{\Sigma^-} = 1 \text{ and } u|_{\Sigma^+} = 1 \\ u|_{\Gamma}^- = u|_{\Gamma}^+ \text{ and } \partial_x u|_{\Gamma}^- = \partial_x u|_{\Gamma}^+ \end{cases}$$

Its variational formulation in

$$V = \{(v^-, v^+) \in H^1(\Omega^-) \times H^1(\Omega^+), v|_{\Sigma^-}^- = 0, v|_{\Sigma^-}^+ = 0, v|_{\Gamma}^- = v|_{\Gamma}^+\}$$

is

$$\left| \begin{array}{l} \text{find } (u^-, u^+) \in H^1(\Omega^-) \times H^1(\Omega^+), u|_{\Sigma^-}^- = 1, u|_{\Sigma^-}^+ = 1, u|_{\Gamma}^- = u|_{\Gamma}^+ \text{ such that} \\ \int_{\Omega^-} \nabla u^- \cdot \nabla v^- + \int_{\Omega^+} \nabla u^+ \cdot \nabla v^+ = \int_{\Omega^-} f v^- + \int_{\Omega^+} f v^+ \quad \forall v \in V. \end{array} \right.$$

Note that derivatives matching is taken into account in a weak sense. The implementation in XLIFE++, using P^2 Lagrange finite element, looks like:

```
#include "xlife++.h"
using namespace xlifepp;

Real f(const Point& P, Parameters& pa = defaultParameters)
{
    return -8.;
}

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en); // mandatory initialization of xlifepp

    // mesh domain
    Strings sn(4);
    sn[1] = "x=1/2-"; sn[3] = "x=0";
    Rectangle r1(_xmin=0, _xmax=0.5, _ymin=0, _ymax=1, _nnodes=Numbers(20, 40),
        _domain_name="Omega-", _side_names=sn);
    Mesh mesh2d(r1, triangle, 1, _structured);
    sn[1] = "x=1"; sn[3] = "x=1/2+";
    Rectangle r2(_xmin=0.5, _xmax=1, _ymin=0, _ymax=1, _nnodes=Numbers(20, 40),
        _domain_name="Omega+", _side_names=sn);
    Mesh mesh2d_p(r2, triangle, 1, structured);
    mesh2d.merge(mesh2d_p);
    Domain omegaM=mesh2d.domain("Omega-"), omegaP=mesh2d.domain("Omega+");
    Domain sigmaM=mesh2d.domain("x=0"), sigmaP=mesh2d.domain("x=1");
    Domain gamma=mesh2d.domain("x=1/2- or x=1/2+");

    // create P2 interpolation
    Space VM(_domain=omegaM, _interpolation=P2, _name="VM");
    Unknown uM(VM, _name="u-");
    TestFunction vM(uM, _name="v-");
    Space VP(_domain=omegaP, _interpolation=P2, _name="VP");
    Unknown uP(VP, _name="u+");
    TestFunction vP(uP, _name="v+");

    // create bilinear form and linear form
    BilinearForm auv=intg(omegaM, grad(uM)|grad(vM))+intg(omegaP, grad(uP)|grad(vP));
    LinearForm fv=intg(omegaM, f*vM)+intg(omegaP, f*vP);
    EssentialConditions ecs=(uM|sigmaM == 1) & (uP|sigmaP == 1) & ((uM|gamma) - (uP|gamma) == 0);
    TermMatrix A(auv, ecs, _name="A");
    TermVector B(fv, _name="B");

    // solve linear system AX=B using LU factorization
    TermVector U=directSolve(A, B);
    saveToFile("U_LT", U, vtu);
    return 0;
}
```

Here, a tool merging mesh is used to create a two domains mesh. GMSH should be used also. The picture below shows that the solution is continuous across the boundary Γ .




Figure 3.7: Solution of the Laplace 2D problem with transmission condition on the unit square $[0, 1]^2$

3.2.5 Average condition

As a last example of essential condition, we consider average condition, for instance:

$$\int_{\Sigma} u = 0.$$

Such condition is tricky to take into account in FE softwares. Generally, they do not! Because XLIFE++ uses a powerful process to deal with essential conditions, such condition can be easily addressed:

```
#include "xlife++.h"
using namespace xlifepp;

Real f(const Point& P, Parameters& pa = defaultParameters)
{return -8.;}

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en); // mandatory initialization of xlifepp

    // create a mesh and Domains
    SquareGeo sq(_origin=Point(0., 0.), _length=1, _nnodes=10, _domain_name="Omega",
        _side_names=Strings("y=0", "x=1", "y=1", "x=0"));
    Mesh mesh2d(sq, triangle, 1, structured);
    Domain omega=mesh2d.domain("Omega");
    Domain sigmaM=mesh2d.domain("x=0"), sigmaP=mesh2d.domain("x=1");

    // create interpolation
    Space V(_domain=omega, _interpolation=P2, _name="V");
    Unknown u(V, _name="u");
    TestFunction v(u, _name="v");

    // create bilinear form and linear form
    BilinearForm auv=intg(omega, grad(u) | grad(v));
    LinearForm fv=intg(omega, f*v);
    EssentialConditions ecs= (intg(sigmaM, u) = 0);
    TermMatrix A(auv, ecs, _name="A");
    TermVector F(fv, _name="B");

    // solve linear system AX=F using LU factorization
    TermVector U=directSolve(A, F);
```

```

saveToFile("U_LA", U, vtu);
return 0;
}

```




Figure 3.8: Solution of the Laplace 2D problem with average condition on the unit square $[0, 1]^2$



Beware of some average conditions. For instance, when adding the "full" average condition

$$\int_{\Omega} u = 0$$

the resulting reduced matrix is a full matrix. So, the problem is bigger and slower to solve!

3.3 Eigenvalues and eigenvectors of Laplace operator

This example shows how to get eigen functions of Laplace operator equipped with homogeneous Neumann condition:

$$\begin{cases} -\Delta u + u = \lambda u & \text{in } \Omega \\ \partial_n u = 0 & \text{on } \partial\Omega \end{cases}$$

and its variational formulation in $V = H^1(\Omega)$:

$$\left| \begin{array}{l} \text{find } (u, \lambda) \in V \times \mathbb{R} \text{ such that} \\ \int_{\Omega} \nabla u \cdot \nabla v + \int_{\Omega} u v = \lambda \int_{\Omega} u v \quad \forall v \in V. \end{array} \right.$$

```

#include "xlife++.h"
using namespace xlifepp;

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en); // mandatory initialization of xlifepp

    // mesh square
    SquareGeo sq(_origin=Point(0., 0.), _length=1, _nnodes=20);
    Mesh mesh2d(sq, triangle, 1, gmsh);
    Domain omega = mesh2d.domain("Omega");

    // build P2 interpolation
    Space Vk(_domain=omega, _interpolation=P2, _name="Vk");
    Unknown u(Vk, _name="u");
}

```

```

TestFunction v(u, _name="v");

// build eigen system
BilinearForm auv = intg(omega, grad(u) | grad(v)) + intg(omega, u * v) ,
    muv = intg(omega, u * v);
TermMatrix A(auv, _name="auv"), M(muv, _name="muv");

// compute the 10 first smallest in magnitude
EigenElements eigs = eigenInternSolve(A, M, _nev=10, _mode=krylovSchur, _which="SM"); //
    internal solver
theCout << eigs.values;
saveToFile("eigs", eigs.vectors, vtu);
return 0;
}

```




Figure 3.9: 9 first eigen vectors of the Laplace 2D problem with P2 elements

3.4 Discontinuous Galerkin method for 2D Dirichlet problem

Consider the Laplace problem with homogeneous Dirichlet condition:

$$\begin{cases} -\Delta u = f & \text{in } \Omega \\ u = 0 & \text{on } \partial\Omega \end{cases}$$

Consider a discontinuous Galerkin space V_h , e.g. discontinuous P^1 -Lagrange space and let introduce the IP (Interior Penalty) formulation:

$$\left| \begin{array}{l} \text{find } u_h \in V_h \text{ such that} \\ \int_{\Omega} \nabla_h u_h \cdot \nabla_h v - \int_{\Gamma} \{\nabla_h u_h \cdot n\} [v] - \int_{\Gamma} [u_h] \{\nabla_h v \cdot n\} + \int_{\Gamma} \mu [u_h] [v] = \int_{\Omega} f v \quad \forall v \in V_h. \end{array} \right.$$

where $\Omega = \bigcup T_\ell$, $\Gamma = \bigcup \partial T_\ell$ (the set of all sides of mesh elements) and, $S_{k,\ell}$ denoting the side shared by the elements T_k and T_ℓ :

$$\{v\}_{|S_{k\ell}} = \frac{1}{2} \left((v|_{T_k})_{|S_{k\ell}} + (v|_{T_\ell})_{|S_{k\ell}} \right) \quad [v]_{|S_{k\ell}} = \left((v|_{T_k})_{|S_{k\ell}} - (v|_{T_\ell})_{|S_{k\ell}} \right).$$

For a non shared side S_k , we set

$$\{v\}_{|S_k} = [v]_{|S_k} = (v|_{T_k})_{|S_k}.$$

The operators $\{.\}$ and $[.]$ are implemented in XLiFE++ as `mean(.)` and `jump(.)` operators. The normal vector n is chosen as the outward normal from T_k on side $S_{k\ell}$; in practice outward from the "first" parent element of the side. μ is a penalty function usually chosen to be proportional to the inverse of the measure of the side $S_{k\ell}$. Note that the Dirichlet boundary condition is a natural condition in this formulation.

To deal with a such formulation, the following objects have to be constructed from a geometrical domain, say ω :

- a FE space specifying $L2$ conformity (discontinuous space) defined on ω
- the geometrical domain Γ of sides of ω using the function `sides(omega)`
- the bilinear form related to IP formulation and involving `mean(.)` and `jump(.)` operators

The XLiFE++ implementation of this problem using discontinuous P1-Lagrange is the following:

```
#include "xlife++.h"
using namespace xlifepp;

Real uex(const Point& p, Parameters& pars=defaultParameters)
{return sin(pi_*p(1))*sin(pi_*p(2));}
Real f(const Point& p, Parameters& pars=defaultParameters)
{return 2*pi_*pi_*sin(pi_*p(1))*sin(pi_*p(2));}
Real fmu(const Point& p, Parameters& pars=defaultParameters)
{GeomElement* gelt=getElementP();
 if(gelt!=0) return 1/gelt->measure();
 return 0.;
}

int main(int argc, char** argv)
{
  init(argc, argv, _lang=en); // mandatory initialization of xlifepp
  // create mesh and geometrical domains
  Rectangle R(_origin=Point(0.,0.), _xlength=1., _ylength=1., _nnodes=31, _domain_name="Omega");
  Mesh mR(R, _triangle, 1, _structured, _alternateSplit);
  Domain omega=mR.domain("Omega");
  Domain gamma=sides(omega); // create domain of sides
  // create discontinuous P1-Lagrange space
  Space V(_domain=omega, _FE_type=Lagrange, _order=1, _Sobolev_type=L2, _name="V");
  Unknown u(V, _name="u"); TestFunction v(u, _name="v");
  // create bilinear form and TermMatrix
  Function mu(fmu); mu.require("element");
  BilinearForm a=intg(omega, grad(u)|grad(v))-intg(gamma, mean(grad(u)|_n)*jump(v))
    -intg(gamma, jump(u)*mean(grad(v)|_n))+intg(gamma, mu*jump(u)*jump(v));
  TermMatrix A(a, _name="A");
  // create the right hand side and solve the linear system
  TermVector F(intg(omega, f*v), _name="F");
  TermVector U=directSolve(A, F);
  saveToFile("U", U, _vtu);
  // compute L2 error
  TermMatrix M(intg(omega, u*v), _name="M");
  TermVector Uex(u, omega, uex);
```

```

TermVector E=U-Uex;
theCout<<" IP : |U-uex|L2 = "<<sqrt(M*E|E)<<eol;
return 0;
}

```

The L^2 error is about 0.00317 for 5400 DoFs. Using Paraview with the *Warp by scalar* filter that produces elevation, the approximated field u looks like:




Figure 3.10: Solution of the 2D Dirichlet problem on the unit square $[0, 1]^2$ with discontinuous P1-Lagrange elements, IP formulation (left) and NIPG formulation (right)

It can be noticed that the field is discontinuous and major errors are located on the corners. NIPG formulation is another penalty method corresponding to the bilinear form:

$$\int_{\Omega} \nabla_h u_h \cdot \nabla_h v - \int_{\Gamma} \{\nabla_h u_h \cdot n\} [v] + \int_{\Gamma} [u_h] \{\nabla_h v \cdot n\} + \int_{\Gamma} \mu [u_h] [v]$$

that is close to the IP formulation but non-symmetric. For NIPG, the L^2 error is weaker (about 0.00141) and the solution is less polluted at the corners.

3.5 Mixed formulation

3.5.1 Laplace problem using P0 and Raviart-Thomas elements

Consider the Laplace problem with homogeneous Dirichlet condition:

$$\begin{cases} -\Delta u = f & \text{in } \Omega \\ u = 0 & \text{on } \partial\Omega \end{cases}$$

Introducing $p = \nabla u$, it is rewritten as a mixed problem in (u, p) :

$$\begin{cases} -\operatorname{div} p = f & \text{in } \Omega \\ p = \nabla u & \text{in } \Omega \\ u = 0 & \text{on } \partial\Omega \end{cases}$$

with the following variational formulation:

$$\left| \begin{array}{l} \text{find } (u, p) \in L^2(\Omega) \times H(\text{div}, \Omega) \text{ such that} \\ - \int_{\Omega} \text{div } p \, v = \int_{\Omega} f \, v \quad \forall v \in L^2(\Omega) \\ \int_{\Omega} u \, \text{div } q + \int_{\Omega} p \cdot q = 0 \quad \forall q \in H(\text{div}, \Omega). \end{array} \right.$$

Note that the Dirichlet boundary condition is a natural condition in this formulation.

The XLIFE++ implementation of this problem using P0 approximation for $L^2(\Omega)$ and an approximation of $H(\text{div}, \Omega)$ using Raviart-Thomas elements of order 1 is the following:

```
#include "xlife++.h"
using namespace xlifepp;

Real f(const Point& P, Parameters& pa = defaultParameters)
{ Real x=P(1), y=P(2);
  return 32*(x*(1-x)+y*(1-y)); }

int main(int argc, char** argv)
{
  init(argc, argv, _lang=en);
  // mesh square
  SquareGeo sq(_origin=Point(0., 0.), _length=1, _nnodes=21);
  Mesh mesh2d(sq, triangle, 1, structured);
  Domain omega=mesh2d.domain("Omega");
  // create approximation P0 and RT1
  Space H(_domain=omega, _interpolation=P0, _name="H", _notOptimizeNumbering);
  Space V(_domain=omega, _FE_type=RaviartThomas, _order=1, _name="V");
  Unknown p(V, _name="p");
  TestFunction q(p, _name="q"); // p=grad(u)
  Unknown u(H, _name="u");
  TestFunction v(u, _name="v");
  // create problem (Poisson problem)
  TermMatrix A(intg(omega, p|q) + intg(omega, u*div(q)) - intg(omega, div(p)*v));
  TermVector b(intg(omega, f*v));
  // solve and save solution
  TermVector X=directSolve(A, b);
  saveToFile("u", X(u), vtu);
  return 0;
}
```

Using Paraview with the *Cell data to point data* filter that moves P0 data to P1 data and the *Warp by scalar* filter that produces elevation, the approximated field u looks like:




Figure 3.11: Solution of the Laplace 2D problem with mixed formulation P0-RT1 on the unit square $[0, 1]^2$

3.5.2 2D Stokes problem

We consider the problem of a flow entrained in a cavity, say $\Omega =]0, 1[\times]0, 1[$:

$$\left\{ \begin{array}{ll} -\nu \Delta \mathbf{u} + \nabla p = \mathbf{f} & \text{dans } \Omega \\ \operatorname{div} \mathbf{u} = 0 & \text{dans } \Omega \\ \mathbf{u} = \mathbf{g} & \text{sur } \Sigma = \{0\} \times]0, 1[\\ \mathbf{u} = \mathbf{0} & \text{sur } \Gamma = \partial\Omega \setminus \Sigma \end{array} \right. \quad (3.1)$$

with $\mathbf{f} \in L^2(\Sigma)$ and $\mathbf{g} = (0, v_0)$, $v_0 \in H^{\frac{1}{2}}(\Sigma)$. Note that $\mathbf{g} \cdot \mathbf{n} = 0$.

This problem has the following variational formulation: find $(\mathbf{u}, p) \in H^1(\Omega)^2 \times L_0^2(\Omega)$ such that for all $(\mathbf{v}, p) \in H_0^1(\Omega)^2 \times L_0^2(\Omega)$:

$$\left\{ \begin{array}{l} \nu \int_{\Omega} \nabla \mathbf{u} : \nabla \mathbf{v} - \int_{\Omega} p \operatorname{div} \mathbf{v} - \int_{\Omega} \operatorname{div} \mathbf{u} q = \int_{\Omega} \mathbf{f} \mathbf{v} \\ \mathbf{u} = \mathbf{g} \text{ on } \Sigma \text{ and } \mathbf{u} = \mathbf{0} \text{ on } \Gamma \end{array} \right. \quad (3.2)$$

The following XLIFE++ implementation of this problem solves the 2D Stokes problem using different couple of approximations for the pressure p and the velocity v : (P^0, P^2) , (P^1, P^2) , (P^0, CR) ; CR corresponds to a Crouzeix-Raviart finite element approximation leading to a non-conforming approximation of H^1 . Note that the (P^0, P^1) approximation is not working because of dof locking.

```
#include "xlife++.h"
using namespace xlifepp;
using namespace std;

Vector<Real> g(const Point& p, Parameters& pa = defaultParameters)
{
    Vector<Real> r(2, 0.);
    r(2) = 1.;
    return r;
}

int main(int argc, char** argv)
{
    init(_lang=en); // mandatory initialization of xlifepp
    verboseLevel(1);
    //geometry data
    Square sq(_origin=Point(0., 0.), _length=1., _nnodes=30, _domain_name="Omega",
```

```

        _side_names=Strings("Gamma","Gamma", "Gamma", "Sigma"));
Mesh mesh(sq,_triangle);
Domain Omega=mesh.domain("Omega");
Domain Sigma=mesh.domain("Sigma");
Domain Gamma=mesh.domain("Gamma");
// solve Stokes 2D for several approximations
list<pair<InterpolationType,InterpolationType>> pint={{P0,P2},{P1,P2},{P0,CR}};
for(auto ps:pint)
{
    Space H1(_domain=Omega,_interpolation=ps.second,_name="H1");
    Unknown u(H1,_name="u",_dim=2); TestFunction v(u,_name="v");
    Space L2(_domain=Omega,_interpolation=ps.first,_name="L2");
    Unknown p(L2,_name="p"); TestFunction q(p,_name="q");
    BilinearForm a = intg(Omega,grad(u)%grad(v))-intg(Omega,p*div(v))-intg(Omega,div(u)*q);
    EssentialConditions ecs = (u|Gamma == 0) & (u | Sigma == g) & (intg(Omega,p)==0);
    TermMatrix A(a,ecs,_name="A");
    TermVector b(u,Omega,0.,_name="b");
    TermVector X=directSolve(A,b);
    String ext="_"+words("interpolation",ps.first)+"_"+words("interpolation",ps.second);
    saveToFile("p"+ext,X(p),_vtu);
    if(ps.second==_CR)
    {
        Space V1(_domain=Omega,_interpolation=P1,_name="V1");
        TermVector u1=projection(X(u),V1,2);
        saveToFile("u"+ext,u1,"u1",_vtu);
    }
    else saveToFile("u"+ext,X(u),_vtu);
}
return 0;
}

```

Using Paraview with the *Glyph* filter that represents 2D vectors with arrows, we get the following pictures:




Figure 3.12: Solution of the 2D Stokes problem using different approximations


Note that to approximate the space $L_0^2(\Omega)$, an essential condition of the zero mean type of pressure p has been used. Such a condition is quite costly because it interacts with all the pressure dofs. If we remove it, the matrix becomes singular (the pressure being defined to within a constant) and direct solvers fail. But iterative solvers do converge to the right velocity, and pressure to the right constant, determined by the initial guess of the iterative solver !

Note also that, when using Crouzeix-Raviart element, in order to visualize the velocity, it is required to project the CR solution in a standard Lagrange finite element space (here P^1).

3.6 Fictitious domain method

A well-known method to avoid some complex meshes consists in using the fictitious domain method where the boundary condition on an inside obstacle is taken into account by a Lagrange multiplier. To illustrate it, we consider the following 2D Laplace problem in the domain $\Omega = C \setminus B(O, R)$ with $C =]0, 1[\times]0, 1[$ the unit square, $B(O, R)$ the ball with center C and radius R such that $B \subset C$:

$$\begin{cases} -\Delta u = f & \text{in } \Omega \\ u = 0 & \text{on } \partial C = \Sigma \\ u = g & \text{on } \partial B = \Gamma \end{cases}$$



Let us introduce the minimization problem:

$$\min_{\tilde{v} \in \tilde{V}(g)} \frac{1}{2} \int_C |\nabla \tilde{v}|^2 - \int_C \tilde{f} \tilde{v}$$

where

$$\tilde{V}(g) = \{ \tilde{v} \in H^1(C), \tilde{v}|_{\Sigma} = 0 \text{ and } \tilde{v}|_{\Gamma} = g \} \text{ and } \tilde{f} = \begin{cases} f & \text{in } \Omega \\ 0 & \text{in } B \end{cases}.$$

It has a unique solution $\tilde{u} \in \tilde{V}(g)$ such that $\tilde{u} = u$ on Ω and there exists $p \in H^{-\frac{1}{2}}(\Gamma)$ such that

$$\begin{cases} \int_C \nabla \tilde{u} \cdot \nabla \tilde{v} - \int_{\Gamma} p \tilde{v} = \int_C \tilde{f} \tilde{v} & \forall \tilde{v} \in H_0^1(C) \\ \int_{\Gamma} \tilde{u} q = \int_{\Gamma} g q & \forall q \in H^{-\frac{1}{2}}(\Gamma), \end{cases}$$

where the integrals on Γ are to be understood as the duality product on $H^{-\frac{1}{2}}(\Gamma) \times H^{\frac{1}{2}}(\Gamma)$.

The key idea of fictitious domain method is to use two different meshes for C and Γ . As a consequence, the computation of integrals on Γ involves shape functions that lie on two different meshes, inducing interpolation operations from one mesh to the other one. XLIFE++ manages this interpolation operations in an hidden way for the user:

```
#include "xlife++.h"
using namespace xlifepp;

Real R;

Real f(const Point& P, Parameters& pa = defaultParameters)
{ if (norm(P) <= R) return 0.;
  return 2*pi_*pi_*sin(pi_*P(1))*sin(pi_*P(2)); }

Real g(const Point& P, Parameters& pa = defaultParameters)
{ return sin(pi_*P(1))*sin(pi_*P(2)); }

int main(int argc, char** argv)
{
```

```

init(argc, argv, _lang=en); // mandatory initialization of xlifepp

// create meshes (rectangle and circle)
R=0.2;
SquareGeo sq(_xmin =0, _xmax = 1, _ymin = 0, _ymax = 1,
    _hsteps=0.05,
    _domain_name = "Omega", _side_names="Sigma");
Disk circle(_center=Point(0.5, 0.5), _radius =R, _hsteps=0.05,
    _domain_name = "Gamma");
Mesh meshS(sq, triangle);
Mesh meshG(circle, segment, 1, gmsh);
Domain omega = meshS.domain("Omega"),
    sigmat = meshS.domain("Sigma"),
    gammat = meshG.domain("Gamma");

// create spaces and unknowns
Space Vt(_domain=omega, _interpolation=P1, _name="Vt");
Unknown ut(Vt, _name="ut"); TestFunction vt(ut, _name="vt");
Space W(_domain=gammat, _interpolation=P0, _name="W");
Unknown p(W, _name="p"); TestFunction q(p, _name="q");

// create bilinear forms and Terms
BilinearForm at = intg(omega, grad(ut)|grad(vt))-intg(gammat, p*vt)
    - intg(gammat, ut*q);
BoundaryConditions bcst = (ut|sigmat =0);
TermMatrix At(at, bcst, _name="At");
TermVector Ft(intg(omega, f*vt)-intg(gammat, g*q), _name="Ft");

// solve linear system and save the solution to a vtu file
TermVector Ut = directSolve(At, Ft);
saveToFile("Ut", Ut, vtu);

return 0;
}

```

To extract the solution on the real domain Ω , a L2 projection is used:

```

// create a mesh for Omega
Disk disk(_center=Point(0.5,0.5), _radius =R, _hsteps=0.05,
    _domain_name = "Obstacle", _side_names="Gamma");
Mesh mesh(rectangle-disk, _triangle);
Domain omega = mesh.domain("Omega");
Space V(omega, P1, "V"); Unknown u(V, "u"); TestFunction v(u, "v");

//compute L2 projection of ut on omega
TermMatrix M(intg(omega, u*v)), M2(intg(omega, ut*v));
TermVector PUt = directSolve(M, M2*Ut);
saveToFile("PUt", PUt, _vtu);

```

Note that the computation of the matrix M2 also requires a computation of an integrals involving two meshes!




Figure 3.13: Solution of the Laplace 2D problem with the fictitious domain method

3.7 Maxwell equations using Nedelec elements

3.7.1 2D Maxwell equations

XLiFE++ provides Nedelec elements (first and second family) that are $H(\text{curl})$ conforming. Consider the following academic Maxwell problem:

$$\begin{cases} \text{curl curl } \mathbf{E} - \omega^2 \mu \varepsilon \mathbf{E} = \mathbf{f} & \text{in } \Omega \\ \mathbf{E} \times \mathbf{n} = 0 & \text{on } \partial\Omega \end{cases}$$

with the following weak form:

$$\left| \begin{array}{l} \text{find } \mathbf{E} \in V = \{\mathbf{v} \in H(\text{curl}, \Omega), \mathbf{v} \times \mathbf{n} = 0 \text{ on } \partial\Omega\} \text{ such that} \\ \int_{\Omega} \text{curl } \mathbf{E} \text{ curl } \mathbf{v} = -\omega^2 \mu \varepsilon \int_{\Omega} \mathbf{E} \mathbf{v} \quad \forall \mathbf{v} \in V. \end{array} \right.$$

Using first family Nedelec's element, the XLiFE++ program looks like:

```
#include "xlife++.h"
using namespace xlifepp;

Real omg=1, eps=1, mu=1, a=pi_, ome=omg* omg* mu* eps;

Vector<Real> f(const Point& P, Parameters& pa = defaultParameters)
{
    Real x=P(1), y=P(2);
```

```

Vector<Real> res(2);
Real c=2*a*a-ome;
res(1)=-c*cos(a*x)*sin(a*y);
res(2)= c*sin(a*x)*cos(a*y);
return res;
}

Vector<Real> solex(const Point& P, Parameters& pa = defaultParameters)
{
    Real x=P(1), y=P(2);
    Vector<Real> res(2);
    res(1)=-cos(a*x)*sin(a*y);
    res(2)= sin(a*x)*cos(a*y);
    return res;
}

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en);
    // mesh square using gmsh
    SquareGeo sq(_xmin=0, _xmax=1, _ymin=0, _ymax=1, _nnodes=50, _side_names="Gamma");
    Mesh mesh2d(sq, triangle, 1, gmsh);
    Domain omega=mesh2d.domain("Omega");
    Domain gamma=mesh2d.domain("Gamma");
    // define space and unknown
    Space V(_domain=omega, _FE_type=Nedelec, _order=1, _name="V");
    Unknown e(V, _name="E");
    TestFunction q(e, _name="q");
    // define forms, matrices and vectors
    BilinearForm aev=intg(omega, curl(e)|curl(q)) - ome*intg(omega, e|q);
    LinearForm l=intg(omega, f|q);
    EssentialConditions ecs = (ncross(e)|gamma=0);
    // compute
    TermMatrix A(aev, ecs, _name="A");
    TermVector b(l, _name="B");
    // solve
    TermVector E=directSolve(A, b);
    // P1 interpolation, L2 projection on H1
    Space W(_domain=omega, _interpolation=P1, _name="W");
    TermVector EP1=projection(E, W, 2);
    EP1.name("E");
    saveToFile("E", EP1, vtu);
    return 0;
}

```

As Nedelec finite elements approximation are not conforming in H_1 , the solution is not continuous across elements (only tangent component is continuous). So to represent the solution, it is projected on H_1 as follows:

$$\left| \begin{array}{l} \text{find } \mathbf{E}_1 \in L^2(\Omega) \text{ such that} \\ \int_{\Omega} \mathbf{E}_1 \mathbf{w} = \int_{\Omega} \mathbf{E} \mathbf{w} \quad \forall \mathbf{w} \in L^2(\Omega). \end{array} \right.$$

Using an H_1 conforming approximation for $\mathbf{E}_1$ leads to a continuous representation of the projection. We show on the next figure the E_x component field provided by this example:




Figure 3.14: First component of the solution of the Maxwell 2D problem using Nedgelec first family elements, and nodal error




Figure 3.15: L^2 errors versus the step h for 1 and 2 order Nedgelec first family approximation

3.7.2 3D Maxwell equations

Dealing with 3D Maxwell problem using Nedgelec elements is very similar to the 2D case. We consider the academic Maxwell problem:

$$\text{curl curl } \mathbf{E} - \omega^2 \mu \varepsilon \mathbf{E} = \mathbf{f} \quad \text{in } \Omega$$

equipped with the natural boundary condition:

$$\text{curl } \mathbf{E} \times \mathbf{n} = \mathbf{g} \quad \text{on } \partial\Omega.$$

It has the following weak form:

$$\left| \begin{array}{l} \text{find } \mathbf{E} \in V = \{\mathbf{v} \in H(\text{curl}, \Omega)\} \text{ such that} \\ \int_{\Omega} \text{curl } \mathbf{E} \cdot \text{curl } \mathbf{v} - \omega^2 \mu \varepsilon \int_{\Omega} \mathbf{E} \cdot \mathbf{v} = \int_{\Omega} \mathbf{f} \cdot \mathbf{v} + \int_{\partial\Omega} \mathbf{g} \cdot \mathbf{v} \quad \forall \mathbf{v} \in V. \end{array} \right.$$

In the example we use as a solution

$$\mathbf{E}_{ex}(x, y, z) = \begin{pmatrix} -2 \cos(ax) \sin(ay) \sin(az) \\ \sin(ax) \cos(ay) \sin(az) \\ \sin(ax) \sin(ay) \cos(az) \end{pmatrix}$$

with $f = \text{curl curl } \mathbf{E}_{ex} - \omega^2 \mu \epsilon \mathbf{E}_{ex}$ and $g = \text{curl } \mathbf{E}_{ex} \times n$.

Using the first family Nedelec's elements, the XLIFE++ program looks like:

```
#include "xlife++.h"
using namespace xlifepp;

Real omg=1, eps=1, mu=1, a=pi_, ome=omg* omg* mu* eps;

Vector<Real> f(const Point& P, Parameters& pa = defaultParameters)
{
    Real x=P(1), y=P(2), z=P(3);
    Vector<Real> res(3);
    Real c=3*a*a-ome;
    res(1)=-2*cos(a*x)*sin(a*y)*sin(a*z)*c;
    res(2)= sin(a*x)*cos(a*y)*sin(a*z)*c;
    res(3)= sin(a*x)*sin(a*y)*cos(a*z)*c;
    return res;
}

Vector<Real> fg(const Point& P, Parameters& pa = defaultParameters) // rot u
{
    Real x=P(1), y=P(2), z=P(3);
    Vector<Real> res(3);
    res(1)= 0.;
    res(2)=-3*a*cos(a*x)*sin(a*y)*cos(a*z);
    res(3)= 3*a*cos(a*x)*cos(a*y)*sin(a*z);
    Vector<real_t>& n=getN();
    return crossProduct(res,n);
}

Vector<Real> solex(const Point& P, Parameters& pa = defaultParameters)
{
    Real x=P(1), y=P(2), z=P(3);
    Vector<Real> res(3);
    res(1)=-2*cos(a*x)*sin(a*y)*sin(a*z);
    res(2)= sin(a*x)*cos(a*y)*sin(a*z);
    res(3)= sin(a*x)*sin(a*y)*cos(a*z);
    return res;
}

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en);
    // mesh cube using gmsh
    Cube cu(_origin=Point(0.,0.,0.), _length=1., _nnodes=11,
            _domain_name="Omega", _side_names="Gamma");
    Mesh mesh3d(cu, _tetrahedron, 1, gmsh, "mesh of the unit cube");
    Domain omega=mesh3d.domain("Omega"), gamma=mesh3d.domain("Gamma");
    // define space and unknown
    Space V(_domain=omega, _interpolation=N1_1, _name="V", _notOptimizeNumbering);
    Unknown e(V, _name="E"); TestFunction q(e, _name="q");
    // define forms
    BilinearForm aev=intg(omega, curl(e) | curl(q)) - ome*intg(omega, e | q);
    LinearForm lf=intg(omega, f | q);
    Function g(fg); g.require(_n);
```

```

LinearForm lg=intg(gamma,g|q);
// compute matrix and vector
TermMatrix A(aev, _name="A");
TermVector b = TermVector(lf)+ TermVector(lg);
// solve system
TermVector E=directSolve(A, b);

// L2 projection on P1 FE
Space W(_domain=omega, _interpolation=P1, _name="W");
TermVector EP1=projection(E, W, 3);
saveToFile("E", EP1, vtu);
// interpolation on P1 mesh
Unknown u(W, _name="u", _dim=3);
TermVector Ei=interpolate(u,omega,E,"Ei");
saveToFile("Ei", Ei, vtu);
return 0;
}

```

As Nedelec finite elements approximation are not conforming in H^1 , the solution is not continuous across elements (only tangent component is continuous). So to represent the solution, it is projected on H^1 as follows:

$$\left| \begin{array}{l} \text{find } \mathbf{E}_1 \in L^2(\Omega) \text{ such that} \\ \int_{\Omega} \mathbf{E}_1 \mathbf{w} = \int_{\Omega} \mathbf{E} \mathbf{w} \quad \forall \mathbf{w} \in L^2(\Omega). \end{array} \right.$$

Using an H^1 conforming approximation for $\mathbf{E}_1$ leads to a continuous representation of the projection. We show on the next figure the module of the field E provided by this example:




Figure 3.16: Module of the solution of the Maxwell 3D problem using Nedelec first family elements

Alternatively, the `interpolate` function provides the interpolation of E on nodes of a P1 approximation.

On the next figure, the convergence curve shows a rate convergence of L^2 error in $h^{1.3}$:




Figure 3.17: L^2 errors versus the step h for first order Nedelec first family approximation

3.7.3 3D Maxwell equations in a half waveguide using PML

Now, we consider a waveguide equipped with a PML (Perfectly Matched Layer). Just recall that such a layer allows to absorb the waves without any reflection if the layer is infinite. When the PML is bounded, there is only some weak reflections due to a reflection on the back of the PML, more and more strong as the layer becomes thin.




Figure 3.18: Maxwell half wave-guide

The strong formulation is the following ($\mu\varepsilon = 1$):

$$\left\{ \begin{array}{ll} \text{curl curl } \mathbf{E} - \omega^2 \mathbf{E} = \mathbf{f} & \text{in } \Omega_g \\ \text{curl } \mathbb{A}^{-1} \text{curl } \mathbf{E} - \omega^2 \mathbb{A} \mathbf{E} = \mathbf{f} & \text{in } \Omega_d \quad (\text{PML}) \\ \mathbf{E} \times \mathbf{n} = \mathbf{g} & \text{on } \Sigma_g \\ \text{curl } \mathbf{E} \times \mathbf{n} = 0 & \text{on } \Sigma_d \\ \mathbf{E} \times \mathbf{n} = 0 & \text{on } \Gamma_g \cup \Gamma_d \\ [\mathbf{E} \times \mathbf{n}]_{\Sigma_0} = 0, \quad [\text{curl } \mathbf{E} \times \mathbf{n}]_{\Sigma_0} = 0 & (\text{transmission condition}) \end{array} \right.$$

with $(\alpha \in \mathbb{C})$

$$\mathbb{A} = \begin{bmatrix} \frac{1}{\alpha} & 0 & 0 \\ 0 & \alpha & 0 \\ 0 & 0 & \alpha \end{bmatrix}.$$

Let us introduce

$$V_g^0 = \{\mathbf{v} \in H(\text{curl}, \Omega_g), \mathbf{v} \times \mathbf{n} = 0 \text{ on } \Gamma_g\}, \quad V_d^0 = \{\mathbf{v} \in H(\text{curl}, \Omega_d), \mathbf{v} \times \mathbf{n} = 0 \text{ on } \Gamma_d\}$$

and

$$W = \left\{ (\mathbf{v}_g, \mathbf{v}_d) \in V_g^0 \times V_d^0 \text{ s.t. } \mathbf{v}_g \times \mathbf{n} = \mathbf{v}_d \times \mathbf{n} \text{ on } \Sigma_0 \right\}.$$

The strong formulation has the following weak form:

$$\left| \begin{array}{l} \text{find } (\mathbf{E}_g, \mathbf{E}_d) \in W \text{ such that } \mathbf{E}_g \times \mathbf{n} = \mathbf{g} \text{ on } \Sigma_g \text{ and } \forall (\mathbf{v}_g, \mathbf{v}_d) \in W \text{ with } \mathbf{v}_g \times \mathbf{n} = 0 \text{ on } \Sigma_g : \\ \int_{\Omega_g} \text{curl } \mathbf{E}_g \cdot \text{curl } \mathbf{v}_g - \omega^2 \int_{\Omega_g} \mathbf{E}_g \cdot \mathbf{v}_g + \int_{\Omega_d} \mathbb{A}^{-1} \text{curl } \mathbf{E}_d \cdot \text{curl } \mathbf{v}_d - \omega^2 \int_{\Omega_d} \mathbb{A} \mathbf{E}_d \cdot \mathbf{v}_d = 0. \end{array} \right.$$

Note that we have to deal with many essential conditions, in particular the transmission condition $\mathbf{E}_g \times n = \mathbf{E}_d \times n$ on Σ_0 .

In the following example, a 'Neumann' mode of the wave-guide is used as exact solution. Using the first family Nedelec's elements (NE11 or NE12) the XLIFE++ program looks like:

```
#include "xlife++.h"
using namespace xlifepp;
// Neumann modes and their tangential traces (n=[0 0 -1])
Vector<Complex> mode_Neumann(const Point&P, Real n, Real m, Parameters& pa=defaultParameters)
{
    Real x = P(1), y = P(2), z = P(3), cst;
    Real a = pa("a"), b = pa("b"), w = pa("w");
    Vector<Complex> u(3);
    Real lambda = pi_*pi_ * ( n*n / (a*a) + m*m / (b*b) );
    if ( (n == 0) || (m == 0) ) cst = sqrt(2.)/sqrt(lambda * a * b);
    else cst = 2./sqrt(lambda * a * b);
    Complex beta = sqrt(Complex(w*w-lambda));
    u(1) = - m*pi_/b * cst * exp(i_*beta*z) * cos(n*pi_*x/a) * sin(m*pi_*y/b);
    u(2) =  n*pi_/a * cst * exp(i_*beta*z) * sin(n*pi_*x/a) * cos(m*pi_*y/b);
    return u;
}
Vector<Complex> nug_mode_Neumann(const Point&P, Real n, Real m, Parameters& pa=defaultParameters)
{
    Vector<Complex> ru = mode_Neumann(P,n,m,pa);
    Complex t=ru(1); ru(1)=ru(2); ru(2)=-t;
    return ru;
}
Vector<Complex> u_exa(const Point&P, Parameters& pa=defaultParameters)
{
    return mode_Neumann(P,1,0,pa);
}
Vector<Complex> nug_u_exa(const Point&P, Parameters& pa=defaultParameters)
{
    return nug_mode_Neumann(P,1,0,pa);
}
// PML matrices
xlifepp::Matrix<Complex> A_alpha(const Point&P, Parameters& pa=defaultParameters)
{
    Complex alpha = pa("alpha");
    xlifepp::Matrix<Complex> A(3,3);
    A(1,1)=1./alpha; A(2,2)=1./alpha; A(3,3)=alpha;
    return A;
}
xlifepp::Matrix<Complex> A_alpha_inv(const Point&P, Parameters& pa=defaultParameters)
{
    Complex alpha = pa("alpha");
    xlifepp::Matrix<Complex> A(3,3);
    A(1,1)=alpha; A(2,2)=alpha; A(3,3)=1./alpha;
    return A;
}
// null function
Vector<Real> f0 (const Point&P, Parameters& pa=defaultParameters )
{
    return Vector<Real>(3);
}

//----- main programm -----
int main(int argc, char** argv)
{
    init(argc, argv, _lang=en);
    // Geometric data
    Real a=1, b=1, w=sqrt(1.25)*pi_; // section lengths
    Real h=3., hp=2.; // waveguide length and PML length
    Real dx=2./10.; // mesh step
    Complex alpha=exp(- i_*pi_/4); // PML coefficient
    // mesh waveguide using gmsh
    Cuboid
    C_a(_xmin=0., _xmax=a, _ymin=0., _ymax=b, _zmin=-h, _zmax=0., _hsteps=dx, _domain_name="Omega_g",
        _side_names=Strings("Sigma_g", "Sigma_0", "Gamma", "Gamma", "Gamma", "Gamma")),
    C_b(_xmin=0., _xmax=a, _ymin=0., _ymax=b, _zmin=0, _zmax=hp, _hsteps=dx, _domain_name="Omega_d",
        _side_names=Strings("Sigma_0", "Sigma_d", "Gamma", "Gamma", "Gamma", "Gamma"));
```

```

Mesh mail3d(C_a+C_b, _tetrahedron, 1, _gmsh);
Domain Omega_g=mail3d.domain("Omega_g"), Omega_d=mail3d.domain("Omega_d"),
    Sigma_0=mail3d.domain("Sigma_0"), Sigma_g=mail3d.domain("Sigma_g"),
    Gamma =mail3d.domain("Gamma");
Sigma_g.setNormalOrientation (_outwardsDomain, Omega_g);
Sigma_0.updateParentOfSideElements();
Parameters pars;
pars<<Parameter(a, "a")<<Parameter(b, "b")<<Parameter(w, "w")<<Parameter(alpha, "alpha");
// Construct Nedelec Spaces (order 1 : NE11 or 2 : NE12)
Space Vg(_domain=Omega_g, _interpolation=NE1_1, _name="Hrot_Ned_g", _optimizeNumbering);
Unknown ug(Vg, _name="ug"); TestFunction vg(ug, _name="vg");
Space Vd(_domain=Omega_d, _interpolation=NE1_1, _name="Hrot_Ned_d", _optimizeNumbering);
Unknown ud(Vd, _name="ud"); TestFunction vd(ud, _name="vd");
// Function data
Function uex(u_exa, pars), nugux(nug_u_exa, pars), fzero(f0, pars);
Function fA(A_alpha, pars), fAinv(A_alpha_inv, pars);
nugux.require(_n);
// Build system and solve it
BilinearForm auv = intg(Omega_g, rot(ug)|rot(vg)) - w*w*intg(Omega_g, ug|vg)
    + intg(Omega_d, fAinv*rot(ud)|rot(vd)) - w*w*intg(Omega_d, fA*ud|vd);
LinearForm bv = intg(Omega_g, fzero|vg) + intg(Omega_d, fzero|vd);
EssentialConditions ecs = (ncross(ug)|Gamma=0)&(ncross(ud)|Gamma=0)&(ncross(ug)|Sigma_g=nugux)
    & (ncross(ud)-ncross(ug)|Sigma_0=0);
TermMatrix A(auv, ecs, _name="A");
TermVector B(bv, _name="B");
TermVector U = directSolve(A,B);
//Project solution on Lagrange spaces P1 (or P2 if NE12 used) and export solution
Space Wg(_domain=Omega_g, _interpolation=P1, _name="Wg");
Unknown upg(Wg, _name="upg", _dim=3); TestFunction vpg(upg, _name="vpg");
Space Wd(_domain=Omega_d, _interpolation=P1, _name="Wd");
Unknown upd(Wd, _name="upd", _dim=3); TestFunction vpd(upd, _name="vpd");
TermVector Ug = projection(U(ug), Wg, 3), Ud = projection(U(ud), Wd, 3);
TermVector Up = Ug + Ud; Up.name("Up");
TermVector Uexag(upg, Omega_g, uex), Uexad(upd, Omega_d, uex);
TermVector Uexa = Uexag + Uexad; Uexa.name("Uexa");
saveToFile("solMaxwellPML", Uexa, Up, _vtu);
//Compute L2 error on Omega_g (ug) in Nedelec space
TermMatrix M(intg(Omega_g, ug|vg), _name="M");
TermVector Urot = projection(Uexag, Vg, 1); //projection on Nedelec space
TermVector E1 = Urot - U(ug);
Real er=sqrt(abs((M*E1|E1))), norm=sqrt(abs((M*Urot|Urot)));
theCout<<"L2 error (projection) = "<<er<<eol;
theCout<<"relative L2 error (projection) : " <<100*er/norm<<"% \n"<<eol;
return 0;
}

```




Figure 3.19: Examples of solution of Maxwell equation in a half wave-guide using PML and Nedelec first family approximations

3.8 3D Helmholtz problem using single layer potential integral equation

XLiFE++ is also able to deal with integral equation. This example illustrates the computation of the acoustic scattering by a sphere:

$$\begin{cases} \Delta u + k^2 u = 0 & \text{in } \Omega = \mathbb{R}^3 / B(0, R) \\ u = -u_{inc} & \text{on } S \end{cases}$$

Using single layer potential leads to the integral equation:

$$\int_S G(x, y) p(x) dx = -u_{inc} \quad \text{on } S$$

where G is the Green function of the Helmholtz equation:

$$G(x, y) = \frac{e^{ik|x-y|}}{4\pi|x-y|}.$$

We deal with the variational formulation in $V = H^{\frac{1}{2}}(S)$:

$$\left| \begin{array}{l} \text{find } p \in V \text{ such that} \\ \int_S \int_S p(x) G(x, y) \bar{q}(y) dx dy = - \int_S u_{inc} \bar{q} \quad \forall q \in V. \end{array} \right.$$

The solution u is get from potential p from the integral representation:

$$u(x) = \int_S G(x, y) p(y) dy.$$

This example has been implemented in XLIFE++ using a P^0 Lagrange interpolation:

```
#include "xlife++.h"
using namespace xlifepp;

// incident plane wave
Complex uinc(const Point& p, Parameters& pa = defaultParameters)
{
    Real kx=pa("kx"), ky=pa("ky"), kz=pa("kz");
    Real kp=kx*p(1)+ky*p(2);
    return exp(i_*kp);
}

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en); // mandatory initialization of xlifepp
    // define parameters and functions
    Parameters pars;
    pars << Parameter(1., "k"); // wave number k
    pars << Parameter(1., "kx") << Parameter(0., "ky") << Parameter(0., "kz"); // kx, ky, kz
    pars << Parameter(1., "radius"); // disk radius
    Kernel G = Helmholtz2dKernel(pars); // load Helmholtz2D kernel
    Function finc(uinc, pars); // define right hand side function
    Function scatSol(scatteredFieldDiskDirichlet, pars); // exact solution

    // meshing the unit disk
    Number npa=16; // nb of points by diameter of disk
    Disk sp(_center=Point(0., 0.), _radius=1, _nnodes=npa, _domain_name="disk");
    Mesh mS(sp, segment, 1, gmsh);
    Domain disk = mS.domain("disk");

    // Lagrange P0 space and unknown
    Space V1(_domain=disk, _interpolation=P1, _name="V1", _notOptimizeNumbering);
    Unknown u1(V1, _name="u1"); TestFunction v1(u1, _name="v1");

    // form definitions
    IntegrationMethods ims(_method=Duffy, _order=5,
        _quad=GaussLegendre, _order=5, _bound=1.,
        _quad=GaussLegendre, _order=4, _bound=2.,
        _quad=GaussLegendre, _order=3);
    BilinearForm blf0=intg(disk, disk, u1*G*v1, _method=ims);
    LinearForm fv0 = -intg(disk, finc*v1);

    // compute matrix and right hand side and solve system
    TermMatrix A0(blf0, _storage=denseDual, _name="A0");
    TermVector B0(fv0, _name="B0");
    TermVector U0 = directSolve(A0, B0);

    // integral representation on x plane (far from disk), using P1 nodes
    Number npp=20, npc=8*npp/10;
    Real xm=4., eps=0.0001;
    Point C1(0., -xm), C2(0., xm), C3(0., -xm);
    SquareGeo sqx(_center=Point(0., 0.), _length=4., _nnodes=npp, _domain_name="Omega");
    Disk dx(_center=Point(0., 0.), _radius=1.25, _nnodes=npc);
    Mesh mx0(sqx-dx, triangle, 1, gmsh);
    Domain planx0 = mx0.domain("Omega");
    Space Wx(_domain=planx0, _interpolation=P1, _name="Wx", _notOptimizeNumbering);
    Unknown wx(Wx, _name="wx");
    TermVector U0x0=integralRepresentation(wx, planx0, intg(disk, G*u1), U0);
```

```

TermMatrix Mx0(intg(planx0, wx*wx), _name="Mx0");

// compare to exact solution
TermVector solx0(wx, planx0, scatSol);
TermVector ec0x0=U0x0 - solx0;
theCout << "L2 error on x=0 plane: " << sqrt(abs((Mx0*ec0x0)|ec0x0)) << endl;

// export solution to file
saveToFile("U0", U0, vtu);
saveToFile("U0x0", U0x0, vtu);
return 0;
}

```




Figure 3.20: Solution of the 3D Helmholtz problem using single layer BEM on the unit sphere

3.9 2D Helmholtz problem coupling FEM and integral representation

We want to solve the acoustic diffraction of a plane wave on the disk of radius 1, with the boundary Γ :

$$\begin{cases} \Delta u + k^2 u = 0 & \text{in } \mathbb{R}^2 / D \\ \partial_n u = g & \text{on } \Gamma \text{ (} n \text{ the outward normal)} \end{cases}$$

where $g = \partial_n(e^{ikx})$.

Let Ω be a domain that strictly surrounding the disk D and Σ its boundary. We have to point out that in this case, we use normals going outside the domain of computation Ω but then the normal on the obstacle (defined on Γ) is going inside the obstacle, that is opposite to usual case (see Figure 3.21). Then, because of the normal inverted, the solution u may be represented by the integral representation formula (G is the Green function related to the 2D Helmholtz equation in free space):

$$\forall x \in \Sigma, \quad u(x) = - \int_{\Gamma} \partial_{n_y} G(x, y) u(y) dy + \int_{\Gamma} G(x, y) \partial_{n_y} u(y) dy \quad (3.3)$$

say, because the boundary condition:

$$u(x) = - \int_{\Gamma} \partial_{n_y} G(x, y) u(y) dy + \int_{\Gamma} G(x, y) g(y) dy.$$

n_y is the outward normal (to Ω not the obstacle) on Γ and n_x will denote the outward normal on Σ . Now matching values and normal derivative on Σ , we introduce the boundary condition:

$$(\partial_{n_x} + \lambda)u(x) = -(\partial_{n_x} + \lambda) \int_{\Gamma} \partial_{n_y} G(x, y) u(y) dy + (\partial_{n_x} + \lambda) \int_{\Gamma} G(x, y) g(y) dy$$

that reads, because G is not singular on $\Gamma \times \Sigma$:

$$\begin{aligned} (\partial_{n_x} + \lambda)u(x) = & - \int_{\Gamma} \partial_{n_x} \partial_{n_y} G(x, y) u(y) dy - \lambda \int_{\Gamma} \partial_{n_y} G(x, y) u(y) dy \\ & + \int_{\Gamma} \partial_{n_x} G(x, y) g(y) dy + \lambda \int_{\Gamma} G(x, y) g(y) dy = \mathcal{R}_{\lambda}(u)(x) \end{aligned}$$

Using this exact boundary condition, if $\text{Im}(\lambda) \neq 0$ the initial problem is equivalent to:

$$\begin{cases} \Delta u + k^2 u = 0 & \text{in } \Omega \\ \partial_n u = g & \text{on } \Gamma \\ (\partial_{n_x} + \lambda)u = \mathcal{R}_{\lambda}(u) & \text{on } \Sigma \end{cases}$$

Its variational formulation in $V = H^1(\Omega)$ is:

$$\left| \begin{array}{l} \text{find } u \in V \text{ such that } \forall v \in V \\ \int_{\Omega} \nabla u \cdot \nabla \bar{v} - k^2 \int_{\Omega} u \bar{v} + \lambda \int_{\Sigma} u \bar{v} + \int_{\Sigma} \int_{\Gamma} u(y) \partial_{n_x} \partial_{n_y} G(x, y) \bar{v}(x) + \lambda \int_{\Sigma} \int_{\Gamma} u(y) \partial_{n_y} G(x, y) \bar{v}(x) \\ = \int_{\Gamma} g \bar{v} + \int_{\Sigma} \int_{\Gamma} g(y) \partial_{n_x} G(x, y) \bar{v}(x) + \lambda \int_{\Sigma} \int_{\Gamma} g(y) G(x, y) \bar{v}(x). \end{array} \right.$$

Considering the geometrical configuration:




Figure 3.21: Geometrical configuration for the FEM-Integral Representation problem. The normal on Γ is going inside the obstacle (to point outside Ω).

the variational formulation is implemented as follows:

```
#include "xlife++.h"
using namespace xlifepp;

Complex data_g(const Point& P, Parameters& pa = defaultParameters)
{
    Real x=P(1), k=pa("k");
    Vector<Complex> g(2, 0.);
    g(1) = i_*k*exp(i_*k*x);
    return dot(g, P/norm2(P)); //dr(e^{ikx})
}

Complex u_inc(const Point& P, Parameters& pa = defaultParameters)
{
    Real x=P(1), k=pa("k");
    return exp(i_*k*x);
}
```

```

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en); // mandatory initialization of xlifepp
    //parameters
    Number nh = 10; // number of elements on Gamma
    Real h=2*pi_/nh; // size of mesh
    Real re=1.+2*h; // exterior radius
    Number ne=Number(2*pi_*re/h); // number of elements on Sigma
    Real l = 4*re; // length of exterior square
    Number nr=Number(4*l/h); // number of elements on exterior square
    Real k= 4, k2=k*k; // wavenumber
    Parameters pars;
    pars << Parameter(k, "k") << Parameter(k2, "k2");
    Kernel H=Helmholtz2dKernel(pars);
    Function g(data_g, pars);
    Function ui(u_inc, pars);
    //Mesh and domains definition
    Disk d1(_center=Point(0., 0.), _radius=1, _nnodes=nh, _side_names=Strings(4, "Gamma"));
    Disk d2(_center=Point(0., 0.), _radius=re, _nnodes=ne, _domain_name="Omega",
        _side_names=Strings(4, "Sigma"));
    SquareGeo sq(_center=Point(0., 0.), _length=l, _nnodes=nr, _domain_name="Omega_ext");
    Mesh mesh(sq+(d2-d1), triangle, 1, gmsh);
    Domain omega=mesh.domain("Omega");
    Domain sigma=mesh.domain("Sigma");
    Domain gamma=mesh.domain("Gamma");
    Domain omega_ext=mesh.domain("Omega_ext"); //for integral representation
    sigma.setNormalOrientation(_outwardsDomain, omega); //outwards normals
    gamma.setNormalOrientation(_outwardsDomain, omega);

    //create P2 Lagrange interpolation
    Space V(_domain=omega, _interpolation=P2, _name="V");
    Unknown u(V, _name="u"); TestFunction v(u, _name="v");
    // create bilinear form and linear form
    Complex lambda=-i_*k;
    BilinearForm auv =
        intg(omega, grad(u) | grad(v)) - k2*intg(omega, u*v) + lambda*intg(sigma, u*v)
        + intg(sigma, gamma, u*(grad_x(H) | _nx) | _ny)*v)
        + lambda*intg(sigma, gamma, u*(grad_y(H) | _ny)*v);
    BilinearForm alv =
        intg(sigma, gamma, u*(grad_x(H) | _nx)*v) + lambda*intg(sigma, gamma, u*H*v);
    TermMatrix A(auv), ALV(alv);
    TermVector B(intg(gamma, g*v));
    TermVector G(u, gamma, g);
    B+=ALV*G;
    //solve linear system AU=F
    TermVector U=directSolve(A, B);
    saveToFile("U.vtk", U, vtk);
    //integral representation on omega_ext
    Space Vext(_domain=omega_ext, _interpolation=P2, _name="Vext", _notOptimizeNumbering);
    Unknown uext(Vext, _name="uext");
    TermVector Uext =
        -integralRepresentation(uext, omega_ext, intg(gamma, (grad_y(H) | _ny)*U))
        + integralRepresentation(uext, omega_ext, intg(gamma, H*G));
    saveToFile("Uext.vtk", Uext, vtk);
    //total field
    TermVector Ui(u, omega, ui), Utot=Ui+U;
    TermVector Uixt(uext, omega_ext, ui), Utotext=Uixt+Uext;
    saveToFile("Utot.vtk", Utot, vtk);
    saveToFile("Utotext.vtk", Utotext, vtk);
    return 0;
}

```

In the beginning, some geometric parameters used to design crown surrounded by a square, are given. Next the mesh is generated using gmsh mode and the geometrical domains are get from the mesh. The normal orientations are chosen in order to have outwards normals to the crown omega.

Then a P2 Lagrange space over the elements of the crown omega is constructed and all bilinear and linear forms involved in variational form are defined. Then the TermMatrix and TermVector are computed and the problem is solved using a direct method (Umfpack if it is installed, LU factorization else), that leads to the solution U in the crown omega.

Finally, using integral representation formula 3.3, the solution is computed in the exterior domain omega_ext. The vectors U and Uext are diffracted fields. To get total field, the incident field has to be added to the diffracted field. This is the final job that it is done.

The real part of the total field computed is presented on the figure 3.22.




Figure 3.22: 2D Helmholtz diffraction problem using FE-IR method: real part of the total field

3.10 2D Helmholtz problem coupling FEM and BEM

We want to solve the acoustic propagation of a plane wave in a heterogeneous medium. In order to do that, we distinguish a domain Ω that is heterogeneous, its boundary Γ and the exterior domain Ω_{ext} that is homogeneous (see Figure 3.23).




Figure 3.23: Domains for computation: Ω the heterogeneous medium, Ω_{ext} the homogeneous exterior domain and $\Gamma = \partial\Omega$.

We solve:

$$\begin{cases} \Delta u(x) + k^2 \eta^2(x) u(x) = 0 & \text{in } \mathbb{R}^2 \\ u(x) = -u_i(x) & \text{on } \Gamma \end{cases}$$

with $\eta(x) = 1$ in Ω_{ext} , and $\eta(x)$ that can vary in Ω , and finally with $u_i = e^{ikx}$.
We will use: $\Omega = [-0.5, 0.5]^2$ and

$$\eta(x) = \begin{cases} \exp(-(x_1^2 - 0.25) * (x_2^2 - 0.25) / (2. * 0.05)), & \text{when } \max(x_1, x_2) < 0.5. \\ 1 & \text{otherwise.} \end{cases}$$




Figure 3.24: $\eta(x)$ in $\Omega \cup \Omega_{\text{ext}}$.

We decompose the problem in a coupled system of two equations:

- in the FEM part, the solution solves the following equation:

$$\Delta u + k^2 \eta^2 u = 0$$

which gives the variational formulation:

$$\left| \begin{array}{l} \text{Find } u \in H^1(\Omega) \text{ such that :} \\ \int_{\Omega} \nabla u(x) \cdot \nabla \bar{v}(x) dx - k^2 \int_{\Omega} \eta^2(x) u(x) \bar{v}(x) dx - \int_{\Gamma} \lambda(x) \bar{v}(x) dx = 0, \quad \forall v \in H^1(\Omega) \end{array} \right. \quad (3.4)$$

with $\lambda = \frac{\partial u}{\partial n}$ is the normal trace of u on Γ .

- in the BEM part, we solve:

$$\begin{cases} \Delta u + k^2 u = 0 & \text{in } \Omega_{\text{ext}} \\ u = -u_i & \text{on } \Gamma. \end{cases} \quad (3.5)$$

The scattered field verifies:

$$u_s(x) = -S_{\Gamma} \lambda(x) + K_{\Gamma} u(x), x \in \Omega_{\text{ext}}, \quad (3.6)$$

with u the total field solution of the equation and λ the normal trace of u on Γ , S_{Γ} and K_{Γ} are the single and double layer boundary potentials:

$$\begin{aligned} S_{\Gamma} \phi(x) &= \int_{\Gamma} G(x, y) \phi(y) dy, \\ K_{\Gamma} \phi(x) &= \int_{\Gamma} \frac{\partial G(x, y)}{\partial n_y} \phi(y) dy, \end{aligned}$$

and

$$G(x, y) = \frac{e^{ik\|x-y\|}}{4\pi\|x-y\|}$$

Since $u_s = u - u_i$, and taking the limit when x goes to Γ , we obtain the integral equation:

$$\left(\frac{I}{2} - K_\Gamma\right)u(x) + S_\Gamma\lambda(x) = u_i(x), x \in \Gamma. \quad (3.7)$$

The resulting variational formulation for the BEM part is then:

$$\left| \begin{array}{l} \text{Find } u \in H^{1/2}(\Gamma) \text{ and } \lambda \in H^{-1/2}(\Gamma) \text{ such that :} \\ \frac{1}{2} \int_{\Gamma} u(x) \bar{\tau}(x) dx - \int_{\Gamma \times \Gamma} u(y) \frac{\partial G(x, y)}{\partial n_y} \bar{\tau}(x) dy dx + \int_{\Gamma \times \Gamma} \lambda(y) G(x, y) \bar{\tau}(x) dy dx \\ = \int_{\Gamma} u_i(x) \bar{\tau}(x) dx, \forall \tau \in H^{1/2}(\Gamma). \end{array} \right. \quad (3.8)$$

By adding the variational formulations relatives to the two linked problems, we obtain the final variational formulation.

Finally, the solution is obtained directly from u for the FEM part and we need to compute the integral representation to obtain u_s , the scattered field, and then to add the incident field to obtain the total field for this problem.

The last step is to merge the FEM solution in Ω and the BEM solution in Ω_{ext} to obtain a solution on the whole domain $\Omega \cup \Omega_{\text{ext}}$ to simplify the visualization.




Figure 3.25: Solution of the FEM-BEM problem.

The code of this example follows:

```
#include "xlife++.h"
using namespace xlifepp;
using namespace std;

// find = eta(x)
Real find(const Point & M, Parameters & pa = defaultParameters)
{
    Real res=1.;
    if (std::max(std::abs(M[0]), std::abs(M[1])) < 0.5)
        res=std::exp(-(M[0]*M[0]-0.25)*(M[1]*M[1]-0.25))/(2.*0.05));
```

```

    return res;
}
Real eta2(const Point & M, Parameters & pa = defaultParameters)
{
    Real tmp=find(M);
    return tmp*tmp;
}
Complex gl(const Point& M, Parameters& pa = defaultParameters)
{
    Real k=real(pa("k"));
    Point d(1., 0.);
    return exp(i_*(k*dot(M, d)));
}

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en);    // mandatory initialization of xlifepp
    verboseLevel(10);
    Real k=10.;
    // meshing
    Real hsize=(2*pi_/k)/15.;
    SquareGeo sp(_center=Point(0., 0.), _length=1., _hsteps=hsize, _domain_name="Omega",
        _side_names="Gamma");
    Mesh ml=Mesh(sp, triangle, 1, gmsh);
    Domain omega = ml.domain("Omega");
    Domain gamma = ml.domain("Gamma");
    theCout << "Mesh size = " << hsize << eol;
    theCout << "Number of Triangles = " << ml.nbOfElements() << eol;
    // defining parameter and kernel
    Parameters pars;
    pars << Parameter(k, "k");
    Kernel G=Helmholtz2dKernel(pars);
    Function finc(gl, pars);
    // defining space, unknown and test function
    Space V1(_domain=omega, _interpolation=P1, _name="V1", _notOptimizeNumbering);
    Space V0(_domain=gamma, _interpolation=P1, _name="V0", _notOptimizeNumbering);
    Unknown u1(V1, _name="u1"); TestFunction v1(u1, _name="v1");
    Unknown l0(V0, _name="l0"); TestFunction lt0(l0, _name="lt0");
    theCout << "Nb dofs BEM= " << V0.nbDofs() << " Nb dofs FEM= " << V1.nbDofs() << eol;
    // defining bilinear and linear form
    IntegrationMethods ims(_method=Duffy, _order=15, _bound=0.,
        _quad=defaultQuadrature, _order=12, _bound=1.,
        _quad=defaultQuadrature, _order=10, _bound=2.,
        _quad=defaultQuadrature, _order=8);
    BilinearForm blf=intg(omega, grad(u1)|grad(v1))-k*k*intg(omega, eta2*u1*v1)
        - intg(gamma, l0*v1) + 0.5*intg(gamma, u1*lt0)
        - intg(gamma, gamma, u1*ndotgrad_y(G)*lt0, _method=ims)
        + intg(gamma, gamma, l0*G*lt0, _method=ims);
    LinearForm lf=intg(gamma, finc*lt0);
    // computing FEM/BEM matrix and right hand side vector
    TermMatrix lhs(blf, _name="lhs");
    TermVector rhs(lf);
    // solving linear system using direct method
    TermVector sol=directSolve(lhs, rhs);

    // Representing the solution FEM and BEM
    SquareGeo Sint(_center=Point(0., 0.), _length=1, _hsteps=hsize, _domain_name="S_int");
    SquareGeo Sext(_center=Point(0., 0.), _length=3, _hsteps=1.5*hsize, _domain_name="S_ext");
    Mesh mrep(Sext+Sint, _triangle, 1, gmsh);
    Domain S_ext=mrep.domain("S_ext"), S_int=mrep.domain("S_int");
    Domain S=merge(S_ext, S_int, "S");
    Space Vrep(_domain=S, _interpolation=P1, _name="Vrep", _notOptimizeNumbering);
    Unknown ur(Vrep, _name="ur");

```

```

Function Find(find, pars);
TermVector findex(ur, S, Find);
saveToFile("findex", findex, vtu); // Representing eta
TermVector Uint=interpolate(ur, S_int, sol(u1)); // FEM solution (total field)
saveToFile("Uint", Uint, vtu);

// Representing of the BEM part
IntegrationMethods imr(_quad=GaussLegendre, _order=20, _bound=1.,
                        _quad=GaussLegendre, _order=10, _bound=2.,
                        _quad=GaussLegendre, _order=5);

TermVector Uext =
- integralRepresentation(ur, S_ext, intg(gamma, G*sol(10), _method=imr))
+ integralRepresentation(ur, S_ext, intg(gamma, ndotgrad_y(G)*sol(u1), _method=imr));

TermVector Uinc(ur, S_ext, findc);
saveToFile("Uinc", Uinc, vtu); // Incident field
saveToFile("Uext", Uext, vtu); // scattered field in exterior domain
TermVector Uext_t = Uext + Uinc;
saveToFile("Uext_t", Uext_t, vtu); // Total field in exterior domain
TermVector U=merge(Uint, Uext_t); // Merged FEM and BEM solutions
saveToFile("U", U, vtu);
theCout << "Program finished" << eol;
return 0;
}

```

3.11 3D Maxwell problem using EFIE

Solving diffraction of an electromagnetic plane wave on a obstacle using BEM is more intricate. Indeed, it is a vector problem and it involves Raviart-Thomas elements. We show how XLIFE++ can deal easily with.

Let Γ be the boundary of a bounded domain Ω of $\mathbb{R}^3$, we want to solve the Maxwell problem on the exterior domain Ω_e :

$$\begin{cases} \operatorname{curl} \mathbf{E} - i k \mathbf{H} = 0 & \text{in } \Omega_e \\ \operatorname{curl} \mathbf{H} + i k \mathbf{E} = 0 & \text{in } \Omega_e \\ \mathbf{E} \times \mathbf{n} = 0 & \text{on } \Gamma \\ \lim_{|x| \rightarrow \infty} \left((\mathbf{H} - \mathbf{H}_{inc}) \times \frac{x}{|x|} - (\mathbf{E} - \mathbf{E}_{inc}) \right) = 0 & \text{(Silver-Muller condition)} \end{cases}$$

where $(\mathbf{E}_{inc}, \mathbf{H}_{inc})$ is an incident field (a solution of Maxwell equation in free space), for instance a plane wave.

The EFIE (Electric Field Integral Equation) consists in finding the potential $\mathbf{J}$ in the space

$$H_{\operatorname{div}}(\Gamma) = \{\mathbf{V} \in L^2(\Gamma)^3, \mathbf{V} \cdot \mathbf{n} = 0, \operatorname{div}_{\Gamma} \mathbf{V} \in L^2(\Gamma)\}$$

such that, $\forall \mathbf{V} \in H_{\operatorname{div}}(\Gamma)$

$$k \int_{\Gamma} \int_{\Gamma} \mathbf{J}(y) G(x, y) \cdot \mathbf{V}(x) - \frac{1}{k} \int_{\Gamma} \int_{\Gamma} \operatorname{div}_{\Gamma} \mathbf{J}(y) G(x, y) \operatorname{div}_{\Gamma} \mathbf{V}(x) = - \int_{\Gamma} \mathbf{E}_{inc} \cdot \mathbf{V}$$

where G is the Green function related to the Helmholtz 3D problem in free space.

This equation has a unique solution, except for a discrete set of wavenumbers corresponding to the resonance frequencies of the cavity Ω .

Using the Stratton-Chu representation formula, the scattered electric field may be reconstructed in Ω_e :

$$\mathbf{E}(x) = \mathbf{E}_{inc}(x) + \frac{1}{k} \int_{\Gamma} \nabla_x G(x, y) \operatorname{div}_{\Gamma} \mathbf{J}(y) + k \int_{\Gamma} G(x, y) \mathbf{J}(y).$$

This problem is implemented in XLIFE++ as follows:

```
#include "xlife++.h"
using namespace xlifepp;
Vector<complex_t> data_incField(const Point& P, Parameters& pars)
{
    Vector<real_t> incPol(3, 0.); incPol(1)=1.; Point incDir(0., 0., 1.) ;
    Real k = pars("k");
    return incPol * exp(i_*k * dot(P, incDir));
}

Vector<complex_t> uinc(const Point& P, Parameters& pars)
{
    Vector<real_t> incPol(3, 0.); incPol(1)=1.; Point incDir(0., 0., 1.) ;
    Real k = pars("k");
    return incPol*exp(i_*k * dot(P, incDir));
}

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en);
    // define parameters and functions
    Real k= 1, R=1.; Parameters pars;
    pars << Parameter(k, "k") << Parameter(R, "radius");
    Kernel H = Helmholtz3dKernel(pars); // load Helmholtz3D kernel
    Function Einc(data_incField, pars); // define right hand side
    Function Uex(scatteredFieldMaxwellExn, pars);
    // meshing the unit sphere
    Number npa=15; Point O(0, 0, 0);
    Sphere sphere(_center=O, _radius=R, _nnodes=npa, _domain_name="Gamma");
    Mesh meshSh(sphere, triangle, 1, gmsh);
    Domain Gamma = meshSh.domain("Gamma");
    // define FE-RT1 space and unknown
    Space V_h(_domain=Gamma, _interpolation=RT_1, _name="Vh");
    Unknown U(V_h, _name="U"); TestFunction V(U, _name="V");
    // compute BEM system and solve it
    IntegrationMethods ims(_method=SauterSchwabIM, _order=4, _bound=0.,
        _quad=defaultQuadrature, _order=5, _bound=2.,
        _quad=defaultQuadrature, _order=3);
    BilinearForm auv = k*intg(Gamma, Gamma, U*H|V, ims)
        -(1./k)*intg(Gamma, Gamma, div(U)*H*div(V), ims);
    TermMatrix A(auv, _name="A");
    TermVector B(-intg(Gamma, Einc|V));
    TermVector J = directSolve(A, B);
    // get P1 representation of solution and export it to vtu file
    Space L_h(_domain=Gamma, _interpolation=P1, _name="Lh");
    Unknown U3(L_h, _name="U3", _dim=3); TestFunction V3(U3, _name="V3");
    TermVector JP1=projection(J, L_h, 3, _L2Projector);
    saveToFile("JP1", JP1(U3[1]), vtu);
    // integral representation on y=0 plane (excluding sphere), using P1 nodes
    Number npp=30, npc=5;
    Square sqx(_center=O, _length=20., _nnodes=npp, _domain_name="Omega");
    Disk dx(_center=O, _radius=1.2*R, _nnodes=npa);
    Mesh mx0(sqx-dx, triangle, 1, gmsh);
    mx0.rotate3d(1., 0., 0., pi_/2);
    Domain py0 = mx0.domain("Omega");
    Space Vy0(_domain=py0, _interpolation=P1, _name="Vy0", _notOptimizeNumbering);
    Unknown W(Vy0, _name="W", _dim=3);
    IntegrationMethods im(_quad=defaultQuadrature, _order=10, _bound=1., _quad=defaultQuadrature,
        _order=5);
    TermVector Uext=
        (1./k)*integralRepresentation(W, py0, intg(Gamma, grad_x(H)*div(U), _method=im), J)
        + k*integralRepresentation(W, py0, intg(Gamma, H*U, _method=im), J);
```

```

saveToFile("Uext", Uext, vtu);
// build exact solution, export to vtu file and compute error
TermVector Uexa(W, py0, Uex);
saveToFile("Uexa", Uexa, vtu);
TermMatrix M(intg(py0, W|W));
TermVector E=Uext-Uexa;
theCout << "L2 error = " << sqrt(real(M*E|E)) << endl;
return 0;
}

```

In order to build an approximated space of $H_{\text{div}}(\Gamma)$ we use the Raviart-Thomas element of order 1.

As the integrals involved in bilinear form are singular, we use here the Sauter-Schwab method to compute them when two triangles are adjacent, a quadrature method of order 5 if the two triangles are close ($0 < d(T1, T2) < 2h$) and a quadrature method of order 3 when the two triangles are far ($d(T1, T2) \geq 2h$).

Note that the unknowns in RT approximation are the normal fluxes on the edge of the triangulation. In order to plot the potential $\mathbf{J}$, we have to move to a P1 representation, say $\tilde{\mathbf{J}}$. This can be done using a L2 projection from $H_{\text{div}}(\Gamma)$ to $L^2(\Gamma)$:

$$\int_{\Gamma} \tilde{\mathbf{J}} | \mathbf{V} = \int_{\Gamma} \mathbf{J} | \mathbf{V} \quad \forall V \in L^2(\Gamma)$$

This is what is done by the XLIFE++ function `projection`.

We obtain the following potential:




Figure 3.26: 3D Maxwell problem on the unit sphere, using EFIE, potential

On the following figures, we show the approximated electric field and the exact electric field. The component E_y is not shown because it is zero.




Figure 3.27: 3D Maxwell problem on the unit sphere, using EFIE, x component




Figure 3.28: 3D Maxwell problem on the unit sphere, using EFIE, y component

3.12 2D Elasticity problem

The elasticity problem illustrates how to use vector unknown in XLiFE++:

$$\begin{cases} -\operatorname{div}(\sigma(\mathbf{u})) - \omega^2 \mathbf{u} = \mathbf{f} & \text{in } \Omega \\ \sigma(\mathbf{u}) \mathbf{n} = 0 & \text{on } \partial\Omega \end{cases}$$

For homogeneous isotropic material:

$$\sigma(\mathbf{u}) = \lambda \operatorname{div}(\mathbf{u}) \mathbb{I} + 2\mu \varepsilon(\mathbf{u}) \quad \varepsilon_{ij}(\mathbf{u}) = \partial_i u_j.$$

The variational formulation in $V = (H^1(\Omega))^3$ is:

$$\left| \begin{array}{l} \text{find } \mathbf{u} \in V \text{ such that} \\ \lambda \int_{\Omega} \operatorname{div}(\mathbf{u}) \operatorname{div}(\tilde{\mathbf{v}}) + 2\mu \int_{\Omega} \varepsilon(\mathbf{u}) : \varepsilon(\tilde{\mathbf{v}}) - \omega^2 \int_{\Omega} u \tilde{v} = \int_{\Omega} \tilde{\mathbf{f}} \cdot \tilde{\mathbf{v}} \quad \forall \mathbf{v} \in V. \end{array} \right.$$

This is implemented as follows:

```
#include "xlife++.h"
using namespace xlifepp;

// data function
Vector<Real> f(const Point& P, Parameters& pa = defaultParameters)
{ Vector<Real> F(2, 0.); F(2)=-0.005; return F;}

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en); // mandatory initialization of xlifepp

    // mesh rectangle
    Rectangle rect(_center=Point(0., 0.), _xlength=20, _ylength=2, _nnodes=Numbers(50, 5),
        _domain_name="Omega", _side_names=Strings("", "", "", "Gamma"));
    Mesh mesh2d(rect, triangle, 1, gmsh);
    Domain omega=mesh2d.domain("Omega"), Gamma=mesh2d.domain("Gamma");
    // create P1 Lagrange interpolation
    Space V(_domain=omega, _interpolation=P1, _name="V");
    Unknown u(V, _name="u", _dim=2); TestFunction v(u, _name="v");
    // create bilinear form and linear form
    Real lambda=167.06, mu=56.67, omg2=0, rho=7.86;
    BilinearForm auv = lambda*intg(omega, div(u)*div(v))
        + 2*mu*intg(omega, epsilon(u) % epsilon(v)) - omg2*intg(omega, u|v);
    LinearForm fv=intg(omega, f|v);
    EssentialConditions ecs= (u|Gamma=0);
    TermMatrix A(auv, ecs, _name="A");
    TermVector B(fv, _name="B");
    //solve linear system AX=B using direct method
    TermVector U=directSolve(A, B);
    thePrintStream<<U;
    saveToFile("U", U, vtu);

    // create the deformation of the mesh
    for (number_t i=0; i<mesh2d.nbOfNodes(); i++)
        mesh2d.nodes[i] += U.evaluate(mesh2d.nodes[i]).value<std::vector<Real>>();
    mesh2d.saveToFile("Ud", mesh);

    return 0;
}
```




Figure 3.29: Displacement and modulus of the solution of the elasticity 2D problem

3.13 2D Bilaplacian problem

The 2d bilaplacian problem illustrates how to use Morley or Argyris element in XLIFE++:

$$\begin{cases} \Delta^2 u = \mathbf{f} & \text{in } \Omega \\ u = 0 \text{ and } \nabla u \cdot \mathbf{n} = 0 & \text{on } \partial\Omega \end{cases}$$

The variational formulation in $V = \{v \in H^2(\Omega), u = 0 \text{ and } \nabla u \cdot \mathbf{n} = 0 \text{ on } \partial\Omega\}$ is:

$$\left| \begin{array}{l} \text{find } \mathbf{u} \in V \text{ such that} \\ \int_{\Omega} (\partial_{xx} u \partial_{xx} v + \partial_{yy} u \partial_{yy} v + 2\partial_{xy} u \partial_{xy} v) = \int_{\Omega} f v \quad \forall \mathbf{v} \in V. \end{array} \right.$$

The implementation in XLiFE++ using Morley elements is the following :

```
#include "xlife++.h"
using namespace xlifepp;

// data function
Real uex(const Point& P, Parameters& pa = defaultParameters)
{
    Real x=P(1), y=P(2), kp=pi_;
    Real r=sin(kp*x)*sin(kp*y);
    return r*r;
}

Real f(const Point& P, Parameters& pa = defaultParameters)
{
    Real x=P(1), y=P(2);
    Real dkp=2*k*pi_;
    Real cx=cos(dkp*x), cy=cos(dkp*y);
    return 0.25*dkp*dkp*dkp*dkp*(4*cx*cy-cx-cy);
}

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en); // mandatory initialization of xlifepp
    // mesh rectangle
    SquareGeo sq(_xmin=0, _xmax=1, _ymin=0, _ymax=1., _hsteps=0.05, _domain_name="Omega",
        _side_names="Gamma");
    Mesh mesh(sq, triangle, 1, gmsh);
    Domain omega=mesh.domain("Omega"), gamma=mesh.domain("Gamma");
    // create space
    Space V(_domain=omega, _FE_type=Morley, _order=1, _name="V");
    Unknown u(V, _name="u"); TestFunction v(u, _name="v");
    // create problem
    EssentialConditions ecs= (u|gamma == 0) & (ndotgrad(u)|gamma == 0);
    TermMatrix A(intg(omega, dxx(u)*dxx(v))+intg(omega, dyy(u)*dyy(v))+2*intg(omega,
        dxy(u)*dxy(v)), ecs);
    TermVector B(intg(omega, f*v), _name="B");
    // solve problem
    TermVector U=directSolve(A, B);
    // interpolate on P1 and export to vtu file
    Space W(_domain=omega, _interpolation=P1, _name="W", _notOptimizeNumbering);
    Unknown w(W, _name="w");
    TermVector Up1=interpolate(w, omega, U, "Up1");
    saveToFile("U", Up1, vtu);
    TermVector Uel(w, omega, uex, _name="Uel");
    TermVector Er=Up1-Uel;
    saveToFile("Er", Er, vtu);
    return 0;
}
```




Figure 3.30: Approximate solution and difference with exact solution of the biharmonic 2D problem

In order to use Argyris element in place of Morley element, replace the space definition:

```
Space V(_domain=omega, _FE_type=Argyris, _order=1, _name="V");
```

The next figure shows the L^2 convergence rate of the Morley approximation when solving the 2d biharmonic problem; in agreement with the order 2 predicting by the theory.




Figure 3.31: L^2 convergence rate of the Morley approximation

3.14 Solving wave equation

So far, only the harmonic problems were considered. Time problem may also be solved using XLife++. But there is no specific tools dedicated to. Users have to implement the time loop related to the finite difference time scheme they choose.

As an example, consider the wave equation:

$$\begin{cases} \frac{\partial^2 u}{\partial t^2} - c^2 \Delta u = f & \text{in } \Omega \times]0, T[\\ \frac{\partial u}{\partial n} = 0 & \text{in } \partial\Omega \times]0, T[\\ u(x, 0) = \frac{\partial u}{\partial t}(x, 0) = 0 & \text{in } \Omega \end{cases}$$

Using classical leap-frog scheme with time discretization $t^n = n\Delta t$, leads to (u^n approximates $u(x, t^n)$):

$$\begin{cases} u^{n+1} = 2u^n - u^{n-1} + (c\Delta t)^2 \Delta u^n + (\Delta t)^2 f^n & \text{in } \Omega, \forall n > 1 \\ \frac{\partial u^n}{\partial n} = 0 & \text{in } \partial\Omega, \forall n > 1 \\ u^0 = u^1 = 0 & \text{in } \Omega \end{cases}$$

or, in variational form, $\forall v \in V = H^1(\Omega)$:

$$\begin{cases} \int_{\Omega} u^{n+1} v = 2 \int_{\Omega} u^n v - \int_{\Omega} u^{n-1} v - (c\Delta t)^2 \int_{\Omega} \nabla u^n \cdot \nabla v + (\Delta t)^2 \int_{\Omega} f^n v & \forall n > 1 \\ u^0 = u^1 = 0 & \text{in } \Omega \end{cases}$$

When approximating space V by a finite dimension space V_h with basis $(w_i)_{i=1,p}$, the variational formulation is reinterpreted in terms of matrices and vectors as follows:

$$\begin{cases} U^{n+1} = 2U^n - U^{n-1} - \mathbb{M}^{-1} ((c\Delta t)^2 \mathbb{K} U^n - (\Delta t)^2 F^n) & \forall n > 1 \\ U^0 = U^1 = 0 & \text{in } \Omega \end{cases}$$

where

$$\mathbb{M}_{ij} = \int_{\Omega} w_i w_j, \mathbb{K}_{ij} = \int_{\Omega} \nabla w_i \cdot \nabla w_j, (F^n)_i = \int_{\Omega} f^n w_i.$$

The XLIFE++ implementation of this scheme on the unity square when using P1 Lagrange interpolation looks like ($f(x, t) = h(t)g(x)$):

```
#include "xlife++.h"
using namespace xlifepp;

Real g(const Point& P, Parameters& pa = defaultParameters)
{
    Real d=P.distance(Point(0.5, 0.5));
    Real R= 0.02;           // source radius
    Real amp= 1./(pi_*R*R); // source amplitude (constant power)
    if (d<=0.02) return amp; else return 0.;
}

Real h(const Real& t)
{
    Real a=10000, t0=0.04 ; //gaussian slope and center
    return exp(-a*(t-t0)*(t-t0));
}

int main(int argc, char** argv)
{
    init(argc, argv, _lang=en);
    // create a mesh and domain omega
    SquareGeo sq(_origin=Point(0., 0.), _length=1, _nnodes=70);
    Mesh mesh2d(sq, triangle, 1, structured);
    Domain omega=mesh2d.domain("Omega");
    // create interpolation
    Space V(_domain=omega, _interpolation=P1, _name="V");
```

```

Unknown u(V, _name="u");
TestFunction v(u, _name="v");
// define FE terms
TermMatrix A(intg(omega, grad(u)|grad(v)), _name="A"), M(intg(omega, u*v), _name="M");
TermVector G(intg(omega, g*v), _name="G");
TermMatrix L; IdltFactorize(M, L);
// leap-frog scheme
Real c=1, dt=0.004, dt2=dt*dt, cdt2=c*c*dt2;
Number nbt=200;
TermVectors U(nbt); // to store solution at t=ndt
TermVector zeros(u, omega, 0.); U(1)=zeros; U(2)=zeros;
Real t=dt;
for (Number n=2; n<nbt; n++, t+=dt)
{
    U(n+1)=2.*U(n)-U(n-1)-factSolve(L, cdt2*(A*U(n))-dt2*h(t)*G);
}
saveToFile("U", U, vtu);
return 0;
}

```

Note the very simple syntax taken into account the leap-frog scheme. The Figure 3.32 represents the solution at different instants for a constant source localized in disk with center $(0.5, 0.5)$, radius $R = 0.02$ and time excitation that is a Gaussian function. For chosen parameter $dt = 0.04$, the leap-frog scheme is stable (it satisfies the CFL condition) but dispersion effects obviously appear.




Figure 3.32: Solution of the wave equation at different instants for a constant source localized in disk with center $(0.5, 0.5)$

This chapter is devoted to the basics of C++ language required to use XLiFE++. It is addressed to people who do not know C++.

4.1 Instruction sequence

All C++ instructions (ending by semicolon) are defined in block delimited by braces:

```
{
  instruction;
  instruction;
  \ldots
}
```

Instruction block may be nested in other one:

```
{
  instruction;
  {
    instruction ;
    instruction ;
  }
  \ldots
}
```

and are naturally involved in tests, loops, ... and functions.

A function is defined by its name, a list of input argument types, an output argument type and an instruction sequence in an instruction block:

```
argout name_of_function(argin1 , argin2 , \ldots)
{
  instruction;
  instruction;
  \ldots
  return something;
}
```

The main program is a particular function returning an error code:

```
int main()
{
  \ldots
  return 0;  //no error
}
```

4.2 Variables

In C++, any variable has to be declared, say defined by specifying its type. Fundamental types are:

- Integer number: **int** (Int type in XLiFE++), **unsigned int** (Number type in XLiFE++) and **short unsigned int** (Dimen type in XLiFE++)

- Real number: **float** for single precision (32bits) or **double** (64bits) for double precision (Real type in XLIIFE++)
- Boolean: **bool** that takes `true` (1) or `false` (0) as value
- Character: **char** containing one of the standard ASCII character

All other types are derived types (pointer, reference) or classes (**Complex**, **String** for instance).

All variable names must begin with a letter of the alphabet. Do not begin by underscore (`_`) because it is used by XLIIFE++. After the first initial letter, variable names can also contain letters and numbers. No spaces or special characters, however, are allowed. Upper-case characters are distinct from lower-case characters.

A variable may be declared anywhere. When they are declared before the beginning of the main, they are available anywhere in the file where they are declared.



All variables declared in an instruction block are deleted at the end of the block.

4.3 Basic operations

The C++ provides a lot of operators. The main ones are :

- `=` : assignment
- `+`, `-`, `*`, `/` : usual algebraic operators
- `+=`, `-=`, `*=`, `/=` : operation on left variable
- `++`, `--` : to increment by 1 (`+=1`) and decrement by 1 (`-=1`)
- `==`, `!=`, `<`, `>`, `<=`, `>=`, `!` : comparison operators and negation
- `&&`, `||` : logical and, or
- `<<`, `>>` : to insert in a stream (read, write)

All these operators may work on object of a class if they have been defined for this class. See documentation of a class to know what operators it supports.

The operators `+=`, `-=`, `*=`, `/=` may be useful when they act on large structure because they, generally, do not modify their representation and avoid copy.

4.4 if, switch, for and while

The syntax of test is the following:

```
if (predicate)
{
    \ldots
}
else if (predicate2)
{
    \ldots
}
```

```
else
{
    \ldots
}
```

`else if` and `else` blocks are optional, and you can have as many `else if` blocks as you want. `predicate` is a boolean or an expression returning a boolean (*true* or *false*):

```
if ((x==3 && y<=2) || (! a>b))
{
    \ldots
}
```

For multiple choice, use the **switch** instruction:

```
switch (i)
{
    case 0:
    {
        \ldots
        break;
    }
    case 1:
    {
        \ldots
        break;
    }
    \ldots
    default :
    {
        \ldots.
    }
}
```

The **switch** variable has to be of enumeration type (integer or explicit enumeration).

The syntax of the **for** loop is the following:

```
for( initialization; end_test; incrementing sequence)
{
    \ldots
}
```

The simplest loop is:

```
for( int i=0; i< n; i++)
{
    \ldots
}
```

An other example with no initializer and two incrementing values:

```
int i=1, j=10;
for (; i< n && j>0; i++, j--)
{
    \ldots
}
```

A **for** loop may be replaced by a **while** loop:

```

int i=0;
while(i<n)
{
    \ldots
    i++;
}

```

4.5 In/out operations

The simplest way to print something on screen is to use the predefined output stream **cout** with operator <<:

```

Real x=2.25;
Number i=3;
String msg=" Xlife++ :";
cout << msg << " x=" << x << " i=" << i << eol;

```

eol is the XLIfe++ end of line. You can insert in output stream any object of a class as the operator << is defined for this class. Almost all XLIfe++ classes offer this feature.

To read information from keyboard, you have to use the predefined input stream **cin** with operator >>:

```

Real x;
Number i=3;
cin >> i >> x;

```

The program waits for an input of a real value, then for an input of integer value.

To print on a file, the method is the same except that you have to define an output stream on a file :

```

ofstream out;
out.open("myfile");
Real x=2.25;
Number i=3;
String msg=" Xlife++ :";
out << msg << " x=" << x << " i=" << i << eol;
out.close();

```

To read from a file :

```

ifstream in;
in.open("myfile");
Real x;
Number i=3;
in >> i >> x;
in.close();

```

The file has to be compliant with data to read. The default separators are white space and carriage return (end of line).

To read and write on file in a same time, use **fstream**.



All stream stuff is defined in the C++ standard template library (STL). To use it, write at the beginning of your c++ files :

```
#include <iostream>
#include <fstream>
\dots

using namespace std;
```

4.6 Using standard functions

The STL library provides some fundamental functions such as **abs**, **sqrt**, **power**, **exp**, **sin**, ... To use it, you have to include the *cmath* header file :

```
#include <cmath>
using namespace std;
\dots
double pi=4*atan(1);
double y=sqrt(x);
\dots
```

4.7 Use of classes

The C++ allows defining new types of variable embedding complex structure : say class. A class may handle some data (member) and functions (member functions). A variable of a class is called an object.

In XLiFE++, you will have only to use it, not to define new one. The main questions are : how to create an object of a class, how to access to its members and how to apply operations on it. To illustrate concepts, we will use the very simple Complex class:

```
class Complex
{
public:
float x, y;
Complex(float a=0, float b=0) : x(a), y(b) {}
float abs() {return sqrt(x*x+y*y);}
Complex& operator+=(const Complex& c)
{ x+=c.x; y+=c.y; return *this; }
\dots
};
```

Classes have special functions, called constructors, to create object. They have the name of the class and are invoked at the declaration of the object:

```
int main()
{
Complex z1;           //default constructor
Complex z2(1,0);      //explicit constructor
Complex z4(z2);       //copy constructor
Complex z5=z3;        //use copy constructor

Complex z4=Complex(0,1);
}
```

Copy constructor and operator = are always defined. When operator = is used in a declaration, the copy constructor is invoked. The last instruction uses the explicit constructor and the copy constructor. In practice,

compiler are optimized to avoid copy.

To address a member or a member function, you have to use the operator point (.):

```
int main()
{
    Complex z(0,1);
    float r=z.x;
    float i=z.y;
    float a=z.abs();
}
```

and to use operators, use it as usual:

```
int main()
{
    Complex z1(0,1), z2(1,0);
    z1+=z2;
}
```

Most of XLiFE++ user's classes have been developed to be close to natural usage.

4.8 Understanding memory usage

In scientific computing, the computer memory is often asked intensively. So its usage has to be well managed:

- Avoid copy of large structures (mainly `TermMatrix`);
- Clear large object (generally it exists a `clear` function). You do not have to delete objects, they are automatically destroyed at the end of the blocks where they have been declared !
- When it is possible, use `+=`, `-=`, `*=`, `/=` operators instead of `+`, `-`, `*`, `/` operators which induce some copies;
- In large linear combination of `TermMatrix`, do not use partial combinations which also induce unnecessary copies and more computation time.

4.9 Main user's classes of XLiFE++

For sake of simplicity, the developers choose to limit the number of user's classes and to restrict the use of template paradigm. Up to now the only template objects are `Vector` and `Matrix` to deal with real or complex vectors/matrices. The name of every XLiFE++ class begins with a capital letter.

XLiFE++ provides some utility classes (see user documentation for details) :

`String` to deal with character string

`Strings` to deal with vector of character strings

`Number` to deal with unsigned (positive) integers

`Numbers` to deal with vector of unsigned (positive) integers

`Real` to deal with floats, whatever the precision.

`Reals` to deal with vector of floats, whatever the precision.

`Complex` to deal with complexes

`Vector<T>` to deal with numerical vectors (T is a real/complex scalar or real/complex Vector)

`Matrix<T>` to deal with numerical matrices (T is a real/complex scalar or real/complex Matrix)

`RealVector`, `RealVectors`, `RealMatrix`, `RealMatrices` are aliases of previous real vectors and matrices

`Complexes`, `ComplexVector`, `ComplexVectors`, `ComplexMatrix`, `ComplexMatrices` are aliases of previous complex vectors and matrices

Point to deal with Point in 1D, 2D, 3D
Parameter structure to deal with named parameter of type Real, Complex, Integer, String
Parameters a list of parameters
Function generalized function handling a c++ function and a list of parameters
Kernel generalized kernel managing a **Function** (the kernel) and some additional data (singularity type, singularity order, ...)
TensorKernel a special form of kernel useful to DtN map

XLiFE++ also provides the main user's modelling classes:

Geometry to describe geometric objects (segment, rectangle, ellipse, ball, cylinder, ...). Each geometry has its own modelling class (**Segment**, **Rectangle**, **Ellipse**, **Ball**, **Cylinder**, ...)
Mesh mesh structure containing nodes, geometric elements, ...
Domain alias of geometric domains describing part of the mesh, in particular boundaries, and **Domains** to deal with vectors of **Domain**'s
Space class handles discrete spaces (FE space or spectral space) and **Spaces** some vectors of **Space**'s
Unknown, **TestFunction** abstract elements of space and **Unknowns**, **TestFunctions** to handle vector of **Unknown**'s and **TestFunction**'s
LinearForm symbolic representation of a linear form
BiLinearForm symbolic representation of a bilinear form
EssentialCondition symbolic representation of an essential condition on a geometric domain
EssentialConditions list of essential conditions
TermVector algebraic representation of a linear form or element of space as vector
TermVectors list of **TermVector**'s
TermMatrix algebraic representation of a bilinear form
EigenElements list of eigen pairs (eigen value, eigen vector)

5.1 The `init` function

As said in chapter 2, every program using XLiFE++ begins by a call to the `init` function, taking up to 4 key/value arguments:

`_lang` enum to set the language for print and log messages. Possible values are *en* for English, *fr* for French, *de* for German, or *es* for Spanish. Default value is *en*.

`_verbose` integer to set the verbose level. Default value is 1.

`_trackingMode` boolean to set if in the log file, you have a backtrace of every call to a XLiFE++ routine. Default value is false.

`_isLogged` boolean to activate log. Default value is false.

Furthermore, the `init` function loads functionalities linked to the trace of where such messages come from. If this function is not called, XLiFE++ cannot work !!! These parameters can also be set from dedicated command line options:

Command line options for XLiFE++ executables:

<code>-h</code>	prints the current help
<code>-j <num>, -jobs <num>, --jobs <num></code>	define the number of threads. Default is -1, meaning automatical behavior.
<code>-l <string>, -lang <string>, --lang <string></code>	define the language used for messages. Default is <i>en</i> .
<code>-vl <num>, -verbose-level <num>, --verbose-level <num></code>	define the verbose level. Default is 0.
<code>-v</code>	set the verbose level to 1.
<code>-vv</code>	set the verbose level to 2.
<code>-vvv</code>	set the verbose level to 3.

To deal with these command line options, you just have to give standard arguments to the `init` function:

```
init(argc, argv, _lang=fr);
```

5.2 Managing your own options

XLiFE++ provides an `Options` object to manage user options, that can be read from the command line or from files.

What is an option ? An option has:

- A name, that will be used to get the value of an option, as for a `Parameter`.



An option name cannot start with a sequence of "-" characters. First characters must be alphanumerical.

- One or several keys used to define an option (key in a file or command line option). A key cannot be used twice, and some keys are forbidden, due to some keys dedicated to system options (see section 2.2 about the `init` function).

- A value, that can be scalar (`Int`, `Number`, `Real`, `Complex` or `String`) or vector (`Ints`, `Numbers`, `Reals`, `Complexes` or `Strings`). This is the default value of the option and determines its data type. For vector types, size is not relevant.

This class provides a default constructor. In order to define a user option, you can use the function `addOption`:

```
Options opts;
opts.addOption("t1", 1.2);
opts.addOption("t2", "tata");
opts.addOption("t3", "-t", Complex(0.,1.));
opts.addOption("t4", Strings("-tu","-tv"), Reals(1.1, -2.4, 0.7));
opts.addOption("t5", Strings("tata","titi"));
```

To parse options from file and or command line arguments, you may use one of the following line:

```
opts.parse(argc, argv);
String filename="param.txt";
opts.parse(filename);
opts.parse(filename, argc, argv);
```

where `argc` and `argv` are the arguments of the main function dedicated to command line arguments of the executable. When using both filename and command line arguments, the latter are given priority.

Let's now talk about how use options in a file or command-line.

First option is named "t1". So it can be used through the key "t1", "-t1" or "--t1". Fourth option is named "t4" and has 2 aliases: "-tu" et "-tv". So it can be used through the key "t4", "-t4", "--t4", "-tu" or "-tv".

```
./exec --t1 2.5 -t2 tutu -t3 2.5 -0.1 -t4 2.2 -4.8 1.4 -t5 "tutu" toto "ta ta" titi
```

When passing options from command line, you consider a `Complex` value as 2 `Real` values. Furthermore, quotes are not necessary for `String` values, unless the value contains special characters such as blank spaces, escape characters, ... Here is an example of ASCII file used to define options:

```
t1 3.7
t2 "ti ti"
t3 (2.5,-0.2)
t4 2.5 -2 3.4 4.7
t5 "titi" tutu "ta ta" toto
```

When passing options from a file, a `Complex` value is now written as a complex, namely real part and imaginary part are delimited by a comma and inside parentheses. As for command-line case, quotes are not necessary for `String` values, unless the value contains special characters such as blank spaces, escape characters, ...

5.3 Using XLIFE++ with global parameters

5.3.1 Global constants and objects

Some global constants are available and may be useful to you:

pi_ the π constant with the `Real` precision

i_ the imaginary number with the `Complex` precision

theEulerConst the Euler-Mascheroni constant

theTolerance the precision used to convergence in norms

theEpsilon the machine epsilon

Some usefulw objets are also available:

thePrintStream_ the dedicated file stream to the print.txt file generated while executing a program using XLIFE++.

theCout Using this stream object means using either the standard output stream `std::cout` and the previous file stream `thePrintStream_`. This is the reason why we recommend you to always use this stream.

col An alias to `std::endl`

5.3.2 Multi-threading

XLIFE++, when configured with OPENMP, uses automatically multi-threading. We saw that the `init` function enables you to define the number of threads that will be used, but you can also change the number of threads everywhere you want in your program. To modify its value, use the `numberOfThreads` function:

```
numberOfThreads(24);  
\ldots  
numberOfThreads(12);  
\ldots
```

When used without argument, the routine returns the number of threads currently defined.



In multithreading environment, the stream `theCout` prints only on the thread 0.

5.3.3 The verbosity

We saw that the `init` function enables you to define the verbosity, but you can also change the verbose level everywhere you want in your program. To modify its value, use the `verboseLevel(...)` function:

```
verboseLevel(10);  
\ldots  
verboseLevel(0);  
\ldots
```

When the verbose level is set to 0, nothing is printed except the errors and warnings.



In multithreading environment, it may appear other print files (`printxx.txt`) corresponding to outputs of each thread.

The *geometry* library collects all the general classes and functionalities about geometries, meshes, geometrical domains and geometrical elements.

In order to handle a finite element mesh, XLIFE++ provides the class *Mesh*. Thus, the user must first create an object of this type, which can be done mainly in two ways:

- Reading a file containing the description of the geometry,
- or using XLIFE++ internal (simple) meshing tools.

The internal tools are designed to provide the user with a mesh in a straightforward way. They only deal with simple geometries. Complicated geometries need to use a specific software that stores the geometrical description of the mesh into a file.

In this section we will see:

1. How to define geometries, canonical ones and more complicated ones: section 6.1
2. How to apply transformations on geometries (rotations, translations, ...): section 6.2
3. How to extrude geometries (by translation or rotation): section 6.3
4. How to define a mesh from a geometry: section 6.4
5. How to transform a mesh: section 6.9
6. How to define a mesh from a file: section 6.8
7. How to use geometrical domains: section 6.10

6.1 Defining geometries

To define a geometry object, you will use a constructor:

```
Pyramid pyr(key1 = val1, key2 = val2, \ldots);
```

There are a lot of available parameters (or keys) for each geometry object. You can give them in any order. Some keys are parts of a group of keys. When you use a group of keys, you have to set every key of the group. For instance, in the following example, to define a triangle, you have to give the three vertices of the triangles with the keys *_v1*, *_v2*, *_v3*. You must not forget one of them.

```
Triangle tri(_v1 = Point(0.,0.), _v2 = Point(1.,0.), _v3 = Point(0.,1.), \ldots);
```

There are 3 kind of parameters (plus 1 single parameter):

- First, you have parameters dedicated to geometry definition. This part is different for each geometry and will be explained in following subsections.

- Secondly you have 2 parameters dedicated to mesh parameters such as the number of nodes on each edge of the geometry (always greater than 2) or the local mesh step on each vertex of the geometry (fitted to the gmsh mesh generator). For this 2 kinds of arguments, you will have the choice to give a value per edge (or vertex), or a smaller number of values according to properties of symmetry of the geometry, or a common value for each edge (or vertex). To set the number of nodes on each edge, you will have to use the **_nnodes** key. To set the local mesh step on each vertex, you will have to use the **_hsteps** key. These parameters are optional and only one of them is to be used.

```
Triangle tri(_v1 = Point(0.,0.), _v2 = Point(1.,0.), _v3 = Point(0.,1.), _nnodes =
Numbers(11,15,11));
```

What is the difference between **_nnodes** and **_hsteps** ? It is as in the GMSH documentation.

_nnodes When you use this parameter, you set the number of nodes of a regular mesh on an edge. As a result, the mesh step is constant on the edge. Using this parameter, you can refine a mesh near an edge.

_hsteps When you use this parameter, you set the value of the mesh step near a vertex. If the mesh step is the same for both vertices of the edge, then this is a regular mesh (equivalent to define the number of nodes in this case). If the mesh step is different on vertices of an edge, it varies progressively to fit the expected value on vertices. Using this parameter, you can refine a mesh near a vertex.

- Thirdly you have parameters dedicated to definition of geometrical domains. These keys are all optional:

_domain_name is used to set the name of the main domain of the geometry. The main domain depends on the type of mesh (if you mesh a cube with triangles, the main domain will be the whole border, whereas with tetrahedra, it is the cube itself).

_side_names is used to set the names of every side domain. You can give a vector of strings (**Strings** object) or a single **String** if it is the same name for every side domain.

Default values are empty strings. When a domain has an empty name, it is not built. For some geometries (cylinders and cones), there is an additional parameter.

- At last you have **_type**, for geometries fitted to the subdivision mesh generator (See subsection 6.4.2 for details).


Let's summarize information about these keys:

key	authorized types	examples
_domain_name	String or const char*	_domain_name ="Omega"
_hsteps	single real value, std::vector of real values or Reals	_hsteps =0.5, _hsteps = Reals (0.5, 0.2)
_nnodes	single (unsigned) integer value, std::vector of integer values, Number or Numbers	_nnodes =11, _hsteps = Numbers (11, 22)
_side_names	single string, std::vector of string, String or Strings	_side_names ="Gamma", _side_names = Strings ("Gam1", "Gam2", "Gam2")
_type	single (unsigned) integer value, or Number	_type =1

In the following, we will see how to define each canonical geometries, before showing how to define more complicated ones.

6.1.1 Segments

A segment is just a straight line between 2 points.



The general case is to give points through parameters `_v1` and `_v2`, but when 1D, you can give directly the real coordinate:

```
Segment s1(_v1=Point(0.,0.,0.), _v2=Point(0.,1.,-1.), _nnodes=11, _domain_name="Omega");
Segment s2(_v1=Point(0.,0.), _v2=Point(0.,1.), _hsteps=0.1, _domain_name="Omega");
Segment s3(_v1=Point(0.), _v2=Point(1.), _hsteps=Reals(0.1,0.2), _domain_name="Omega");
Segment s4(_v1=0., _v2=1., _nnodes=11, _domain_name="Omega");
```

In previous examples `s3` and `s4` are identical. A better comprehensive way for `s4` is to use parameters `_xmin` and `_xmax` instead of `_v1` and `_v2`:

```
Segment s4(_xmin=0., _xmax=1., _nnodes=11, _domain_name="Omega");
```

In previous examples, you can notice that `_nnodes` take only a single integer value and `_hsteps` can take one real value or a vector of 2 real values (`Reals` object).

One of the combination `_xmin` and `_xmax` or `_v1` and `_v2` is needed.

After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Examples:

```
// segment [-2,5] with 50 points when meshing
Segment s1(_xmin=-2, _xmax=5, _nnodes=50);
// segment linking A(1,2,3) and B(-2,5,0) with 20 points when meshing and domain is "Omega1"
Point a(1.,2.,3.);
Point b(-2.,5.,0.);
Segment s2(_v1=a, _v2=b, _nnodes=20, _domain_name="Omega1");
// segment [0,1] with 20 points when meshing and side domains are "Gamma1" and "Gamma2"
Segment s3(_xmin=0., _xmax=1., _nnodes=20, _side_names=Strings("Gamma1", "Gamma2"));
// segment [0,1] with 10 points when meshing and domain is "Omega" and side domains are "Gamma1" and "Gamma2"
Segment s4(_xmin=0., _xmax=1., _nnodes=10, _domain_name="Omega",
    _side_names=Strings("Gamma1", "Gamma2"));
// segment [0,1] with 10 points when meshing and domain is "Omega" and side domain is "Gamma"
Segment s4(_xmin=0., _xmax=1., _nnodes=10, _domain_name="Omega", _side_names="Gamma");
```

You can reverse the orientation of a segment by using one of the following:

```
Segment s1(_xmin=-2, _xmax=5, _nnodes=50);
s1.reverse(); // s1 is modified
Segment s2=~s1; // s1 is not modified
```



When defining composite or loop geometries, you shall not use the `reverse` method, but only the `~` operator


Let's summarize information about geometrical keys for segments:

key(s)	authorized types	examples
_v1, _v2	single integer or real value, or <code>Point</code>	<code>_v1=Point(0.)</code> , <code>_v2=Point(0.,0.)</code> , <code>_v1=Point(0.,0.,0.)</code> , <code>_v2=0.</code>
_xmin, _xmax	single integer or real value	<code>_xmin=1</code> , <code>_xmax=-2.5</code>

6.1.2 Elliptic and circular arcs

Elliptic arcs

To define an elliptic arc, you need 4 points : the center of the ellipse, the apogee of the ellipse and the bounds of the arc.



There is a parameter for each of them : **_center**, **_apogee**, **_v1** and **_v2**. These parameters take 2D or 3D points. When omitted, the apogee point is defined as the first bound of the arc. An elliptic arc must be smaller than a half-ellipse, to be defined correctly.

_nnodes take only one single value and **_hsteps** can take one real value or a vector of 2 real values (`Reals` object). After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Example:

```
Point c(0.,0.,0.);
Point a(2.,0.,0.);
Point p1(0.,1.,1.);
Point p2(-1.,2.,0.)
// whole side domain will be "Gamma"
EllArc e1(_center=c, _apogee=a, _v1=p1, _v2=p2, _nnodes=20, _domain_name="Omega",
_side_names="Gamma");
```

You can reverse the orientation of an elliptic arc by using one of the following:

```
EllArc e1(_center=c, _apogee=a, _v1=p1, _v2=p2, _nnodes=20, _domain_name="Omega",
_side_names="Gamma");
e1.reverse(); // e1 is modified
EllArc e2=~e1; // e1 is not modified
```



When defining composite or loop geometries, you shall not use the `reverse` method, but only the `~` operator

Let's summarize information about geometrical keys on elliptic arcs:


key(s)	authorized types	examples
_apogee, _center, _v1, _v2	<code>Point</code>	<code>_center=Point(0.,0.)</code> , <code>_apogee=Point(0.,0.,0.)</code>



Elliptic arcs cannot be defined if the angular sector is greater than π . This is a GMSH restriction!

Circular arcs

To define a circular arc, you need 3 points : the center of the circle and the bounds of the arc.



There is a parameter for each of them : **_center**, **_v1** and **_v2**. These parameters take 2D or 3D points. A circular arc must be smaller than a half-circle, to be defined correctly.

_nnodes take only one single value and **_hsteps** can take one real value or a vector of 2 real values ([Reals](#) object). After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Example:

```
CircArc c1(_center=Point(0.,0.), _v1=Point(1.,0.), _v2=Point(0.,1.), _nnodes=30,
_domain_name="Omega");
```

You can reverse the orientation of a circular arc by using one of the following:

```
CircArc c1(_center=Point(0.,0.), _v1=Point(1.,0.), _v2=Point(0.,1.), _nnodes=30,
_domain_name="Omega");
c1.reverse(); // c1 is modified
CircArc c2=~c1; // c1 is not modified
```



When defining composite or loop geometries, you shall not use the [reverse](#) method, but only the `~` operator

Let's summarize information about geometrical keys on circular arcs:

key(s)	authorized types	examples
_center , _v1 , _v2	Point	_v2 = Point (0.,0.), _center = Point (0.,0.,0.)



Circular arcs cannot be defined if the angular sector is greater or equal than π . This is a GMSH restriction!

6.1.3 Parametrized arcs

The `parametrizedArc` class deals with curves that are defined from a function $t \in [t_{min}, t_{max}] \Rightarrow P(t) = (x(t), y(t), z(t))$ handled by a `Parametrization` object. When constructing a `parametrizedArc`, the following specific keys are available:

key	authorized types	examples
<code>_parametrization</code>	<code>Parametrization</code> object	<code>class Parametrization par(...); _parametrization = par</code>
<code>_tmin, _tmax</code>	<code>Real</code> value	<code>_tmin=0, _tmax=1</code>
<code>_partitioning</code>	<code>_linearPartition, _splinePartition</code>	<code>_partitioning=_linearPartition</code>
<code>_nbParts</code>	integer value	<code>_nbParts=100</code>

As GMSH does not deal with parametrized curve, when exporting `parametrizedArc` to GMSH, the curve has to be split in smaller parts (segments or splines). Each part will be also discretized according to the general keys `_hsteps` or `_nnodes`. `_nnodes` represents the number of nodes on the arc and should be chosen greater than `_nbParts`. If not, XLIFE++ adjust it to guarantee that there are two nodes by parts. There are two possibilities to set `_hsteps`, either giving a unique real value that is associated to each node of the partition, or giving a vector of `_nbParts + 1` values, each of them associated to each node of the partition.

For more details about `Parametrization`, see the section B.13. The only mandatory key is `_parametrization`, if not redefined `_tmin` and `_tmax` take the values of bounds of the parametrization, the partition is the linear one with 1 segment.




Greater is `_nbParts` better is the approximation of the parametrized arc.

As an illustration here is given the construction of a 2D mesh from a parametrized arc (split in 100 segments) and a segment:

```
Parametrization ps(0,2*pi_,x_1*cos(x_1),x_1*sin(x_1),Parameters(),"tcos(t),tsin(t)");
ParametrizedArc pa(_parametrization = ps, _partitioning=_linearPartition, _nbParts=100,
    _hsteps=0.1,_domain_name="Gamma");
Segment sa(_v1=pa.p2(), _v2=pa.p1(),_hsteps=0.1,_domain_name="Sigma");
Mesh Me2(surfaceFrom(pa+sa,"Omega"),_triangle,1,_gmsht);
```

Note the way to get the end points of the parametrized arc that guarantee the contour is closed!




When the first and last points of the parametrized curve coincides, the curve is closed and can be used to build the surface enclosed:

```

Parametrization pe(0,2*pi_,2*cos(x_1),sin(x_1),Parameters(),"2cos(t),sin(t)");
ParametrizedArc pae(_parametrization = pe,_partitioning=_linearPartition,_nbParts=50,
    _hsteps=0.1,_domain_name="Gamma");
Mesh Mee(surfaceFrom(pae),_triangle,1,_gmsh);

```



6.1.4 Spline arcs

SplineArc is the geometry class describing curves constructed from spline functions, either C2-spline, Catmull-Rom, Bézier spline or B-spline (see section B.14 for a description of spline functions). The mandatory keys to build a SplineArc geometry are

key	authorized types	examples
_spline_type	_CatmullRomSpline, _C2Spline, _BezierSpline, _BSpline	_spline_type =_BSpline
_spline_subtype	_splineInterpolation, _splineApproximation	_spline_subtype =_splineInterpolation
_vertices	vector of Point	(std::vector< Point > vp; ...) _vertices =vp



To close a curve, the last point must be equal to the first one.



_spline_subtype concerns only BSpline and **_splineInterpolation** is the default value in that case.



The standard factory of GMSH does not support the C2-spline. It is available in OpenCascad machinery of GMSH which is not yet addressed by XLiFE++.

Besides standard keys (**_domain_name**, **_side_names**, **_hsteps**, **_nnodes**), all the parameters of spline classes may be addressed with the following keys:

key	authorized types	examples
_spline_BC	_naturalBC, _clampedBC, _periodicBC	_spline_BC =_naturalBC
_tangent_0, _tangent_1	Reals	_tangent0 =Reals(1.,0.)
_degree	integer value	_degree =3
_tension	real value	_tensionFactor =0.5
_spline_parametrization	_xParametrization, _uniformParametrization, _chordalParametrization, _centripetalParametrization	_splineParametrization =_uniformParametrization
_weights	Reals	(Reals w(10) ...) _weights =w
_spline	Spline	(BSpline bsc(points)...) _spline =bsc



Default value of **_spline_BC** is **_clampedBC**. With this condition, the spline is clamped at the end points and the tangential vectors are also prescribed. If you do not set the **_tangent0, _tangent1** parameters, tangent vectors will be chosen as (1, 0, 0)! That means a 0 derivative at end points for C2 spline. The **_tension** parameter concerns only Catmull-Rom spline, its default value is 0.5 that provides curves realizing the best compromise (distance to the control points and curvatures).

These parameters are not available for any type of spline. They have default values regarding the type of spline, that are suitable to use splines with GMSH. If you are a newbie, do not play with spline parameters. For advanced users, read the section B.14 for more details.




By definition, the degree of a Bézier spline is equal to the number of control points minus one. XLIFF++ is compliant with this definition but GMSH is not. A Bézier curve in GMSH is a union of Bézier curves of degree 3 with several drawbacks : the curve is C0 but not necessary C1 and the number of points must be of the form $3k + 1$. So, if you intend to generate a mesh with GMSH, only Bézier spline of degree 3 with 4 control points are authorized. However, if you want to use multiple Bézier curves of degree 3, it is possible by concatenating several **SplineArc** build from Bézier spline of degree 3.

To mesh the surface enclosed by the x-axis and a spline approximation of the sinus curve, let define six points on the sinus curve

```
number_t n=5;
std::vector<Point> points(n+1);
Real x=0, dx=pi/n;
for (number_t i=0; i<=n; i++, x+=dx) points[i]=Point(x, sin(x));
```


• mesh using Catmull-Rom spline

```
Segment s(_v1=points[5], _v2=points[0], _hsteps=0.1, _domain_name="Sigma");
SplineArc sa(_splineType=_CatmullRomSpline, _vertices=points,
             _domain_name="Gamma", _hsteps=0.1);
Mesh msa(surfaceFrom(s+sa), _triangle, 1, _gmsh);
```



- mesh using **B-spline**


```
Segment s(_v1=points[5],_v2=points[0],_hsteps=0.1,_domain_name="Sigma");
SplineArc sa(_splineType=_BSpline,_vertices=points,
              _domain_name="Gamma",_hsteps=0.1);
Mesh msa(surfaceFrom(s+sa),_triangle,1,_gmsh);
```



- mesh using **Bézier curve**

As mentioned above, when GMSH is involved, only Bézier curve with 4 points are allowed:

```
n=3; points.resize(n+1);
x=0.;dx=pi_/n;
for(number_t i=0;i<=n;i++,x+=dx) points[i]=Point(x,sin(x));
SplineArc sa(_splineType=_BezierSpline,_vertices=points,
              _domain_name="Gamma",_hsteps=0.1);
Mesh msa(surfaceFrom(s+sa),_triangle,1,_gmsh);
```




Obviously, Bézier approximation with 4 points is far away from the sinus curve!

To build a closed spline, it is sufficient to take the last control point same as the first control point. The following example show a closed Catmull-Rom spline built from 6 points located on an ellipse:

```
number_t n=6;
vector<Point> pts(n+1);
Real s=0, ds=2*pi_/ns;
for(number_t i=0;i<=n;i++,s+=ds) pts[i]=Point(2*cos(s),sin(s));
SplineArc sd(_splineType=_CatmullRomSpline,_vertices=pts,
              _domain_name="Gamma",_hsteps=0.1);
Mesh msd(surfaceFrom(sd),_triangle,1,_gmsh);
```



As splines are curves (1D objects) do not forget to construct the surface by invoking the `surfaceFrom` command.




Note that users can access to the parametrization of a `SplineArc` and so on, to some particular quantities such as parameter bounds, curvature, curvilinear abscissa, normal vector, ... (see the `Parametrization` class):

```
SplineArc sa(_splineType=_BSpline , _vertices=points , _hsteps=0.1) ;
const Parametrization& pa=sa.parametrization() ;
RealPair bs=pa.bounds() ;
Real tm=(bs.first+bs.second) / 2;
theCout<<" bounds = "<<bs<<eol;
theCout<<"pa.curvature(tm) = "<<pa.curvature(tm)<<eol;
theCout<<"pa.curabc(tm) = "<<pa.curabc(tm)<<eol;
theCout<<"pa.normal(tm) = "<<pa.normal(tm)<<eol;
theCout<<"pa.tangent(tm) = "<<pa.tangent(tm)<<eol;
```

6.1.5 Polygons and polygon-like

Polygons

A polygon is defined by its ordered list of vertices.



To do so, you will use the parameter `_vertices`.

`_nnodes` can take one single value or a vector of values (`Numbers` object) and `_hsteps` can take one real value or a vector of real values (`Reals` object). The vector sizes are the number of vertices (same as the number of edges for a polygon). After these arguments, you can give names of main domain and side domains as explained in

preamble of this section.

Example:


```
std::vector<Point> p(5);
p[0]=Point(0.,0.);
p[1]=Point(8.,0.);
p[2]=Point(9.,4.);
p[3]=Point(5.,2.);
p[4]=Point(1.,4.);
Polygon poly1(_vertices=p, _nnodes=Numbers(15, 10, 8, 8, 10), _domain_name="Omega",
_side_names="Sigma");
```

Let's summarize information about geometrical keys on polygons:

key	authorized types	examples
_vertices	vector of Point	(std::vector<Point> vp; ...) _vertices=vp

Triangles

To define a triangle, you give the 3 vertices.



There is a parameter for each of them: **_v1**, **_v2** and **_v3**. These parameters take 2D or 3D points.

_nnodes can take one single value or a vector of 3 values (**Numbers** object) and **_hsteps** can take one real value or a vector of 3 real values (**Reals** object). After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Example:


```
Point a(-1.,2.,0.);
Point b(1.,-4.,2.);
Point c(2.,3.,1.);
Triangle t1(_v1=a, _v2=b, _v3=c, _nnodes=Numbers(10,15,20), _domain_name="Omega",
_side_names="Gamma");
```

Let's summarize information about geometrical keys on triangles:

key(s)	authorized types	examples
_v1, _v2, _v3	Point	_v1=Point(0.,0.) , _v2=Point(0.,0.,0.)

Quadrangles

To define a quadrangle, you give the 4 vertices.



There is a parameter for each of them: **_v1**, **_v2**, **_v3** and **_v4**. These parameters take 2D or 3D points. **_nnodes** can take one single value or a vector of 4 values (**Numbers** object) and **_hsteps** can take one real value or a vector of 4 real values (**Reals** object). After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Example:


```
Quadrangle q1(_v1=Point(0.,0.), _v2=Point(2.,0.), _v3=Point(2.,1.), _v4=Point(0.,1.),
_nnodes=Numbers(20, 10, 20, 10), _domain_name="Omega", _side_names="Gamma");
```

Let's summarize information about geometrical keys on quadrangles:

key(s)	authorized types	examples
_v1 , _v2 , _v3 , _v4	Point	_v1=Point(0.,0.) , _v4=Point(0.,0.,0.)

Parallelograms

To define a parallelogram, you give 3 vertices. If you refer to the following figure, p_3 is unnecessary.



There is a parameter for each of them: **_v1**, **_v2**, and **_v4**. These parameters take 2D or 3D points. **_nnodes** can take one single value or a vector of 2 or 4 values (**Numbers** object) and **_hsteps** can take one real value or a vector of 4 real values (**Reals** object). After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Examples:


```
Parallelogram p1(_v1=Point(0.,0.), _v2=Point(2.,0.), _v4=Point(0.,1.), _nnodes=Numbers(20, 10,
20, 10), _domain_name="Omega", _side_names="Gamma");
Parallelogram p2(_v1=Point(0.,0.), _v2=Point(2.,0.), _v4=Point(0.,1.), _nnodes=Numbers(20, 10),
_domain_name="Omega", _side_names="Gamma");
```

Both parallelograms of previous examples are identical. This explains the ability to give 2 values for **_nnodes**. Let's summarize information about geometrical keys on parallelograms:

key(s)	authorized types	examples
_v1 , _v2 , _v4	Point	_v1=Point(0.,0.) , _v2=Point(0.,0.,0.)

Rectangles

To define a rectangle, you give 3 vertices, as for parallelograms.



There is a parameter for each of them: **_v1**, **_v2**, and **_v4**, as for [Parallelogram](#). These parameters take 2D or 3D points.

For rectangles in plane $z=0$, where sides are parallel to x-axis and y-axis, you can define the rectangle by its center (c in the figure) and its lengths or p_1 (recalled origin in this case) and its lengths. You may use **_center**, **_xlength** and **_ylength** or **_origin**, **_xlength** and **_ylength** to do so. **_origin** and **_center** take 2D or 3D points. **_xlength** and **_ylength** take one single positive value.

There is another possibility : defining the rectangle by its bounds : parameters **_xmin**, **_xmax**, **_ymin** and **_ymax**. These parameters take one single value.

_nnodes can take one single value or a vector of 2 or 4 values ([Numbers](#) object) and **_hsteps** can take one real value or a vector of 4 real values ([Reals](#) object). After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Examples:

```
Rectangle r1(_v1=Point(0.,0.), _v2=Point(2.,0.), _v4=Point(0.,1.), _nnodes=Numbers(20, 10),
_domain_name="Omega", _side_names=Strings("Gamma1", "Gamma2", "Gamma1", "Gamma2"));
Rectangle r2(_center=Point(1.,0.5), _xlength=2., _ylength=1., _nnodes=Numbers(20, 10),
_domain_name="Omega", _side_names=Strings("Gamma1", "Gamma2", "Gamma1", "Gamma2"));
Rectangle r3(_origin=Point(0.,0.), _xlength=2., _ylength=1., _nnodes=Numbers(20, 10),
_domain_name="Omega", _side_names=Strings("Gamma1", "Gamma2", "Gamma1", "Gamma2"));
Rectangle r3(_xmin=0., _xmax=2., _ymin=0., _ymax=1., _nnodes=Numbers(20, 10),
_domain_name="Omega", _side_names=Strings("Gamma1", "Gamma2", "Gamma1", "Gamma2"));
```


This is 4 definitions of the same [Rectangle](#) object.

Let's summarize information about geometrical keys on rectangles:

key(s)	authorized types	examples
_center , _origin	Point	_origin = Point (0.,0.), _center = Point (0.,0.,0.)
_v1 , _v2 , _v4	Point	_v1 = Point (0.,0.), _v4 = Point (0.,0.,0.)
_xlength , _ylength	single unsigned integer or real positive value	_xlength =1, _ylength =2.5
_xmin , _xmax , _ymin , _ymax	single integer or real value	_xmin =1, _ymax =-2.5

Squares

To define a square, you give 3 vertices, as for rectangles and parallelograms.



There is a parameter for each of them: `_v1`, `_v2`, and `_v4`, as for [Parallelogram](#) and [Rectangle](#). These parameters take 2D or 3D points.

For squares in plane $z=0$, where sides are parallel to x-axis and y-axis, you can define the [SquareGeo](#) by its center (c in the figure) and its length or p_1 (recalled origin in this case) and its length. You may use `_center` and `_length` or `_origin` and `_length` to do so. `_origin` and `_center` take 2D or 3D points. `_length` takes one single positive value.

`_nnodes` can take one single value or a vector of 2 or 4 values ([Numbers](#) object) and `_hsteps` can take one real value or a vector of 4 real values ([Reals](#) object). After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Examples.:

```
SquareGeo s1(_v1=Point(0.,1.), _v2=Point(1.,1.), _v4=Point(0.,2.), _nnodes=Numbers(20, 10),
             _domain_name="Omega", _side_names=Strings("Gamma1", "Gamma2", "Gamma1", "Gamma2"));
SquareGeo s2(_center=Point(0.5,1.5), _length=1., _nnodes=Numbers(20, 10), _domain_name="Omega",
             _side_names=Strings("Gamma1", "Gamma2", "Gamma1", "Gamma2"));
SquareGeo s3(_origin=Point(0.,1.), _length=1., _nnodes=Numbers(20, 10), _domain_name="Omega",
             _side_names=Strings("Gamma1", "Gamma2", "Gamma1", "Gamma2"));
```

This is 3 definitions of the same [SquareGeo](#) object.



There is an alias to the [SquareGeo](#) object: [SquareGeo](#). But it is only available when XLIFE++ is not configured with OPENCASCADE, because OPENCASCADE provides a [Square](#) function and it may result in a conflict.


Let's summarize information about geometrical keys on squares:

key(s)	authorized types	examples
<code>_center</code> , <code>_origin</code>	Point	<code>_origin=Point(0.,0.)</code> , <code>_center=Point(0.,0.,0.)</code>
<code>_v1</code> , <code>_v2</code> , <code>_v4</code>	Point	<code>_v2=Point(0.,0.)</code> , <code>_v4=Point(0.,0.,0.)</code>
<code>_length</code>	single unsigned integer or real positive value	<code>_length=1</code> , <code>_length=2.5</code>

6.1.6 Ellipses and disks

Ellipses

To define an elliptic surface, you have to precise the plane where it is and the axis parameters. To define the plane, you just have to give the center point (parameter `_center`) and 2 other points, in order to have 3 unaligned points. These points are supposed to be both apogees of the ellipse (parameters `_v1` and `_v2`), namely c , p_1 and p_2 in the following figure:




These parameters take 2D or 3D points.

When apogees are along x-axis and y-axis respectively, you can give axis lengths by using **_xlength** and **_ylength** or semi-axis lengths by using **_xradius** and **_yradius**.

_nnodes can take one single value or a vector of 4 values (**Numbers** object), one for each quarter of ellipse. **_hsteps** can take one real value or a vector of 4 real values (**Reals** object). After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Furthermore, you can define elliptical sectors with two additional parameters: **_angle1** and **_angle2**. Values of angles are given in degree and can be any values, under the following behavior:

- Difference between angle values has to be smaller than 2π , but can be greater or equal than π .
- Modulos will be automatically used so that **_angle2** will be greater than **_angle1**
- If the angular sector is greater or equal than π , an intermediate point is built at the intersection of the ellipse and the bisector of the sector.
- Default value for **_angle1** is 0.
- Default value for **_angle2** is 2π .



Whole ellipses **_nnodes** can take one single value or a vector of 4 values (**Numbers** object). **_hsteps** can take one real value or a vector of 4 real values (**Reals** object).

Acute elliptical sectors **_nnodes** can take one single value or a vector of 3 values (**Numbers** object). **_hsteps** can take one real value or a vector of 3 real values (**Reals** object).

Obtuse elliptical sectors **_nnodes** can take one single value or a vector of 4 values (**Numbers** object). **_hsteps** can take one real value or a vector of 4 real values (**Reals** object).

After these arguments, you can give names of main domain and side domains as explained in the preamble of this section.

Examples:

```

Ellipse e1(_center=Point(0.,0.), _v1=Point(2.,0.), _v2=Point(0.,1.), _nnodes=Numbers(5, 10, 5, 10), _domain_name="Omega", _side_names=Strings("Gamma5", "Gamma10", "Gamma5", "Gamma10"));
Ellipse e2(_center=Point(0.,0.,0.), _v1=Point(1.,0.,1.), _v2=Point(0.,1.,1.), _nnodes=40, _domain_name="Omega", _side_names="Gamma");
Ellipse e3(_center=Point(0.,0., _xlength=2, _ylength=3.5, _nnodes=40, _domain_name="Omega", _side_names="Gamma");


```

Lets' summarize information about geometrical keys on ellipses:


key(s)	authorized types	examples
_center, _v1, _v2	Point	_center = Point (0.,0.), _v2 = Point (0.,0.,0.)
_xlength, _ylength, _xradius, _yradius, _angle1, _angle2	single unsigned integer or real positive value; angles in radian	_xlength =1, _yradius =2.5, _angle1 =3*pi/2

Disks

To define an disk, you have to precise the plane where it is and the radius parameters. To define the plane, you just have to give the center point and 2 other points, in order to have 3 unaligned points. These points are supposed to be doing a right angle with the center of the disk (as if they were apogees of an ellipse).



To do so, you will use parameters **_center**, **_v1** and **_v2**, as for an ellipse. These parameters take 2D or 3D points. Furthermore, you can define disk sectors with two additional parameters: **_angle1** and **_angle2**, as for the **Ellipse** object.



Whole disks **_nnodes** can take one single value or a vector of 4 values (**Numbers** object). **_hsteps** can take one real value or a vector of 4 real values (**Reals** object).

Acute circular sectors `_nnodes` can take one single value or a vector of 3 values (`Numbers` object). `_hsteps` can take one real value or a vector of 3 real values (`Reals` object).

Obtuse circular sectors `_nnodes` can take one single value or a vector of 4 values (`Numbers` object). `_hsteps` can take one real value or a vector of 4 real values (`Reals` object).

After these arguments, you can give names of main domain and side domains as explained in the preamble of this section.

Examples:

```
Disk d1(_center=Point(0.,0.), _v1=Point(1.,0.), _v2=Point(0.,1.), _nnodes=Numbers(5, 10, 5, 10),
        _domain_name="Omega", _side_names=Strings("Gamma5", "Gamma10", "Gamma5", "Gamma10"));
Disk d2(_center=Point(0.,0.,0.), _v1=Point(1.,0.,1.), _v2=Point(0.,1.,1.), _nnodes=40,
        _domain_name="Omega", _side_names="Gamma");
Disk d3(_center=Point(0.,0.), _radius=2.5, _nnodes=40, _domain_name="Omega", _side_names="Gamma");
```



The `Disk` object has another name: `Circle`

Let's summarize information about geometrical keys on disks:

key	authorized types	examples
<code>_center, _v1, _v2</code>	<code>Point</code>	<code>_center=Point(0.,0.),</code> <code>_v1=Point(0.,0.,0.)</code>
<code>_radius, _angle1,</code> <code>_angle2</code>	single unsigned integer or real positive value	<code>_radius=1, _angle1=247.5</code>


6.1.7 Parametrized surface

A `ParametrizedSurface` geometry is defined by a `Parametrization` handling a map $(u, v) \in \hat{\Omega} \rightarrow P(u, v) \in \mathbb{R}^3$. In most of cases, $\hat{\Omega} = [x_1, x_2] \times [y_1, y_2]$. Since mesh tools, generally, does not support this type of geometry representation, two additional data must be provided, to describe how to partition the surface into small representable pieces:

- the type of partition : linear or spline (key `_partitioning` with value `_linearPartition` or `_splinePartition`)
- the number of pieces in the partition (key `_nbParts`)

The following example shows the construction of a `ParametrizedSurface` using a parametrization defined by a symbolic function and a linear partition with 50 pieces:


```
Parametrization pars(0,2*pi_,0.,2*pi_, x_1, x_2,cos(x_1)*cos(x_2),Parameters());
ParametrizedSurface Psl(_parametrization = pars, _partitioning=_linearPartition, _nbParts=50,
                        _hsteps=0.2, _domain_name=sh, _side_names="Gamma");
```



The number of parts (triangles) is not strictly equal to 50 because the partitioning process consists in splitting the u-direction and v-direction relatively to their lengths such the total number of triangles be close to 50. The parameter **_hsteps** is propagated on all vertices of the triangle partition. It is not yet possible to manage different **_hsteps**. The side names are numbered relatively to the parametrization: $v = v_{min}$, $u = u_{max}$, $v = v_{max}$, $u = u_{min}$.

To get a good linear approximation of an oscillating surface, a lot of triangles are required, up to the desired mesh ideally! This is why using a spline partition is a better solution:

```
ParametrizedSurface Pss(_parametrization = pars, _partitioning=_splinePartition, _nbParts=16,
                        _hsteps=0.2, _domain_name=sh, _side_names="Gamma");
```



In addition to the standard keys (**_hsteps**, **_domain_name**, ...) only the following keys are available:

key	authorized types	examples
_parametrization ,	Parametrization object	_parametrization =pars
_partitioning	_linearPartition , _splinePartition	_partitioning =_splinePartition
_nbParts	unsigned int (Number)	_nbParts =16



Be cautious, in any case the surface meshed is an approximated surface of the parametrized surface. As spline partition uses interpolation splines, the approximation may be a quite good one.



Up to now, the [ParametrizedSurface](#) geometry can be meshed only with the OpenCascade engine!

6.1.8 Spline surface


A spline surface is a geometrical surface in 3D built from a [Nurbs](#) object (see subsection B.14.5), implicitly parametrized by two scalars $(u, v) \in [0, 1] \times [0, 1]$. It has at most 4 sides (some may be degenerated).

A [SplineSurface](#) geometry may be either constructed directly from a [Nurbs](#) object:

```
Number nbu=7, m= 2*nbu+1, n=nbu+1;
Real ds=pi/(2*nbu); real_t u=-pi/2,v;
Points pts(m*n);
for (Number i=0; i<=2*nbu; i++,u+=ds)
{
    v=0;
    for (Number j=0; j<=nbu; j++,v+=ds) pts[i*n+j]=Point(cos(u)*cos(v),cos(u)*sin(v),sin(u));
}
NURBS nul(_splineInterpolation,pts,m,); // interpolation nurbs
SplineSurface spsI(_spline=nul, _hsteps=0.2, _domain_name=sh,
    _side_names=Strings("Gamma1","Gamma2","Gamma3","Gamma4"));
```

or using parameter keys:

```
SplineSurface sps(_vertices=pts, _nbu=m, _hsteps=0.2, _domain_name=sh,
    _side_names=Strings("Gamma1","Gamma2","Gamma3","Gamma4"));
```



Sides names order rule is $v = 0$, $u = 1$, $v = 1$ and $u = 0$. In the previous example, because some bound points collapse, there are only two sides really named ($v = 0$ and $v = 1$), corresponding to "Gamma1" and "Gamma3".



By using the option `_splineApproximation`, it is also possible to address approximation splines.

In addition to the standard keys (`_hsteps`, `_domain_name`, ...) the following keys are available:

key	authorized types	examples
_spline	Nurbs	_spline =nu
_splineSubtype	_splineInterpolation* _splineApproximation	or _splineSubtype = _splineInterpolation
_vertices	Point vector (Points)	_vertices =pts
_weights	Real vector (Reals)	_weights =ws
_nbu	unsigned int (Number)	_nbu =5



Do not forget to specify the value nbu (either in NURBS construction or in key) that specifies the number of control/interpolation points in u-direction; the number of points in v-direction is deduced from the size of control/interpolation point vector. It should be a multiple of nbu!




Up to now, such [SplineSurface](#) geometry can be meshed only with the OpenCascade engine!

6.1.9 Polyhedra and polyhedron-likes

Polyhedra

A polyhedron is defined by its faces. The list of faces is a vector of polygons (See subsection 6.1.5 for details).



To do so, you will use the parameter **_faces**. The only other parameter you may use is **_domain_name**, to set the name of the polyhedral main domain. Everything else is defined by the faces.

Example:

```
std::vector<Point> v(5), v2(4);
v[0]=Point(0.,0.,0.); v[1]=Point(2.,0.,0.); v[2]=Point(3.,1.,0.); v[3]=Point(1.,4.,0.);
v[4]=Point(-1.,2.,0.);
Polygon pg1(_vertices=v, _domain_name="Gamma1");
v[0]=Point(0.,0.,1.); v[1]=Point(2.,0.,1.); v[2]=Point(3.,1.,1.); v[3]=Point(1.,4.,1.);
v[4]=Point(-1.,2.,1.);
Polygon pg2(_vertices=v, _domain_name="Gamma2");
v2[0]=Point(0.,0.,0.); v2[1]=Point(2.,0.,0.); v2[2]=Point(2.,0.,1.); v2[3]=Point(0.,0.,1.);
Polygon pg3(_vertices=v2, _domain_name="Sigma");
v2[0]=Point(2.,0.,0.); v2[1]=Point(3.,1.,0.); v2[2]=Point(3.,1.,1.); v2[3]=Point(2.,0.,1.);
Polygon pg4(_vertices=v2, _domain_name="Sigma");
v2[0]=Point(3.,1.,0.); v2[1]=Point(1.,4.,0.); v2[2]=Point(1.,4.,1.); v2[3]=Point(3.,1.,1.);
Polygon pg5(_vertices=v2, _domain_name="Sigma");
v2[0]=Point(1.,4.,0.); v2[1]=Point(-1.,2.,0.); v2[2]=Point(-1.,2.,1.); v2[3]=Point(1.,4.,1.);
```

```

Polygon pg6(_vertices=v2, _domain_name="Sigma");
v2[0]=Point(-1.,2.,0.); v2[1]=Point(0.,0.,0.); v2[2]=Point(0.,0.,1.); v2[3]=Point(-1.,2., 1.);
Polygon pg7(_vertices=v2, _domain_name="Sigma");
std::vector<Polygon> faces(7);
faces[0]=pg1; faces[1]=pg2; faces[2]=pg3; faces[3]=pg4; faces[4]=pg5; faces[5]=pg6; faces[6]=pg7;
Polyhedron poly1(_faces=faces, _domain_name="Omega");


```

Let's summarize information about geometrical keys on polyhedra:

key	authorized types	examples
_faces	vector of Polygon	(std::vector< Polygon > vp; ...) _faces =vp

Tetrahedra

To define a tetrahedron, you give the 4 vertices.



There is a parameter for each of them: **_v1**, **_v2**, **_v3** and **_v4**. These parameters take 3D points. **_nnodes** can take one single value or a vector of 6 values (**Numbers** object) and **_hsteps** can take one real value or a vector of 4 real values (**Reals** object). After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Example:

```

Point a(1.,0.,0.), b(0.,1.,0.), c(0.,0.,1.), d(0.,0.,0.);
Tetrahedron t1(_v1=a, _v2=b, _v3=c, _v4=d, _nnodes=10, _domain_name="Omega", _side_names="Gamma");


```

Let's summarize information about geometrical keys on tetrahedra:

key(s)	authorized types	examples
_v1, _v2, _v3, _v4	Point	_v1 = Point (0.,0.,0.)

Hexahedra

To define a hexahedron, you just have to give the 8 vertices, defined as in the following figure.



There is a parameter for each of them: **_v1**, **_v2**, **_v3**, **_v4**, **_v5**, **_v6**, **_v7** and **_v8**. These parameters take points or a single value (in this case, it is like a 1D point). **_nnodes** can take one single value or a vector of 12 values (**Numbers** object) and **_hsteps** can take one real value or a vector of 8 real values (**Reals** object). After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Examples:


```
Point a(0.,0.,0.), b(4.,0.,0.), c(4.,2.,0.), d(0.,2.,0.);
Point aa(0.,0.,1.), bb(4.,0.,1.), cc(4.,2.,1.), dd(0.,2.,1.);
Hexahedron h1(_v1=a, _v2=b, _v3=c, _v4=d, _v5=aa, _v6=bb, _v7=cc, _v8=dd, _nnodes=Numbers(40, 20, 40, 20, 40, 20, 40, 20, 10, 10, 10, 10), _domain_name="Omega");
```

Let's summarize information about geometrical keys on hexahedra:

key(s)	authorized types	examples
_v1 , _v2 , _v3 , _v4 , _v5 , _v6 , _v7 , _v8	Point	_v4=Point(0.,0.,0.)


Parallelepipeds

To define a parallelepiped, you just have to give 4 vertices (namely p_1 , p_2 , p_4 and p_5), defined as in the following figure :



There is a parameter for each of them: **_v1**, **_v2**, **_v4**, and **_v5**. These parameters take points or a single value (in this case, it is like a 1D point). **_nnodes** can take one single value or a vector of 3 or 12 values (**Numbers** object) and **_hsteps** can take one real value or a vector of 8 real values (**Reals** object). After these arguments, you can give names of main domain and side domains as explained in preamble of this section.


At last, you can give an additional argument: the number of octants to deal with (parameter **_nbocants**). Let us explain this with the following figure:




Considering the center of the parallelepiped, and the associated trihedron, symbolized by black dashed arrows, the parallelepiped can be splitted into 8 parallelepipedic parts, corresponding to one octant. Octants having a numbering convention, When giving the number of octants he asked, for instance 5, the user wants to build intersection of the parallelepiped with octants 1 to 5. The default value is 8, so that the whole parallelepiped is considered.

This is a way to define some specific geometries, such as:


- the Fichera Parallelepiped (7 octants):




- the big L-shape (6 octants):



- the parallelepiped with 5 octants:



- the small L-shape (3 octants):



Examples:

```

Point a(0.,0.,0.), b(4.,0.,0.), c(4.,2.,0.), d(0.,2.,0.);
Point aa(0.,0.,1.), bb(4.,0.,1.), cc(4.,2.,1.), dd(0.,2.,1.);
Parallelepiped p1(_v1=a, _v2=b, _v4=d, _v5=aa, _nnodes=Numbers(40, 20, 40, 20, 40, 20, 40, 20,
10, 10, 10, 10), _domain_name="Omega");
Parallelepiped p2(_v1=a, _v2=b, _v4=d, _v5=aa, _nnodes=Numbers(40, 20, 10), _domain_name="Omega");


```

Both parallelepipeds of previous examples are identical. This explains the ability to give 3 values for **_nnodes**. Let's summarize information about geometrical keys on parallelepipeds:

key(s)	authorized types	examples
_v1, _v2, _v4, _v5	Point	_v5=Point(0.,0.,0.)
_nboctants	single unsigned integer value between 1 and 8	_nboctants=3

Cuboids

To define a cuboid, you give 4 vertices, as for parallelepipeds.



There is a parameter for each of them: `_v1`, `_v2`, `_v4`, and `_v5`. These parameters take points or a single value (in this case, it is like a 1D point). For cuboids where faces are parallel to planes $x=0$, $y=0$ and $z=0$, you can define the cuboid by its center (c in the figure) and its lengths or p_1 (recalled origin in this case) and its lengths. You may use `_center`, `_xlength`, `_ylength` and `_zlength` or `_origin`, `_xlength`, `_ylength` and `_zlength` to do so. `_origin` and `_center` take points or a single value (in this case, it is like a 1D point). `_xlength`, `_ylength` and `_zlength` take one single positive value. There is another possibility : defining the rectangle by its bounds : parameters `_xmin`, `_xmax`, `_ymin`, `_ymax`, `_zmin` and `_zmax`. These parameters take one single value. `_nnodes` can take one single value or a vector of 3 or 12 values ([Numbers](#) object) and `_hsteps` can take one real value or a vector of 8 real values ([Reals](#) object).

At last, you can give an additional argument: the number of octants to deal with (parameter `_nbocants`). After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Examples:

```
Cuboid c1(_v1=Point(0.,0.,0.), _v2=Point(2.,0.,0.), _v4=Point(0.,3.,0.), _v5=Point(0.,0.,4.),
          _nnodes=40, _domain_name="Omega");
Cuboid c2(_origin=Point(0.,0.,0.), _xlength=2., _ylength=3., _zlength=4., _nnodes=40,
          _domain_name="Omega");
Cuboid c3(_center=Point(1.,1.5.,2.), _xlength=2., _ylength=3., _zlength=4., _nnodes=40,
          _domain_name="Omega");
Cuboid c4(_xmin=0, _xmax=2, _ymin=0, _ymax=3, _zmin=0, _zmax=4, _nnodes=40, _domain_name="Omega");
```


This is 4 definitions of the same `Cuboid` object.

Let's summarize information about geometrical keys on cuboids:

key(s)	authorized types	examples
<code>_center</code> , <code>_origin</code>	<code>Point</code>	<code>_center=Point(0.,0.,0.)</code>
<code>_v1</code> , <code>_v2</code> , <code>_v4</code> , <code>_v5</code>	<code>Point</code>	<code>_v1=Point(0.,0.,0.)</code>
<code>_xlength</code> , <code>_ylength</code> , <code>_zlength</code>	single unsigned integer or real positive value	<code>_xlength=1</code> , <code>_zlength=2.5</code>
<code>_xmin</code> , <code>_xmax</code> , <code>_ymin</code> , <code>_ymax</code> , <code>_zmin</code> , <code>_zmax</code>	single integer or real value	<code>_xmin=1</code> , <code>_zmin=-2.5</code>
<code>_nbocants</code>	single unsigned integer value between 1 and 8	<code>_nbocants=3</code>

Cubes

To define a cube, you give 4 vertices, as for parallelepipeds and cuboids.



There is a parameter for each of them: **_v1**, **_v2**, **_v4**, and **_v5**. These parameters take points or a single value (in this case, it is like a 1D point). For cuboids where faces are parallel to planes $x=0$, $y=0$ and $z=0$, you can define the cuboid by its center (c in the figure) and its lengths or p_1 (recalled origin in this case) and its lengths. You may use **_center** and **_length** or **_origin** and **_length** to do so. **_origin** and **_center** take points or a single value (in this case, it is like a 1D point). **_length** take one single positive value.

_nnodes can take one single value or a vector of 3 or 12 values (**Numbers** object) and **_hsteps** can take one real value or a vector of 8 real values (**Reals** object).

At last, you can give an additional argument: the number of octants to deal with (parameter **_nbocants**).

After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Examples:

```
Cube c1(_v1=Point(0.,0.,0.), _v2=Point(4.,0.,0.), _v4=Point(0.,4.,0.), _v5=Point(0.,0.,4.),
      _nnodes=40, _domain_name="Omega");
Cube c2(_origin=Point(0.,0.,0.), _length=2., _nnodes=40, _domain_name="Omega");
Cube c3(_center=Point(1.,1.,1.), _length=2., _nnodes=40, _domain_name="Omega");
```

This is 3 definitions of the same **Cube** object.


Let's summarize information about geometrical keys on cubes:

key(s)	authorized types	examples
_center , _origin	Point	_center=Point(0.,0.,0.)
_v1 , _v2 , _v4 , _v5	Point	_v1=Point(0.,0.,0.)
_length	single unsigned integer or real positive value	_length=1 , _length=2.5
_nbocants	single unsigned integer value between 1 and 8	_nbocants=3

6.1.10 Ellipsoids and balls

Ellipsoids


To define an ellipsoidal volume, you do the same way as for an ellipse or a disk (See section 6.1.6 or section 6.1.6), namely using 4 points c , p_1 , p_2 , p_6 , defined as in the following figure:



There is a parameter for each of them: **_center**, **_v1**, **_v2**, and **_v6**. These parameters take points or a single value (in this case, it is like a 1D point). For ellipsoidal volumes where main axes are parallel to x-axis, y-axis and z-axis, you can define the ellipsoid with the center and 3 axis lengths. For this purpose, use **_xlength**, **_ylength** and **_zlength**, taking one single positive value. You can also give semi-axis lengths by using **_xradius**, **_yradius** and **_zradius**.

_nnodes can take one single value or a vector of 3 or 12 values (**Numbers** object), one for each quarter of ellipse. **_hsteps** can take one real value or a vector of 6 real values (**Reals** object). After these arguments, you can give names of main domain and side domains as explained in preamble of this section.


At last, you can give an additional argument: the number of octants to deal with (parameter **_nbocants**), as for **Parallelepipiped**, **Cuboid** and **Cube** objects. Let us explain this with the following figure:




Considering the center of the ellipsoid, and the associated trihedron, symbolized by black dashed arrows, the ellipsoid can be splitted into 8 parts, corresponding to one octant. Octants having a numbering convention, When giving the number of octants he asked, for instance 5, the user wants to build intersection of the ellipsoid with octants 1 to 5. The default value is 8, so that the whole ellipsoid is considered.

This is a way to define some specific geometries, such as:


- the Fichera ellipsoid (7 octants):




- the big ellipsoidal L-shape (6 octants):




- the ellipsoid with 5 octants:




- the half ellipsoid (4 octants):




- the small ellipsoidal L-shape (3 octants):



- the quarter of ellipsoid (2 octants):



- the eighth of ellipsoid (1 octant):



Examples:

```

Ellipsoid e1(_center=Point(0.,0.,0.), _v1=Point(3.,0.,0.), _v2=Point(0.,2.,0.),
  _v6=Point(0.,0.,1.), _nnodes=Numbers(35, 30, 25), _domain_name="Omegal",
  _side_names="Gamma");
Ellipsoid e2(_center=Point(0.,0.,0.), _v1=Point(3.,0.,0.), _v2=Point(0.,2.,0.),
  _v6=Point(0.,0.,1.), _nnodes=Numbers(35, 35, 35, 35, 30, 30, 30, 30, 25, 25, 25, 25),
  _domain_name="Omegal", _side_names="Gamma");
Ellipsoid e3(_center=Point(0.,0.,0.), _xlength=6, _ylength=4, _zlength=2, _nnodes=Numbers(35, 30,
  25), _domain_name="Omegal", _side_names="Gamma");

```


This is 3 definitions of the same **Ellipsoid** object. The difference between e_1 and e_2 explains the ability to give 3 values for **_nnodes**.

Let's summarize information about geometrical keys on ellipsoids:

key(s)	authorized types	examples
_center , _v1 , _v2 , _v6	Point	_center = Point (0.,0.,0.)
_xlength , _ylength , _zlength , _xradius , _yradius , _zradius	single unsigned integer or real positive value	_xlength =1, _zradius =2.5
_nboctants	single unsigned integer value between 1 and 8	_nboctants =3

Balls

To define a ball, you do the same way as for an ellipsoid (See section 6.1.10), namely using 4 points c , p_1 , p_2 , p_6 , defined as in the following figure:



There is a parameter for each of them: **_center**, **_v1**, **_v2**, and **_v6**. These parameters take points or a single value (in this case, it is like a 1D point). For balls where main axes are parallel to x-axis, y-axis and z-axis, you can define the ellipsoid with the center and the radius. For this purpose, use **_radius**, taking one single positive value.

_nnodes can take one single value or a vector of 3 or 12 values (**Numbers** object), one for each quarter of ellipse. **_hsteps** can take one real value or a vector of 6 real values (**Reals** object). After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

At last, you can give an additional argument: the number of octants to deal with (parameter **_nboctants**). See section 6.1.9 for details.

Examples:

```

Ball b1(_center=Point(0.,0.,0.), _v1=Point(3.,0.,0.), _v2=Point(0.,3.,0.), _v6=Point(0.,0.,3.),
      _nnodes=Numbers(35, 30, 25), _domain_name="Omega1", _side_names="Gamma");
Ball b2(_center=Point(0.,0.,0.), _v1=Point(3.,0.,0.), _v2=Point(0.,3.,0.), _v6=Point(0.,0.,3.),
      _nnodes=Numbers(35, 35, 35, 30, 30, 30, 30, 25, 25, 25, 25), _domain_name="Omega1",
      _side_names="Gamma");
Ball b3(_center=Point(0.,0.,0.), _radius=3, _nnodes=Numbers(35, 30, 25), _domain_name="Omega1",
      _side_names="Gamma");

```

This is 3 definitions of the same `Ball` object. The difference between b_1 and b_2 explains the ability to give 3 values for `_nnodes`.



The `Ball` object has another name: `Sphere`

Let's summarize information about geometrical keys on balls:


key(s)	authorized types	examples
<code>_center</code> , <code>_v1</code> , <code>_v2</code> , <code>_v6</code>	<code>Point</code>	<code>_center=Point(0.,0.,0.)</code>
<code>_radius</code>	single unsigned integer or real positive value	<code>_radius=1</code> , <code>_radius=2.5</code>
<code>_nbocants</code>	single unsigned integer value between 0 and 8	<code>_nbocants=3</code>

6.1.11 Trunks and trunk-likes

Trunks

A trunk is a generalized truncated cone. To define a trunk, you need to give a surface, namely a polygonal surface (`Polygon`, `Triangle`, `Quadrangle`, `Parallelogram`, `Rectangle`, or `SquareGeo`), or an elliptical surface (`Ellipse` or `Disk`). To define the other surface, you just need to give a point of this surface (*origin*), and the scale factor according to the first surface.


For a trunk with polygonal basis, *origin* is the equivalent of the first vertex of the surface you give, as you can see on the following figure of a trunk with triangular basis. The triangle being defined by its vertices p_1 , p_2 and p_3 , *origin* is the equivalent of p_1 :



To do so, you will use parameter `_basis` to define the basis, parameter `_origin` to define *origin*, and parameter `_scale` to define the scale factor.

`_basis` takes any surface object : `Polygon`, `Triangle`, `Quadrangle`, `Parallelogram`, `Rectangle`, `SquareGeo`, `Ellipse` or `Disk`. `_origin` takes a point or a single value (in this case, it is like a 1D point). `_scale` takes one single positive value.

For a trunk with elliptical basis, *origin* is the center of the second basis, as you can see on the following figure of a trunk with elliptical basis.



To do so, you will use parameters `_center1`, `_v1`, `_v2`, `_center2` and `_scale` to define such a trunk. `_center1`, `_v1`, `_v2` and `_center2` take a point or a single value (in this case, it is like a 1D point). `_center1`, `_v1` and `_v2` are used as for a `Ellipse` or `Disk` object (see section 6.1.6 or section 6.1.6 for details). `_center2` is used in this case instead of `_origin`, as it is the center of the second basis.

`_nnodes` can take one single value or a vector of 3 or n values (`Numbers` object), where n is 3 times the number of edges of the basis. `_hsteps` can take one real value or a vector of p real values (`Reals` object), where p is the number of points defining the trunk. After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Examples:


```
Trunk t1(_basis=Triangle(_v1=Point(0.,0.,0.), _v2=Point(3.,0.,0.), _v3=Point(0.,2.,0.)),
        _origin=Point(0.,2.,1.), _scale=0.5, _nnodes=Numbers(10, 10, 10, 5, 5, 5, 20, 20, 20),
        _domain_name="Omega", _side_names=Strings("Gamma", "Gamma", "Sigma", "Sigma", "Sigma"));
Trunk t2(_basis=Triangle(_v1=Point(0.,0.,0.), _v2=Point(3.,0.,0.), _v3=Point(0.,2.,0.)),
        _origin=Point(0.,2.,1.), _scale=0.5, _nnodes=Numbers(10, 5, 20), _domain_name="Omega",
        _side_names=Strings("Gamma", "Gamma", "Sigma", "Sigma", "Sigma"));
```

This is 2 definitions of the same `Trunk` object, explaining the ability to give 3 values for `_nnodes`, instead of 9. Let's summarize information about geometrical keys on trunks:

key(s)	authorized types	examples
<code>_basis</code>	<code>Polygon</code> , <code>Triangle</code> , <code>Quadrangle</code> , <code>Parallelogram</code> , <code>Rectangle</code> , <code>SquareGeo</code> , <code>Ellipse</code> , <code>Disk</code>	<code>_basis=Triangle(...)</code>
<code>_origin</code>	<code>Point</code>	<code>_origin=Point(0,0,0.)</code>
<code>_scale</code>	single unsigned integer or real positive value	<code>_scale=2</code> , <code>_scale=0.5</code>
<code>_center1</code> , <code>_center2</code> , <code>_v1</code> , <code>_v2</code>	<code>Point</code>	<code>_center1=Point(0,0,0.)</code>

Cylinders

A cylinder is a truncated cone whose apex is at infinite distance. So it is the geometry defined by the extrusion of a surface by translation.



To do so, you have to use parameters **_basis** and **_direction**. **_basis**, as for trunks, take any surface object: [Polygon](#), [Triangle](#), [Quadrangle](#), [Parallelogram](#), [Rectangle](#), [SquareGeo](#), [Ellipse](#) or [Disk](#). **_direction** takes a vector of real numbers ([Point](#) or [Reals](#) objects) or a single value (in this case, it is like a direction parallel to x-axis).

As for a trunk, a cylinder with elliptical basis can be defined by another way, using parameters **_center1**, **_v1**, **_v2** and **_center2**, taking a point or a single value (in this case, it is like a 1D point). **_center1**, **_v1** and **_v2** are used as for a [Ellipse](#) or [Disk](#) object (see section 6.1.6 or section 6.1.6 for details). **_center2** is used in this case instead of **_direction**, as it is easier to give the center of the second basis, instead of the direction vector.

_nnodes can take one single value or a vector of 3 or n values ([Numbers](#) object), where n is 3 times the number of edges of the basis. **_hsteps** can take one real value or a vector of p real values ([Reals](#) object), where p is the number of points defining the trunk. After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Examples:

```
Cylinder c1(_basis=Disk(_center=Point(0.,0.,0.), _v1=Point(2.,0.,0.), _v2=Point(0.,2.,0.)),
_direction=Point(0.,2.,1.), _nnodes=Numbers(10, 10, 10, 10, 5, 5, 5, 5, 20, 20, 20, 20),
_domain_name="Omega", _side_names=Strings("Gamma", "Gamma", "Sigma", "Sigma", "Sigma",
"Sigma"));
Cylinder c2(_basis=Disk(_center=Point(0.,0.,0.), _v1=Point(2.,0.,0.), _v2=Point(0.,2.,0.)),
_direction=Point(0.,2.,1.), _scale=0.5, _nnodes=Numbers(10, 5, 20), _domain_name="Omega",
_side_names=Strings("Gamma", "Gamma", "Sigma", "Sigma", "Sigma", "Sigma"));
Cylinder c3(_center1=Point(0.,0.,0.), _v1=Point(2.,0.,0.), _v2=Point(0.,2.,0.),
_center2=Point(0.,2.,1.), _scale=0.5, _nnodes=Numbers(10, 5, 20), _domain_name="Omega",
_side_names=Strings("Gamma", "Gamma", "Sigma", "Sigma", "Sigma", "Sigma"));
```


This is 3 definitions of the same [Cylinder](#) object, explaining the ability to give 3 values for **_nnodes**, instead of 12.

Let's summarize information about geometrical keys on cylinders:

key(s)	authorized types	examples
_basis	Polygon, Triangle, Quadrangle, Parallelogram, Rectangle, SquareGeo, Ellipse, Disk	_basis =Triangle(...)
_direction	std::vector of real values, Reals or Point	_direction =Reals(0.,0.,1.), _direction =Point(0.,0.,1.)
_center1, _center2, _v1, _v2	Point	_center1 =Point(0.,0.,0.)

Prisms

A prism is by definition a cylinder whose basis is a polygonal surface (Polygon, Triangle, Quadrangle, Parallelogram, Rectangle, or SquareGeo).



As for cylinder, you will use parameters **_basis** and **_direction**. **_basis**, as for trunks, take any polygonal object: Polygon, Triangle, Quadrangle, Parallelogram, Rectangle or SquareGeo. **_direction** takes a vector of real numbers (Point or Reals objects) or a single value (in this case, it is like a direction parallel to x-axis). Often a prism refers to a cylinder with triangular basis (as the finite element cell). So you can also define a prism from 3 points (for triangular basis), using parameters **_v1**, **_v2**, **_v3** instead of **_basis**, taking a point or a single value (in this case, it is like a 1D point).

_nnodes can take one single value or a vector of 3 or n values (Numbers object), where n is 3 times the number of edges of the basis. **_hsteps** can take one real value or a vector of p real values (Reals object), where p is the number of points defining the trunk. After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Examples:

```
Prism p1(_basis=Triangle(_v1=Point(0.,0.,0.), _v2=Point(2.,0.,0.), _v3=Point(0.,1.,0.)),
        _direction=Reals(0.,2.,1.), _nnodes=Numbers(10, 10, 10, 5, 5, 5, 20, 20, 20),
        _domain_name="Omega", _side_names=Strings("Gamma", "Gamma", "Sigma", "Sigma", "Sigma"));
Prism p2(_basis=Triangle(_v1=Point(0.,0.,0.), _v2=Point(2.,0.,0.), _v3=Point(0.,1.,0.)),
        _direction=Reals(0.,2.,1.), _nnodes=Numbers(10, 5, 20), _domain_name="Omega",
        _side_names=Strings("Gamma", "Gamma", "Sigma", "Sigma", "Sigma"));
Prism p3(_v1=Point(0.,0.,0.), _v2=Point(2.,0.,0.), _v3=Point(0.,1.,0.),
        _direction=Reals(0.,2.,1.), _nnodes=Numbers(10, 5, 20), _domain_name="Omega",
        _side_names=Strings("Gamma", "Gamma", "Sigma", "Sigma", "Sigma"));
```


This is 3 definitions of the same Prism object, explaining the ability to give 3 values for **_nnodes**, instead of 9.

Let's summarize information about geometrical keys on prisms:

key(s)	authorized types	examples
_basis	Polygon, Triangle, Quadrangle, Parallelogram, Rectangle, SquareGeo	_basis =Triangle(...)
_direction	std::vector of real values, Reals or Point	_direction =Reals(0.,0.,1.), _direction =Point(0.,0.,1.)
_v1, _v2, _v3	Point	_v2 =Point(0.,0.,0.)

Cones

A cone is defined by a surface and an apex.



To do so, you will use parameters **_basis** and **_apex**. **_basis**, as for trunks, take any surface object: Polygon, Triangle, Quadrangle, Parallelogram, Rectangle, SquareGeo, Ellipse or Disk. **_apex** takes a point or a single value (in this case, it is like a 1D point).

As for trunks and cylinders, you can also define directly a cone with elliptical basis, with parameters **_center1**, **_v1**, **_v2** (and **_apex**). These parameters take a point or a single value (in this case, it is like a 1D point).

_nnodes can take one single value or a vector of 2 or n values (Numbers object), where n is twice the number of edges of the basis. **_hsteps** can take one real value or a vector of p real values (Reals object), where p is the number of points defining the trunk. After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Examples:

```
Cone c1(_basis=Disk(_center=Point(0.,0.,0.), _v1=Point(2.,0.,0.), _v2=Point(0.,2.,0.)),
    _apex=Point(0.,0.,1.), _nnodes=Numbers(20, 20, 20, 20, 10, 10, 10, 10),
    _domain_name="Omega", _side_names="Gamma");
Cone c2(_basis=Disk(_center=Point(0.,0.,0.), _v1=Point(2.,0.,0.), _v2=Point(0.,2.,0.)),
    _apex=Point(0.,0.,1.), _nnodes=Numbers(20, 10), _domain_name="Omega", _side_names="Gamma");
Cone c3(_center1=Point(0.,0.,0.), _v1=Point(2.,0.,0.), _v2=Point(0.,2.,0.),
    _apex=Point(0.,0.,1.), _nnodes=Numbers(20, 10), _domain_name="Omega", _side_names="Gamma");
```

This is 3 definitions of the same Cone object, explaining the ability to give 2 values for **_nnodes**, instead of 8.




Actually, this geometry cannot be meshed directly. Please use Pyramid for cones with polygonal basis, or RevCone for revolution cones.

Let's summarize information about geometrical keys on cones:

key(s)	authorized types	examples
_apex , _center1 , _v1 , _v2	<code>Point</code>	<code>_apex=Point(0.,0.,0.)</code>
_basis	<code>Polygon</code> , <code>Triangle</code> , <code>Quadrangle</code> , <code>Parallelogram</code> , <code>Rectangle</code> , <code>SquareGeo</code> , <code>Ellipse</code> , <code>Disk</code>	<code>_basis=Triangle(...)</code>

Pyramids

A pyramid is a cone with a polygonal basis (`Polygon`, `Triangle`, `Quadrangle`, `Parallelogram`, `Rectangle`, or `SquareGeo`).



As for cones, you will use parameters **_basis** and **_apex**. **_basis** takes any polygonal object: `Polygon`, `Triangle`, `Quadrangle`, `Parallelogram`, `Rectangle` or `SquareGeo`. **_apex** takes a point or a single value (in this case, it is like a 1D point).

Often a pyramid refers to a cone with quadrangular basis (as the finite element cell). So you can also define a pyramid from 4 points (for quadrangular basis), using parameters **_v1**, **_v2**, **_v3**, **_v4** instead of **_basis**, taking a point or a single value (in this case, it is like a 1D point).

_nnodes can take one single value or a vector of 2 or n values (`Numbers` object), where n is twice the number of edges of the basis. **_hsteps** can take one real value or a vector of p real values (`Reals` object), where p is the number of points defining the trunk. After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

Examples:


```
Pyramid p1(_basis=Quadrangle(_v1=Point(0.,0.,0.), _v2=Point(2.,0.,0.), _v3=Point(1.,1.,0.),
    _v4=Point(-1.,2.,0.)), _apex=Point(0.,0.,1.), _nnodes=Numbers(20, 20, 20, 20, 10, 10, 10,
    10), _domain_name="Omega", _side_names="Gamma");
Pyramid p2(_basis=Quadrangle(_v1=Point(0.,0.,0.), _v2=Point(2.,0.,0.), _v3=Point(1.,1.,0.),
    _v4=Point(-1.,2.,0.)), _apex=Point(0.,0.,1.), _nnodes=Numbers(20, 10), _domain_name="Omega",
    _side_names="Gamma");
Pyramid p3(_v1=Point(0.,0.,0.), _v2=Point(2.,0.,0.), _v3=Point(1.,1.,0.), _v4=Point(-1.,2.,0.),
    _apex=Point(0.,0.,1.), _nnodes=Numbers(20, 10), _domain_name="Omega", _side_names="Gamma");
```

This is 3 definitions of the same `Pyramid` object, explaining the ability to give 2 values for **_nnodes**, instead of 8. Let's summarize information about geometrical keys on pyramids:

key(s)	authorized types	examples
_apex , _v1 , _v2 , _v3 , _v4	Point	_apex = Point (0.,0.,0.)
_basis	Polygon , Triangle , Quadrangle , Parallelogram , Rectangle , SquareGeo	_basis = Triangle (...)


Revolution trunks

A revolution trunk is a right trunk with circular basis.



So, to define a revolution trunk, you just need to give centers and radiuses of bases, using dedicated parameters **_center1**, **_center2**, taking a point or a single value (in this case, it is a 1D point), and **_radius1** and **_radius2**, taking one single positive value.

[RevTrunk](#) offers you more geometry abilities. Indeed, you can decide to add extensions at ends of the revolution trunk. Extensions can be : none, flat, ellipsoid, or cone. To define an extension, you just have to give its shape (type [GeometricEndShape](#), values : **_gesNone**, **_gesFlat**, **_gesEllipsoid** or **_gesCone**) and its height (called distance, as it is the distance of the apex/apogee from the corresponding basis of the trunk). Default values are flat with no height. Please also note that any extension means 4 additional edges and 4 additional side domains.



To do so, you will use parameters **_end1_shape** and **_end2_shape**, taking a [GeometricEndShape](#), and **_end1_distance** and **_end2_distance**, taking one single positive value.

_nnodes can take one single value or a vector of 3 or n values ([Numbers](#) object), where n is 3 times the number of edges of the basis. **_hsteps** can take one real value or a vector of p real values ([Reals](#) object), where p is the number of points defining the trunk. After these arguments, you can give names of main domain and side domains as explained in preamble of this section.


You also have an additional parameter, **_nbsubdomains**, enabling you to slice the main trunk (without its extensions) in as many domains as you want.

Let's summarize information about geometrical keys on revolution trunks:

key(s)	authorized types	examples
_center1, _center2	Point	_center2 = Point (0.,0.,0.)
_radius1, _radius2	single unsigned integer or real positive value	_radius1 =1, _radius2 =2.5
_end1_shape, _end2_shape	enum GeometricEndShape	_end1_shape =gesNone, _end2_shape =gesFlat, _end2_shape =gesCone, _end1_shape =gesEllipsoid, _end2_shape =gesSphere
_end1_distance, _end2_distance	single unsigned integer or real positive value	_end1_distance =1, _end2_distance =2.5
_nbsubdomains	single unsigned integer value	_nbsubdomains =2

Revolution cylinders

A revolution cylinder is a revolution trunk where both radii are equal. So, we need centers of both bases, and the radius.



To do so, you just have to give centers and radius of bases, using dedicated parameters **_center1**, **_center2**, taking a point or a single value (in this case, it is a 1D point), and **_radius**, taking one single positive value.

As [RevTrunk](#), [RevCylinder](#) offers you the ability to add extensions at ends of the revolution cylinder. See section 6.1.11 for how to define these extensions. To do so, you will use parameters **_end1_shape** and **_end2_shape**, taking a [GeometricEndShape](#), and **_end1_distance** and **_end2_distance**, taking one single positive value.

_nnodes can take one single value or a vector of 3 or n values ([Numbers](#) object), where n is 3 times the number of edges of the basis. **_hsteps** can take one real value or a vector of p real values ([Reals](#) object), where p is the number of points defining the cylinder. After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

You also have an additional parameter, **_nbsubdomains**, enabling you to slice the main cylinder (without its extensions) in as many domains as you want.

Examples:


```
RevCylinder r1(\center1=Point(0.,0.,0.), _center2=Point(5.,0.,0.), _radius=1, _nnodes=Numbers(10,
10, 10, 10, 10, 10, 10, 10, 10, 50, 50, 50, 50), _domain_name="Omega",
_side_names=Strings("Gamma", "Gamma", "Sigma", "Sigma", "Sigma", "Sigma"));
RevCylinder r2(\center1=Point(0.,0.,0.), _center2=Point(5.,0.,0.), _radius=1, _nnodes=Numbers(10,
10, 50), _domain_name="Omega", _side_names=Strings("Gamma", "Gamma", "Sigma", "Sigma",
"Sigma", "Sigma"));
```

Let's summarize information about geometrical keys on revolution cylinders:

key(s)	authorized types	examples
_center1, _center2	Point	_center1 = Point (0.,0.,0.)
_radius	single unsigned integer or real positive value	_radius =1, _radius =2.5
_end1_shape, _end2_shape	enum GeometricEndShape	_end1_shape =gesNone, _end2_shape =gesFlat, _end1_shape =gesCone, _end2_shape =gesEllipsoid, _end1_shape =gesSphere
_end1_distance, _end2_distance	single unsigned integer or real positive value	_end1_distance =1, _end2_distance =2.5
_nbsubdomains	single unsigned integer value	_nbsubdomains =2

Revolution cones

A revolution cone is a revolution trunk where second radius is equal to 0.



To define a revolution cone, you need to give a center, a radius, and an apex, through parameters **_center**, **_radius** and **_apex**. **_center** and **_apex** take a point or a single value (in this case, it is like a 1D point), whereas **_radius** takes a single positive value.

As [RevTrunk](#), [RevCone](#) offers you more the ability to add an extension to the basis of a revolution cone. See section 6.1.11 for how to define this extension. To do so, you will use parameters **_end_shape**, taking a [GeometricEndShape](#), and **_end_distance**, taking one single positive value.

_nnodes can take one single value or a vector of 2 or n values ([Numbers](#) object), where n is twice the number of edges of the basis. **_hsteps** can take one real value or a vector of p real values ([Reals](#) object), where p is the number of points defining the cone. After these arguments, you can give names of main domain and side domains as explained in preamble of this section.

You also have an additional parameter, **_nbsubdomains**, enabling you to slice the main cone (without its extension) in as many domains as you want.

Let's summarize information about geometrical keys on revolution cones:

key(s)	authorized types	examples
_apex, _center	Point	_apex=Point(0.,0.,0.)
_radius	single unsigned integer or real positive value	_radius=1, _radius=2.5
_end_shape	enum GeometricEndShape	_end_shape=gesNone, _end_shape=gesFlat, _end_shape=gesCone, _end_shape=gesEllipsoid, _end_shape=gesSphere
_end_distance	single unsigned integer or real positive value	_end_distance=1, _end_distance=2.5
_nbsubdomains	single unsigned integer value	_nbsubdomains=2

6.1.12 Definition of a geometry from its boundary

A loop geometry is a geometry defined by its boundaries. For example, instead of defining a triangle, you will define here the surface inside the closed boundary composed of 3 segments.

With XLI++ geometry engine, you can define 2D or 3D geometries, thanks to the following routines:

```

Geometry planeSurfaceFrom(const Geometry& boundary, String domName = String() );
Geometry ruledSurfaceFrom(const Geometry& boundary, String domName = String() );
Geometry volumeFrom(const Geometry& boundary, String domName = String() );

```

The first argument must be a "composite" geometry defined from curve boundaries (2D case) or surface boundaries (3D case) such that the result is closed.

Let's see an example using segments and circular arcs to define a mesh on a rectangle with rounded corners:

```

Point a(-1.5,-4.); Point b(1.5,-4.); Point c(2.,-3.5); Point d(2.,3.5);
Point e(1.5,4.); Point f(-1.5,4.); Point g(-2.,3.5); Point h(-2.,-3.5);
Segment s1(_v1=a, _v2=b, _nnodes=21, _domain_name="AB");
CircArc c1(_center=Point(3.5,0.5), _v1=b, _v2=c, _nnodes=5, _domain_name="BC");
Segment s2(_v1=c, _v2=d, _nnodes=11, _domain_name="CD");
CircArc c2(_center=Point(3.5,1.5), _v1=d, _v2=e, _nnodes=5, _domain_name="DE");
Segment s3(_v1=e, _v2=f, _nnodes=21, _domain_name="EF");
CircArc c3(_center=Point(0.5,1.5), _v1=f, _v2=g, _nnodes=5, _domain_name="FG");
Segment s4(_v1=g, _v2=h, _nnodes=11, _domain_name="GH");
CircArc c4(_center=Point(0.5,0.5), _v1=h, _v2=a, _nnodes=5, _domain_name="HA");
Geometry g=planeSurfaceFrom(s1+c1+s2+c2+s3+c3+s4+c4, "Omega");

```

The `planeSurfaceFrom` routine (or shorter `surfaceFrom`) is devoted to define surfaces from their boundaries. Segments and circular arcs must be defined with the same orientation (clockwise or counter-clockwise).

With such definitions of segments s1, s2, s3 and s4 and circular arcs c1, c2, c3 and c4, in previous example, the following definitions are right :

```

Geometry g=planeSurfaceFrom(s2+c2+s3+c3+s4+c4+s1+c1, "Omega");
Geometry g=planeSurfaceFrom(s1+s2+s3+s4+c1+c2+c3+c4, "Omega");

```

The order of components here, and also the first component, has no meaning, but they all are oriented in the same way.




Figure 6.1: Rectangular geometry with rounded corners, defined with the `surfaceFrom` routine

We tell you that it is also possible for 3D case. Here is an example of a geometry basically composed of a cube and a pyramid sharing one face:

```
Point a(0,0,0); Point b(2,0,0); Point c(2,2,0); Point d(0,2,0);
Point e(0,0,2); Point f(2,0,2); Point g(2,2,2); Point h(0,2,2)
Point i(4,1,1);
SquareGeo s1(_v1=a, _v2=b, _v4=e, _nnodes=11, _domain_name="S1");
SquareGeo s2(_v1=d, _v2=c, _v4=h, _nnodes=11, _domain_name="S2");
SquareGeo s3(_v1=a, _v2=b, _v4=d, _nnodes=11, _domain_name="S3");
SquareGeo s4(_v1=e, _v2=f, _v4=h, _nnodes=11, _domain_name="S4");
SquareGeo s5(_v1=a, _v2=d, _v4=e, _nnodes=11, _domain_name="S5");
Triangle t1(_v1=b, _v2=c, _v3=i, _nnodes=11, _domain_name="T1");
Triangle t2(_v1=c, _v2=g, _v3=i, _nnodes=11, _domain_name="T2");
Triangle t3(_v1=g, _v2=f, _v4=i, _nnodes=11, _domain_name="T3");
Triangle t4(_v1=f, _v2=b, _v4=i, _nnodes=11, _domain_name="T4");
Geometry vf=volumeFrom(s1+s2+s3+s4+s5+t1+t2+t3);
```




Figure 6.2: 3D geometry defined with the `volumeFrom` routine



3D loop geometries can be defined by a mix of 2D loop geometries and 2D canonical geometries.



Although C++ authorizes it, do not write loop geometries as follows:
`volumeFrom(Rectangle(a,b,d,11,11,"R1")+ldots);` You have to define the rectangle r_1 instead, as in the previous example.

6.1.13 Combining geometries

A composite geometry is a geometry defined from a list of canonical or loop geometries. It is for example the right way to define holes in your mesh, or to define multi-domains geometries.

How to define composite geometries ? It's easy, you just have to use the operators + and -.

Let's see a first example:

```
Rectangle r(_xmin=-3, _xmax=3, _ymin=-2, _ymax=2, _nnodes=Numbers(33,22), _domain_name="Omega");
Ellipse e(_center=Point(0,0), _xlength=1, _ylength=0.5, _nnodes=11);
Geometry gm=r-e;
Geometry gp=r+e;
```




Figure 6.3: Composite geometry of an ellipse inside a rectangle

In both cases, the ellipse is geometrically inside the rectangle. This hole will be meshed if you used the operator +, and not meshed if you use the operator -. Both operators can detect if a geometry is inside another geometry, in most of the cases, but the operator - always consider the second geometry as a hole of the first one, even if it is geometrically wrong.



If you forget to give a domain name for the right-hand side of the operator +, it will not be stored, so that you still will have a hole.

These operators work with any geometries as far as geometrical inclusion is easy enough to detect.

Using operators + and - to define composite geometries is not restricted to 2 components. You can define composite geometries with any number of components, and some of them can be loop geometries:

```
Ellipse e1(_center=Point(0.,0.), _v1=Point(4,0.), _v2=Point(0.,5.), _nnodes=12,
_domain_name="Omega1");
Point a(-1.5,-4.); Point b(1.5,-4.); Point c(2.,-3.5); Point d(2.,3.5);
Point e(1.5,4.); Point f(-1.5,4.); Point g(-2.,3.5); Point h(-2.,-3.5);
Segment s1(_v1=a, _v2=b, _nnodes=21, _domain_name="AB");
CircArc c1(_center=Point(3.5,0.5), _v1=b, _v2=c, _nnodes=5, _domain_name="BC");
Segment s2(_v1=c, _v2=d, _nnodes=11, _domain_name="CD");
CircArc c2(_center=Point(3.5,1.5), _v1=d, _v2=e, _nnodes=5, _domain_name="DE");
Segment s3(_v1=e, _v2=f, _nnodes=21, _domain_name="EF");
CircArc c3(_center=Point(0.5,1.5), _v1=f, _v2=g, _nnodes=5, _domain_name="FG");
Segment s4(_v1=g, _v2=h, _nnodes=11, _domain_name="GH");
CircArc c4(_center=Point(0.5,0.5), _v1=h, _v2=a, _nnodes=5, _domain_name="HA");
Geometry sf1=(surfaceFrom(s1+c1+s2+c2+s3+c3+s4+c4, "Omega2");
Ellipse e2(_center=Point(1.,2.), _v1=Point(1.5,2.), _v2=Point(1.,3.), _nnodes=12,
_domain_name="Omega3");
Ellipse e3(_center=Point(0.,0.), _v1=Point(0.5,0.), _v2=Point(0.,1.), _nnodes=12,
_domain_name="Omega4");
Rectangle r2(_xmin=5., _xmax=6., _ymin=0., _ymax=1., _nnodes=6, _domain_name="Omega5");
Segment s5(_v1=Point(5.3,0.5), _v2=Point(5.7,0.5), _nnodes=5);
CircArc c5(_center=Point(5.5,0.5), _v1=Point(5.7,0.5), _v2=Point(5.5,0.7), _nnodes=5);
CircArc c6(_center=Point(5.5,0.5), _v1=Point(5.5,0.7), _v2=Point(5.3,0.5), _nnodes=5);
Geometry sf2=surfaceFrom(s5+c5+c6, "Omega6");
Geometry gmulti=(e1+sf1)-(e2+e3)+r2-sf2;
```




Figure 6.4: Composite geometry with multiple components and inclusions between components



When at least 2 components share several vertices, several edges and/or several surfaces, everything works fine, shared geometrical entities are not duplicated.




Figure 6.5: Composite geometry with edges shared by components.

As far as composite geometries are concerned, XLIFE++ detects inclusions between canonical components. It is not always the case if components are loop geometries. Let's take the previous example, but this time, we want to mesh every domain.

Geometry `gmulti2=(e1+sf1)+(e2+e3)+r2+sf2;`




Figure 6.6: Composite geometry with multiple components and inclusions between components. Some inclusions are not detected correctly.

You can see that both holes of the rounded rectangle are not taken into account, whereas the half disk is correctly managed. Indeed, XLIFE++ can in most of the cases determine if a loop geometry is inside a canonical geometry but it can't determine if a canonical geometry is inside a loop geometry.

How to solve this problem ? By forcing it with the unary ! operator, and rewriting the composite expression if necessary, as in the following:

Geometry `gmulti3=e1+(sf1+!(e2+e3)+r2+sf2;`




Figure 6.7: Composite geometry with multiple components and inclusions between components. Some inclusions are forced.

When you write `sf1+!(e2+e3)`, you tell explicitly that the right operand (`e2+e3`) is forced be inside the left operand (`sf1`).



When at least two components intersect and the intersection has same dimension (2 surfaces whose intersection is a surface, for instance), the resulting mesh will not be generated properly. In this case, you must reconsider how to define your geometry.




Figure 6.8: Partial inclusion is forbidden

6.2 Transformations on geometries

XLiFE++ allows you to apply geometrical transformations on **Mesh**, **Geometry** and **Geometry** children objects. The main type is **Transformation**. It can be a canonical transformation or a composition of transformations.

6.2.1 Canonical transformations

In the following, we will consider straight lines and planes.

A straight line is fully defined by a point and a direction. The latter is a vector of components (2 or 3). This is a reason why we will write a straight line as follows : $(\Omega, \vec{d})$

A plane is fully defined by a point and a normal vector. This is a reason why we will write a plane as follows :
 $[\Omega, \vec{n}]$

Translations

Point B is the image of point A by a translation of vector $\vec{u}$ if and only if

$$\overrightarrow{AB} = \vec{u}$$

A translation can be defined by an STL vector (size 2 or 3) or its components:

```
Vector<Real> u;  
Real ux, uy, uz;  
Translation t1(u), t2(ux, uy), t3(ux, uy, uz);
```



u can be omitted. If so, its default value is the 3d zero vector. uy and uz can be omitted too. If so, their default value is 0.



As the `Vector` class inherits from `std::vector` you can use it in place of `Vector` because all prototypes are based on `std::vector`.

2d rotations

Point B is the image of point A by the 2d rotation of center Ω and of angle θ if and only if

$$\overrightarrow{\Omega B} = \begin{pmatrix} \cos \theta & -\sin \theta \\ \sin \theta & \cos \theta \end{pmatrix} \overrightarrow{\Omega A}$$

A 2d rotation is defined by a point and an angle (in radians):

```
Point omega;  
Real angle;  
Rotation2d r(omega, angle);
```



`angle` can be omitted. If so, its default value is 0 and `omega` can be omitted too. If so, its default value is the 3d zero point.

3d rotations

Point B is the image of point A by the 3d rotation of axis $(\Omega, \vec{d})$ and of angle θ (in radians) if and only if

$$\overrightarrow{\Omega B} = \cos \theta \overrightarrow{\Omega A} + (1 - \cos \theta) \overrightarrow{\Omega A} \cdot \vec{n} + \sin \theta \vec{n} \wedge \overrightarrow{\Omega A} \quad (\text{Rodrigues' rotation formulae})$$

where $\vec{n} = \frac{\vec{u}}{\|\vec{u}\|}$ (the unitary direction).

The direction can be defined by an STL vector or by its components:

```
Point omega;  
Vector<Real> d;  
Real dx, dy, dz;  
Real theta;  
Rotation3d r1(omega, d, theta), r2(omega, dx, dy, dz, theta);
```



In the first syntax, angle can be omitted. If so, its default value is 0. and d can also be omitted. If so, its default value is the 3d zero vector.
In the second syntax, dz can be omitted too. If so, its default value is 0.

Homotheties

Point B is the image of point A by the homothety of center Ω and of factor k if and only if

$$\overrightarrow{\Omega B} = k \overrightarrow{\Omega A}$$

Point omega(1.,2.,3.);
Real k=2.;
Homothety h(omega, k);



factor can be omitted. If so, its default value is 0. and omega can also be omitted. If so, its default value is the 3d zero vector.

Point reflections

Point B is the image of point A by the point reflection of center Ω if and only if

$$\overrightarrow{\Omega B} = -\overrightarrow{\Omega A}$$

It is a homothety of factor -1 and same center.

Point omega(1.,2.,3.);
PointReflection h(omega); // omega can still be omitted, as for homothety

2d reflections

Point B is the image of point A by the 2d reflection of axis $(\Omega, \vec{d})$ if and only if

$$\overrightarrow{AB} = 2\overrightarrow{AH} \quad \text{where } H \text{ is the orthogonal projection of } A \text{ on } (\Omega, \vec{d})$$

Point omega(1.,2.,3.);
Vector<Real> d(1.,0.,0.);
Real dx=1., dy=0.;
Reflection2d r1(omega, d), r2(omega, dx, dy);



In the first syntax, d can be omitted. If so, its default value is the 2d zero vector and omega can be omitted. If so, its default value is the 2d zero point.

3d reflections

Point B is the image of point A by the 2d reflection of plane $[\Omega, \vec{n}]$ if and only if

$$\overrightarrow{AB} = 2\overrightarrow{AH} \quad \text{where } H \text{ is the orthogonal projection of } A \text{ on } [\Omega, \vec{n}]$$

```

Point omega(1.,2.,3.);
Vector<Real> n;
Real nx, ny, nz;
Reflection3d r1(omega, n), r2(omega, nx, ny, nz);

```



In the first syntax, n can be omitted. If so, its default value is the 3d zero vector and omega can be omitted. If so, its default value is the 3d zero point.

6.2.2 Composition of transformations

To define a composition of transformations, you can use the operator `*` between canonical transformations, an is the following example:

```

Rotation2d r1(Point(0.,0.), 120.);
Reflection2d r2(Point(1.,-1.), 1.,2.5, -3.);
Translation t1(-1.,4.);
Homothety h (Point(-1.,0.), -3.2);
Transformation t = r1*h*r2*t1;

```

Composition `*` has to be understood as usual composition operator $\circ$: $t(P)=r1(h(r2(t1(P))))$.

6.2.3 Applying transformations

How to apply a transformation ?

In this paragraph, we will look at the `Cube` object, but you have same functions for any canonical or composite `Geometry`.

If you want to apply a transformation and modify the input object, you can use one of the following functions:

```

!!! apply a geometrical transformation on a Cube
Cube& Cube::transform(const Transformation& t);
!!! apply a translation on a Cube
Cube& Cube::translate(std::vector<Real> u = std::vector<Real>(3,0.));
Cube& Cube::translate(Real ux, Real uy = 0., Real uz = 0.);
!!! apply a rotation 2d on a Cube
Cube& Cube::rotate2d(const Point& c = Point(0.,0.), Real angle = 0.);
!!! apply a rotation 3d on a Cube
Cube& Cube::rotate3d(const Point& c = Point(0.,0.,0.), std::vector<Real> u =
    std::vector<Real>(3,0.), Real angle = 0.);
Cube& Cube::rotate3d(Real ux, Real uy, Real angle);
Cube& Cube::rotate3d(Real ux, Real uy, Real uz, Real angle);
Cube& Cube::rotate3d(const Point& c, Real ux, Real uy, Real angle);
Cube& Cube::rotate3d(const Point& c, Real ux, Real uy, Real uz, Real angle);
!!! apply a homothety on a Cube
Cube& Cube::homothetize(const Point& c = Point(0.,0.,0.), Real factor = 1.);
Cube& Cube::homothetize(Real factor);
!!! apply a point reflection on a Cube
Cube& Cube::pointReflect(const Point& c = Point(0.,0.,0.));
!!! apply a reflection2d on a Cube
Cube& Cube::reflect2d(const Point& c = Point(0.,0.), std::vector<Real> u =
    std::vector<Real>(2,0.));
Cube& Cube::reflect2d(const Point& c, Real ux, Real uy = 0.);
!!! apply a reflection3d on a Cube
Cube& Cube::reflect3d(const Point& c = Point(0.,0.,0.), std::vector<Real> u =
    std::vector<Real>(3,0.));
Cube& Cube::reflect3d(const Point& c, Real ux, Real uy, Real uz = 0.);

```

For instance,

```
Cube c;  
c.translate(0.,0.,1.);
```

If you want now to create a new **Cube** by applying a transformation on a **Cube**, you should use one of the following functions instead:

```
/// apply a geometrical transformation on a Cube (external)  
Cube transform(const Cube& m, const Transformation& t);  
/// apply a translation on a Cube (external)  
Cube translate(const Cube& m, std::vector<Real> u = std::vector<Real>(3,0.));  
Cube translate(const Cube& m, Real ux, Real uy = 0., Real uz = 0.);  
/// apply a rotation 2d on a Cube (external)  
Cube rotate2d(const Cube& m, const Point& c = Point(0.,0.), Real angle = 0.);  
/// apply a rotation 3d on a Cube (external)  
Cube rotate3d(const Cube& m, const Point& c = Point(0.,0.,0.), std::vector<Real> u =  
    std::vector<Real>(3,0.), Real angle = 0.);  
Cube rotate3d(const Cube& m, Real ux, Real uy, Real angle);  
Cube rotate3d(const Cube& m, Real ux, Real uy, Real uz, Real angle);  
Cube rotate3d(const Cube& m, const Point& c, Real ux, Real uy, Real angle);  
Cube rotate3d(const Cube& m, const Point& c, Real ux, Real uy, Real uz, Real angle);  
/// apply a homothety on a Cube (external)  
Cube homothetize(const Cube& m, const Point& c = Point(0.,0.,0.), Real factor = 1.);  
Cube homothetize(const Cube& m, Real factor);  
/// apply a point reflection on a Cube (external)  
Cube pointReflect(const Cube& m, const Point& c = Point(0.,0.,0.));  
/// apply a reflection2d on a Cube (external)  
Cube reflect2d(const Cube& m, const Point& c = Point(0.,0.), std::vector<Real> u =  
    std::vector<Real>(2,0.));  
Cube reflect2d(const Cube& m, const Point& c, Real ux, Real uy = 0.);  
/// apply a reflection3d on a Cube (external)  
Cube reflect3d(const Cube& m, const Point& c = Point(0.,0.,0.), std::vector<Real> u =  
    std::vector<Real>(3,0.));  
Cube reflect3d(const Cube& m, const Point& c, Real ux, Real uy, Real uz = 0.);
```

For instance,

```
Cube c1;  
Cube c2=translate(c1,0.,0.,1.);
```



Of course, you can not apply a 2d rotation or a 2d reflection for geometries defined by 3d points !

What does a transformation really do ?

Applying a transformation on an object means computing the image of each point defining the object. But it can also change names.

When you create a new object by applying a transformation on an object, names are modified. Indeed, the transformation add a suffix "_prime". It concerns geometry names and sidenames.



When you transform a **Geometry**, it also applies the transformation on the underlying bounding box.

6.3 Extrusion of geometries

This is another way to define geometries : by extrusion of geometries of lesser dimension. Extruded geometries can be surfaces or volumes, defined by a geometry (the section of the extruded geometry) and a geometrical transformation. This feature can be used to generate meshes with the GMSH interface with some restrictions about the transformation : only translations or rotations are authorized. There is also another parameter : the number of layers. Let's see the following figures:




Figure 6.9: On the left, extrusion of a disk by a translation, with 3 layers. On the right, extrusion of a circular arc by rotation, with 4 layers

6.3.1 How to apply an extrusion ?

XLIFE++ offers 4 variants of the same function to define a `Geometry` by extrusion, enabling to give the domain name to the extruded geometry and to its sides. Sides numbering is as follows : first, the geometry used as section of the extrusion, second, the other section, and next the lateral surfaces generated by the extrusion.

```
Geometry extrude(const Geometry& g, const Transformation& t, Number layers);
Geometry extrude(const Geometry& g, const Transformation& t, Number layers, String domName);
Geometry extrude(const Geometry& g, const Transformation& t, Number layers, Strings sidenames);
Geometry extrude(const Geometry& g, const Transformation& t, Number layers, String domName,
  Strings sidenames);
```

The `Geometry` given to the `extrude` function can be:

- A canonical one (1D or 2D). Here, a `CircArc`:

```
Point b(1.5, -4., 0.);
Point c(2., -3.5, 0.);
CircArc g(_center=Point(1.5, -3.5, 0.), _v1=b, _v2=c, _nnodes=5, _domain_name="BC");
Geometry e2d=extrude(g, Translation(0., 0., 4.), 5, "Omega");
```




Figure 6.10: Extrusion of a circular arc by translation, with 5 layers

- A loop geometry (1D or 2D). Here, a rounded rectangle defines as in Figure 6.34:

```
Point a(-1.5,-4.,0.); Point b(1.5,-4.,0.); Point c(2.,-3.5,0.); Point d(2.,3.5,0.);
Point e(1.5,4.,0.); Point f(-1.5,4.,0.); Point g(-2.,3.5,0.); Point h(-2.,-3.5,0.);
Segment s1(_v1=a, _v2=b, _nnodes=21, _domain_name="AB");
CircArc c1(_center=Point(3.5,0.5,0.), _v1=b, _v2=c, _nnodes=5, _domain_name="BC");
Segment s2(_v1=c, _v2=d, _nnodes=11, _domain_name="CD");
CircArc c2(_center=Point(3.5,1.5,0.), _v1=d, _v2=e, _nnodes=5, _domain_name="DE");
Segment s3(_v1=e, _v2=f, _nnodes=21, _domain_name="EF");
CircArc c3(_center=Point(0.5,1.5,0.), _v1=f, _v2=g, _nnodes=5, _domain_name="FG");
Segment s4(_v1=g, _v2=h, _nnodes=11, _domain_name="GH");
CircArc c4(_center=Point(0.5,0.5,0.), _v1=h, _v2=a, _nnodes=5, _domain_name="HA");
Geometry g=planeSurfaceFrom(s1+c1+s2+c2+s3+c3+s4+c4, "Omega");
Geometry e3d=extrude(g, Translation(0.,0.,4.), 10, "Omega");
```




Figure 6.11: Extrusion of a rounded rectangle (loop geometry) by a rotation, with 10 layers

- Every composite geometry composed exclusively of a geometry and its holes (1D or 2D). That is to say only operator- or operator-= is used to define the geometry:

```
Ellipse e1(_center=Point(0.,0.,0.), _v1=Point(4,0.,0.), _v2=Point(0.,5.,0.), _nnodes=12,
_domain_name="Omega1", _side_names=Strings("Gamma_1","Gamma_2","Gamma_3","Gamma_4"));
Ellipse e2(_center=Point(1.,2.,0.), _v1=Point(1.5,2.,0.), _v2=Point(1.,3.,0.), _nnodes=12,
_domain_name="Omega3", _side_names=Strings("Gamma_9","Gamma_10","Gamma_11","Gamma_12"));
Geometry e3d2=extrude(e1-e2, Rotation3d(Point(5.,0.,0.), 0., 5., 0., pi_/2.), 10, "Omega",
"Gamma");
```




Figure 6.12: Extrusion of an ellipse with an elliptic hole by rotation, with 10 layers

6.3.2 How to define names of lateral domains of an extrusion ?

Instead of giving the same name to every lateral surface of an extrusion, you can give a name for each of them, but what about sides numbering ?

First example, let's take the extrusion of a `CircArc`:

```
Point b(1.5, -4., 0.);
Point c(2., -3.5, 0.);
CircArc g(_center=Point(1.5, -3.5, 0.), _v1=b1, _v2=c1, _nnodes=5, _domain_name="BC");
Geometry e2d=extrude(g, Translation(0., 0., 4.), 5, "Omega", Strings("Gamma1", "Gamma2"));
```

In Figure 6.10, point *b* is the front below left corner and point *c* is the front top right corner. As *g* is defined from *b* to *c*, the first lateral side, corresponding to domain `Gamma1`, will be the edge below. If you had defined *g* from *c* to *b*, `Gamma1` would have corresponded to the edge above.

Second example, let's take the extrusion of an ellipse with an elliptic hole:

```
Ellipse e1(_center=Point(0., 0., 0.), _v1=Point(4., 0., 0.), _v2=Point(0., 5., 0.), _nnodes=12,
_domain_name="Omega1");
Ellipse e2(_center=Point(1., 2., 0.), _v1=Point(1.5, 2., 0.), _v2=Point(1., 3., 0.), _nnodes=12,
_domain_name="Omega3");
Geometry e3d3=extrude(e1-e2, Rotation3d(Point(5., 0., 0.), 0., 5., 0., pi_/2.), 10, "Omega",
Strings("Gamma1", "Gamma2", "Gamma3", "Gamma4", "Gamma5", "Gamma6", "Gamma7", "Gamma8"));
```

This time lateral surfaces are ordered as follows:

- Lateral surfaces from the outer ellipse are ordered the same way as borders of the ellipse
- Lateral surfaces from the inner ellipse (and every hole in general) are ordered in the reverse order of borders of the ellipse



Contrary to GMSH, you can extrude a geometry by rotation of angle greater than π , by splitting extrusion in 2 half extrusions when angle is not 2π or in 4 quarter extrusions when angle is 2π . As a result, the number of lateral surfaces is multiplied by 2 or 4.

6.3.3 Example: definition of a conesphere

To define geometries based on cones, you always have to use extrusions. It is the case for the conesphere:

```

Real rb=1., hc=3.;
Real hs=rb*rb/hc;
Real rs=sqrt(rb*rb + hs*hs);

Point origin(0.,0.,0.), apex(0.,0.,hc), p1(rb,0.,0.), p2(0.,0.,-hs-rs);

Segment s1(_v1=p1, _v2=apex, _hsteps=0.05);
Segment s2(_v1=apex, _v2=origin, _hsteps=0.05);
Segment s3(_v1=origin, _v2=p2, _hsteps=0.05);
CircArc c1(_center=Point(0.,0.,-cssphereheight), _v1=p2, _v2=p1, _hsteps=0.05);
Disk d1(_center=0.5*p1, _v1=0.5*p1+Point(0.2*rb,0.,0.), _v2=0.5*p1+Point(0.,0.,0.2*rb),
_domain_name="Sigma", _hsteps=0.05);

Geometry base=planeSurfaceFrom(s2+s3+c1+s1, "Gamma");
Geometry g=extrude(base, Rotation3d(Point(0.,0.,0.), 0., 0., 1., 2.*pi_), "Omega1",
Strings("Gamma1", "Gamma2", "Gamma3", "Gamma4", "Gamma5", "Gamma6", "Gamma7", "Gamma8"));

```




Figure 6.13: Mesh of a conesphere

6.4 Defining a mesh from a geometry

XLiFE++ owns some constructors that allow to create meshes based on simple geometries in one, two or three dimensions. The constructors to use are defined as follows:

```

/// constructor from 1D geometries
Mesh (const Geometry& g, Number order = 1, MeshGenerator mg = _defaultGenerator,
      const String& name = "");
/// constructor from 2D or 3D geometries
Mesh (const Geometry& g, ShapeType sh, Number order = 1, MeshGenerator mg = _defaultGenerator,
      const String& name = "");
/// constructor from 2D or 3D geometries with additional options (up to 3)
Mesh (const Geometry& g, ShapeType sh, Number order = 1, MeshGenerator mg = _defaultGenerator,
      MeshOption o1, const String& name = "");
Mesh (const Geometry& g, ShapeType sh, Number order = 1, MeshGenerator mg = _defaultGenerator,
      MeshOption o1, MeshOption o2, const String& name = "");
Mesh (const Geometry& g, ShapeType sh, Number order = 1, MeshGenerator mg = _defaultGenerator,
      MeshOption o1, MeshOption o2, MeshOption o3, const String& name = "");

```

The arguments are:

`g` is the geometrical object to be meshed (such as `Segment`, `Quadrangle`, `Hexahedron`, ..., all of them being declared in the file `geometries.hpp`),

`sh` is the shape of the mesh elements (`_segment`, `_triangle`, `_quadrangle`, `_tetrahedron`, `_hexahedron`),

`order` is the interpolation order of the mesh elements ; it depends on the way the mesh is generated (see below),

`mg` defines the way the object is computed:

- `_structured` : a structured mesh can be built for canonical geometries only (`Segment`, `Parallelogram`, `Rectangle`, `Square`, `Parallelepipiped`, `Cuboid` and `Cube`); the order of the mesh is necessarily one,
- `_subdiv` : an unstructured mesh can be built using the so-called subdivision basic algorithm for the following geometries : `Cube`, `Ball`, `RevTrunk`, `RevCone`, `RevCylinder`, `Disk` and `SetOfElems`; the order can be any integer $k > 0$,
- `_gmsh` : for more complicated geometries, with a nested call of the GMSH software; the order depends on the chosen shape (refer to GMSH documentation).

`oi` defines some additional options proposed by some mesh methods (mesh from parametrization and structured mesh of a parallelogram with triangles) and defined in the following enumeration:

```
enum MeshOption{_defaultMeshOption=0, _unstructuredMesh, _structuredMesh,
               _leftSplit, _rightSplit, _randomSplit, _alternateSplit}
```

`name` defines the mesh name.

Examples:

```
// P1 structured mesh of segment [0,1] with 10 nodes. Domain is Omega
Mesh m1D(Segment(_xmin=0., _xmax=1., _nnodes=10, _domain_name="Omega"), 1, _structured);
// P1 unstructured mesh of disk of center (0,0,1) and radius 2.5 with 40 nodes. Domain is Omega
// and side domain is Gamma
Mesh m2D(Disk(_center=Point(0.,0.,1.), _radius=2.5, _nnodes=40, _domain_name="Omega"
            _side_names="Gamma"), _triangle, 1, _subdiv);
// Q2 unstructured mesh (using gmsh) of cube [0,2]x[0,1]x[0,4] with 20 nodes on x edges, 10 nodes
// on y edges and 40 nodes on z edges
Mesh m3D(Cube(_v1=Point(0.,0.,0.), _v2=Point(2.,0.,0.), _v4=Point(0.,1.,0.), _v5=Point(0.,0.,4.),
            _nnodes=Numbers(20,10,40), _domain_name="Omega"), _hexahedron, 2, _gmsh);
```

This is described in more detail in next paragraph.

Moreover, it is possible to subdivide an existing mesh of order 1: a new mesh is created using the subdivision algorithm mentioned above. The corresponding constructor is defined as follows:

```
/// constructor from a mesh to be subdivided
Mesh (const Mesh& msh, Number nbsubdiv, Number order = 1);
```

The arguments are:

`msh` is the input mesh object, i.e. the given mesh to be subdivided ; it should consist of triangles, quadrangles, tetrahedra or hexahedra ;

`nbsubdiv` is the number of subdivisions to be performed ;

`order` is the order of the final mesh ; its default value is 1.

Example:

```
Mesh m1( "mesh.msh", "My Mesh", msh );
Mesh subm1( m1, 2 );
```

This builds a mesh subm1 which is obtained by subdividing twice the mesh m1, itself read from the file "mesh.msh".

Once a mesh is created, it is possible to get information about what it is made of using the function printInfo, which displays on the terminal general information about the mesh: characteristic data, domains, ...:

```
Mesh m1( "mesh.msh", "My Mesh", msh );
m1.printInfo();
```



If you want to mesh a 2D geometry with segment elements, only borders will be meshed. The same goes for 3D geometries mesh with triangles or quadrangles.

6.4.1 Structured internal meshing tools: structured generator

When the **structured mesh generator** is chosen (mg = _structured), one can create a mesh of order 1:

- of a segment,
- of a parallelogram with triangles or quadrangles,
- of a parallelepiped with hexahedra, prisms or pyramids.

One has to declare an object of type `Geometry`, more precisely of one of its derived type `Segment`, `Parallelogram`, `Rectangle`, `Square`, `Parallelepiped`, `Cuboid` or `Cube` using one of these constructors, that allow in particular to specify the mesh refinement by setting the number of points (nodes) on each edge, including the two endpoints.

Example 1:

```
Strings sn(2);
sn[0] = "Sigma_1";
Mesh mesh1dP1( Segment(_xmin=0, _xmax=1, _nnodes=11, _side_names=sn), 1, _structured, "P1 mesh of [0,1], step=0.1" );
```

This builds a mesh of the interval $[0, 1]$ with 10 subintervals. The boundary domain Sigma_1, corresponding to the lower bound 0 of the interval, will be created; the other one will not be created since it has no name. The second argument is the mesh order; in the case of a structured mesh, the only possible value is 1.

It can be noticed that the segment may have been defined by two points in the plane or in the space as well.

Example 2:

```
Strings sn(4);
sn[0] = "Gamma_1"; sn[2] = "Gamma_2";
Mesh mesh2dP1( Rectangle(_xmin=0, _xmax=1, _ymin=1, _ymax=3, _nnodes=Numbers(3, 5), _side_names=sn), _triangle, 1, _structured, "P1 mesh of [0,1]x[1,3]" );
```

This builds a mesh of the rectangle $[0, 1] \times [1, 3]$ with triangles. The interval $[0, 1]$ is subdivided into 2 subintervals; the interval $[1, 3]$ is subdivided into 4 subintervals. Only the two domains Gamma_1 and Gamma_2 will be created. For a rectangle $[a, b] \times [c, d]$, the correspondence of the sidenames is the following:

sideNames[0] is $[a, b] \times c$, sideNames[1] is $b \times [c, d]$,
sideNames[2] is $[a, b] \times d$, sideNames[3] is $a \times [c, d]$.

Some options may be used to control the splitting of elementary rectangle into triangles :

```
Rectangle R(_xmin=0, _xmax=1, _ymin=1, _ymax=3, _nnodes=Numbers(6, 10));
Mesh mesh2dP1l(R, _triangle, 1, _structured); // default is _leftSplit
Mesh mesh2dP1r(R, _triangle, 1, _structured, _rightSplit);
Mesh mesh2dP1a(R, _triangle, 1, _structured, _alternateSplit);
Mesh mesh2dP1s(R, _triangle, 1, _structured, _randomSplit);
```




Figure 6.14: left, right, alternate and random split of a P1 mesh of a rectangle

Example 3:

```
Strings sn(4);
sn[0] = "Sigma_1"; sn[1] = "Sigma_2";
Mesh mesh2dQ1(Rectangle(_xmin=1, _xmax=2, _ymin=1, _ymax=3, _nnodes=Numbers(3, 5),
    _side_names=sn), _quadrangle, 1, _structured, "Q1 mesh of [1,2]x[1,3]");
```

This builds a mesh of the rectangle $[1, 2] \times [1, 3]$ with quadrangles. Only the two domains Sigma_1 and Sigma_2 will be created. See example 2 for other commentaries.

Example 4:

```
Strings sn( "z=1", "z=5", "y=1", "y=3", "x=0", "x=1");
Mesh mesh3dQ1(Cuboid(_xmin=0, _xmax=1, _ymin=1, _ymax=3, _zmin=1, _zmax=5, _nnodes=Numbers(3, 5,
    9), _side_names=sn), _hexahedron, 1, _structured, "Q1 mesh of [0,1]x[1,3]x[1,5]");
```

This builds a mesh of the parallelepiped $[0, 1] \times [1, 3] \times [1, 5]$ with hexahedra. The interval $[0, 1]$ is subdivided into 2 subintervals ; the interval $[1, 3]$ is subdivided into 4 subintervals ; the interval $[1, 5]$ is subdivided into 8 subintervals. The 6 boundary domains will be created with their corresponding names. For a parallelepiped $[a, b] \times [c, d] \times [e, f]$, the correspondence of the sidenames is the following:

sideNames[0] is $[a, b] \times [c, d] \times e$, sideNames[1] is $[a, b] \times [c, d] \times f$,
sideNames[2] is $[a, b] \times c \times [e, f]$, sideNames[3] is $[a, b] \times d \times [e, f]$,
sideNames[4] is $a \times [c, d] \times [e, f]$, sideNames[5] is $b \times [c, d] \times [e, f]$.

6.4.2 Unstructured internal meshing tools: subdivision generator

When the **subdivision algorithm** is chosen (`mg = _subdiv`), one can create a mesh of any order based on the following volumetric geometries:

- the sphere meshed by tetrahedra,
- the cube meshed by tetrahedra or hexahedra,
- the cone or truncated cone, which may be a cylinder, meshed by tetrahedra or hexahedra.

The following surface geometries are also handled:

- the boundary of the sphere meshed by triangles,
- the boundary of the cube meshed by quadrangles,
- the boundary of the cone or truncated cone meshed by triangles or quadrangles,
- the disk meshed by triangles or quadrangles,
- mesh built from an initial set of triangles or quadrangles in 2D or 3D.

The principle is to start from an initial mesh, a kind of “seed” mesh, consisting of a set of elements, and build the mesh by subdividing each of them by cutting each edge in the middle until a prescribed so-called “subdivision level” is reached. A subdivision level equal to 0 gives a mesh reduced to the initial mesh. A triangle and a quadrangle is subdivided into 4 pieces ; a tetrahedron and a hexahedron is subdivided into 8 pieces. Thus, at each subdivision, the number of elements of the mesh is multiplied by 4 for a surface mesh, by 8 for a volumetric one, and the characteristic dimension of the elements is halved.

One has to declare an object of type `Geometry`, more precisely of type `Sphere`, `Ball`, `Cube`, `RevTrunk`, `RevCone`, `RevCylinder`, `Disk` or `SetOfElems` using one of the available constructors, e.g.:

```
SetOfElems(const std::vector<Point>& pts, const std::vector<std::vector<number_t>>& elems, const
std::vector<std::vector<number_t>>& bounds, const ShapeType esh, const number_t nbsubdiv=1);
```

Mesh of a ball (or sphere) with tetrahedra

The seed of the mesh consists of a unique tetrahedron inside each octant of the Cartesian axes. We can choose the number of octants to be taken into account, from 1 to 8, to mesh different portions of the sphere. The figure 6.15 shows this in the case of a subdivision level equal to 2. Each figure corresponds to the result of the following code, using the unit sphere and *nbocants* varying from 1 to 8:

```
order = 1, nbpts=5, meshType = 1;
Ball sph(_center=Point(0.,0.,0.), _radius=1., _nbocants=nbocants, _nnodes=nbpts,
_type=meshType);
Mesh m(sph, _tetrahedron, order, _subdiv);
```



The class `Sphere` could have been used instead of `Ball`, leading to the same result.

Each color corresponds to a different boundary domain. The default value of the argument `meshType` is 1; setting it to 0 leads to a so-called flat mesh, where the points created during the algorithm are not projected onto the sphere, thus keeping the shape of the initial mesh. We can see the effect of this choice on figure 6.16.




Figure 6.15: Volumic meshes of the different portions of the ball according to the number of octants.




Figure 6.16: Volumic meshes of the different portions of the “flat ball” according to the number of octants.

If we specifically want the mesh inside the whole sphere, it can be useful to start from an icosahedron because of its geometric properties, which lead to a more isotropic mesh than the one based on the 8 octants of the space. On the other hand, there will be no interface planes defined.

In order to activate this option, the argument `nboctants` should simply be set to 0. The following code gives the figure 6.17, which shows both the round and flat results of the algorithm:

```

nbocants = 0, nbpts=5; meshType = 1;
Ball sph(_center=Point(0.,0.,0.), _radius=1., _nbocants=nbocants, _nnodes=nbpts,
_type=meshType);
order = 1;
Mesh m(sph, _tetrahedron, order, _subdiv);

meshType = 0;
Ball sph2(_center=Point(0.,0.,0.), _radius=1., _nbocants=nbocants, _nnodes=nbpts,
_type=meshType);
Mesh m2(sph2, _tetrahedron, order, _subdiv);

```




Figure 6.17: Volumic meshes starting from an icosahedron.

Mesh of a cube with tetrahedra or hexahedra

The selection of the octants is also used in the case of the cube as shown on the figure 6.18, which is the result of the following code, with no subdivision and *nbocants* varying from 1 to 8:

```

order = 1, nbpts=2;
Cube cube(_center=Point(0.,0.,0.), _length=2., _nbocants=nbocants, _nnodes=nbpts);
Mesh m(cube, _hexahedron, order, _subdiv);

```

Notice that the edge length of the total cube is 2, so that the cube in the first octant is the so-called unit cube. Apart the choice of the mesh element (tetrahedron or hexahedron), the main interest of this case is the easy creation of a L-shape domain (3 octants) and the Fichera corner (7 octants), classical benchmark problem in the analysis of corner and edge singularities. It is shown on figure 6.18 in an unusual position; in order to put the missing cube in the first octant, one must apply a rotation, which is done by the following code:

```

order = 1, nbocants=7, nbpts=2;
Cube cube(_center=Point(0.,0.,0.), _length=2., _nbocants=nbocants, _nnodes=nbpts);
    cube.rotate3d(Point(0.,0.,0.), 1.,0.,0., pi);
Mesh m(cube, _hexahedron, order, _subdiv);

```

The two additional arguments define the rotation of angle 180 degrees around the first axis (X-axis); the result is shown on figure 6.18, at the last position (bottom right). If necessary, one can specify one or two more rotations in the form (angle, naxis). The angle is to be given in degrees and naxis defines the rotation axis: it is the number of the absolute axis, thus 1, 2 or 3.




Figure 6.19: Volumic meshes of the “unit” cylinder with tetrahedra and hexahedra.

Obviously, this is a poor approximation of the cylinder. To get a more accurate description, the user can then increase the number of elements (greater value of `nbsubdiv`) or increase the approximation order (or both).

In the case of a tetrahedron mesh, each end-plane may be covered by a “hat”, that is to say a solid whose shape may be a cone or an ellipsoid. The last drawing of figure 6.19 shows such a configuration, with an ellipsoid on the side of P1 (keyword `_gesEllipsoid`) whose apex is at `radius/2` from the basis of the cylinder, and a cone on the side of P2 (keyword `_gesCone`) whose apex is at `radius` from the other basis of the cylinder. It is obtained by the following code:

```
radius=1.;
nbpts=5;
RevCylinder cyl2e(_center1=Point(0.,0.,0.), _center2=Point(0.,0.,1.), _radius=radius,
_end1_shape=_gesEllipsoid, _end1_distance=radius/2, _end2_shape=_gesCone,
_end2_distance=radius, _nnodes=nbpts);
order=1;
Mesh P1VolMeshTetCylE(cyl2e, _tetrahedron, order, _subdiv);
```

Two other keywords exist: `_gesNone` and `_gesFlat`. They have an equivalent meaning in the case of a solid body. They are the default value and indicate that no “hat” should be added at the corresponding end.

Mesh of a cone or a truncated cone with tetrahedra or hexahedra

A truncated cone of revolution is defined by an axis, given by two points P1 and P2, delimited by the two planes containing the two points and orthogonal to the axis. The two circular sections are defined by two radii. The following code produces the first two meshes shown on figure 6.20:

```
nbpts=5;
radius1=0., radius2=1.;
Point P1(-1.,-1.,0.), P2(0.,0.,2.);
RevCone cone(_center=P2, _radius=radius2, _apex=P1, _nnodes=nbpts);
order=1;
Mesh mT(cone, _tetrahedron, order, _subdiv);

radius1=0.5;
RevTrunk cone2(_center1=P1, _radius1=radius1, _center2=P2, _radius2=radius2, _nnodes=nbpts);
Mesh mH(cone2, _hexahedron, order, _subdiv);
```

The number of slices is 0, which means that a suitable default value is automatically computed from the length of the axis and the radii. The first object is a “true” cone since one radius is 0; it can be meshed exactly with tetrahedra. Using hexahedra for this geometry is not advised since the elements will be degenerated at the apex of the cone. Moreover, the radius cannot be 0, it should be at least $1.e-15$, leading to a “near true” cone, but

with highly degenerated hexahedra close to the apex. Hexahedra are more suitable to build a truncated cone ; an example is shown on the middle drawing of the figure 6.20.




Figure 6.20: Volumic meshes of the cone and truncated cone with tetrahedra and hexahedra.

The following code produces the last mesh shown on figure 6.20:

```
nbpts=5;
radius1=0.6, radius2=1.;
RevTrunk cone1(_center1=Point(-1.,-1.,0.), _radius1=radius1, _center2=Point(0.,0.,2.),
    _radius2=radius2, _end1_shape=gesCone, _end1_distance=1.5, _end2_shape=gesEllipsoid,
    _end2_distance=0.7, _nnodes=nbpts);
order=1;
Mesh mTE(cone1, _tetrahedron, order, _subdiv);
```

In the same way as for the cylinder, the truncated cone can be “covered” with a solid. This is only available for a mesh made of tetrahedra. We show a cone and an ellipsoid put at each end of a truncated cone, respectively on the side of P1 and on the side of P2.

Mesh of a sphere with triangles

The same logic described previously for a mesh of tetrahedra apply here for a mesh of triangles. The following code leads to meshes of the boundary of the unit sphere, and the result is shown on figure 6.21:

```
order = 1, nbpts=5;
Ball sph(_center=Point(0.,0.,0.), _radius=1., _nbocants=nbocants, _nnodes=nbpts);
Mesh m(sph, _triangle, order, _subdiv);
```




Figure 6.21: Surfacic meshes of the different portions of the boundary of the sphere according to the number of octants.

Again, if the argument `meshType` is set to 0, we get the “flat” version of the meshes, i.e. the meshes obtained from the subdivision of the nbocants initial triangles (see figure 6.22).




Figure 6.22: Surfacic meshes of the different portions of the “flat sphere” according to the number of octants.

If we specifically want the mesh of the whole sphere, it can be useful to start from an icosahedron because of its geometric properties, which lead to a more isotropic mesh than the one based on the 8 octants of the space. On the other hand, there will be no interface planes defined.

In order to activate this option, the argument `nbocants` should simply be set to 0. The following code gives the figure 6.23, which shows both the round and flat results of the algorithm:

```
nbocants = 0, nbpts=5; meshType = 1;
Ball sph(_center=Point(0.,0.,0.), _radius=1., _nbocants=nbocants, _nnodes=nbpts,
_type=meshType);
```

```

order = 1;
Mesh m(sph, _triangle, order, _subdiv);

meshType = 0;
Ball sph2(_center=Point(0.,0.,0.), _radius=1., _nbocants=nbocants, _nnodes=nbpts,
    _type=meshType);
Mesh m2(sph2, _triangle, order, _subdiv);

```




Figure 6.23: Surfacic meshes starting from an icosahedron.

Mesh of a cube with quadrangles

We can obtain the mesh of the surface of a cube, or part of it, with quadrangles, by using the same logic described just above for the sphere. Consider the following code:

```

order = 1, nbpts=2;
Cube cube(_center=Point(0.,0.,0.), _length=2., _nbocants=nbocants, _nnodes=nbpts);
Mesh m(cube, _quadrangle, order, _subdiv);

```

Letting nbocants vary from 1 to 8, then 0, lead to the objects shown on figure 6.24 below.




Figure 6.24: Surfacic meshes of the different portions of the cube according to the number of octants.

The last object (nbocants = 0) is the simplest mesh of a cube made of 6 quadrangles (squares here). By subdividing it once, we get the previous yellow object (nbocants = 8) made of 24 quadrangles.

Mesh of a cone or a truncated cone with triangles

We can build a mesh of the surface of a truncated cone with triangles. The following code produces the first two drawings of the figure 6.25:

```
radius=1.;
nbslices=1, nbpts=3;
Point P1(0.,0.,0.), P2(0.,0.,1.);
RevCylinder cyl1(_center1=P1, _center2=P2, _radius=radius, _nnodes=nbpts);
order=1;
Mesh m1(cyl, _triangle, order, _subdiv, fname);

nbpts=5;
RevCylinder cylE(_center1=P1, _center2=P2, _radius=radius, _end1_shape=_gesFlat,
_end1_distance=0., _end2_shape=_gesNone, _end2_distance=0., _nnodes=nbpts);
Mesh m1E(cylE, _triangle, order, _subdiv);
```




Figure 6.25: Surfacic meshes of a cylinder.

```
nbpts=5;
radius1=0.5, radius2=1.;
Point P1(-1.,-1.,0.), P2(0.,0.,2.);
RevTrunk cone3(_center1=P1, _radius1=radius1, _center2=P2, _radius2=radius2,
    _end1_shape=_gesNone, _end1_distance=0., _end2_shape=_gesFlat, _end2_distance=0.,
    _nnodes=nbpts);
order=1;
Mesh mI(cone3, _triangle, order, _subdiv);

RevTrunk cone1(_center1=P1, _radius1=radius1, _center2=P2, _radius2=radius2,
    _end1_shape=_gesCone, _end1_distance=1.5, _end2_shape=_gesEllipsoid, _end2_distance=0.7,
    _nnodes=nbpts);
Mesh mIE(cone1, _triangle, order, _subdiv);
```




Figure 6.26: Surfacic meshes of a truncated cone.

Mesh of a cone or a truncated cone with quadrangles

We can build a mesh of the surface of a truncated cone with quadrangles. The following code produces the first two drawings of the figure 6.27:

```
nbpts=5;
radius1=0.5, radius2=1.;
Point P1(-1.,-1.,0.), P2(0.,0.,2.);
RevTrunk cone2(_center1=P1, _radius1=radius1, _center2=P2, _radius2=radius2, _nnodes=nbpts);
order=1;
Mesh mQ(cone2, _quadrangle, order, _subdiv);
```

```

RevTrunk cone3(_center1=P1, _radius1=radius1, _center2=P2, _radius2=radius2,
_end1_shape=_gesNone, _end1_distance=0., _end2_shape=_gesFlat, _end2_distance=0.,
_nnodes=nbpts);
Mesh mQF(cone3, _quadrangle, order, _subdiv, "mQF");
mQF.printInfo();

```

The left truncated cone is opened at both ends (this is the default) ; thus it has two boundaries shown in green (bottom) and orange (top). The object cone2 is the same as the one used previously to make the mesh of hexahedra (see figure 6.20).

The second drawing shows the same object bearing a "lid" on its top (on the side of P2). Indeed, such a truncated cone may be closed at one or both ends by a plane "lid". This is obtained by specifying the geometric end shape to be used at each end: `_gesNone` means that the cone is left opened, which is the default behavior, and `_gesFlat` means that a plane "lid" is requested. The objet proposed in this example has thus one boundary at its other end (on the side of P1), shown as an orange line.

In both cases, the requested number of slices is 0 ; thus, the algorithm decided to create two slices displayed in magenta and yellow. The result of the instruction `mQF.printInfo()`; is the following:

```

Mesh'mQF' (cone - Quadrangle mesh)
space dimension : 3, element dimension : 2
Geometry of shape type revolution volume based on cone of dimension 3,
BoundingBox [-1.45412,0.908248]x[-1.45412,0.908248]x[-0.288675,2.57735], names of variable : x,
y, z
number of elements : 208, number of vertices : 217, number of nodes : 217, number of domains : 5
domain number 0: Omega (whole domain)
domain number 1: Sigma_1 (End subdomain on the side of end point 2)
domain number 2: Sigma_2 (Slice 1)
domain number 3: Sigma_3 (Slice 2)
domain number 4: Kappa_1 (Boundary: End curve on the side of end point 1)

```




Figure 6.27: Surfacic meshes of a cone and a cylinder.

The last drawing shows the surfacic mesh of a cylinder, since it is a particular kind of cone. The cylinder is the same as the one shown on figure 6.19. The code that produces this mesh is:

```

radius=1.;
nbpts=3;
Point P1(0.,0.,0.), P2(0.,0.,1.);
RevCylinder cyl(_center1=P1, _center2=P2, _radius=radius, _nnodes=nbpts);
order=1;
Mesh mQCyl(cyl, _quadrangle, order, _subdiv);

```

The cylinder is opened at both ends and thus has two boundaries shown as a green line and an orange line.

Mesh of a disk or a part of a disk

We can build the mesh of a disk or a portion of a disk, with triangles or quadrangles. Using the following code, we get the result shown on figure 6.28.

```
radius=2.;
nbpts=5, order=1;
Disk pdisk(_center=Point(0.,1.), _radius=radius, _angle1=10., _angle2=300., _nodes=nbpts);
Mesh meshTriDisk(pdisk, _triangle, order, _subdiv);
Mesh meshQuaDisk(pdisk, _quadrangle, order, _subdiv);
```




Figure 6.28: Meshes of a portion of disk with triangles and quadrangles.

Mesh from a set of triangles or quadrangles

This possibility is designed to build a mesh starting from an elementary set of elements. Generally, this initial mesh is build “manually”. This gives a flexible mean to create a mesh which cannot be obtained with another constructor, but without having to resort to the help of a more complicated solution (like an external mesh generator in particular).

Such meshes can be made in 2D or in 3D with triangles or quadrangles. Figure 6.29 shows two examples, in 3D with triangles, in 2D with quadrangles on a domain with a hole.




Figure 6.29: Meshes from initial set of triangles and quadrangles.

The program that produces it looks like the following:

```
order = 1, nbsubdiv = 1;
SetOfElems sot(tpts, telems, tbounds, _triangle, nbsubdiv);
Mesh mI(sot, _triangle, order, _subdiv);
SetOfElems soq(qpts, qelems, qbounds, _quadrangle, nbsubdiv);
Mesh mQ(soq, _quadrangle, order, _subdiv);
```

The mesh of triangle is based on an initial set of 2 triangles {1,2,3} and {1,4,2}, stored in the vector elems. The 4 points are Point(0.,0.,0.), Point(1.,0.,0.), Point(0.,1.,0.3), Point(0.,-1.,0.3) stored in the vector tpts. Four boundaries are defined. A boundary is simply defined by the list of point numbers lying on it, in any order. Thus, here, the four boundaries are {1,4}, {4,2}, {2,3} and {1,3}; they are stored in the vector tbounds. The same apply for the set of quadrangles.

6.4.3 Meshing tool with nested call to GMSH: gmsh generator

Using the GMSH interface to define meshes allows you to define more canonical geometries than both previous generators:

- Segments, ellipses, circles, elliptic or circular arcs as 1D geometries;
- Quadrangles, rectangles, squares, disks, elliptical surfaces, spheres, ellipsoids, triangles as 2D geometries with either triangular or quadrangular mesh elements;
- Hexahedra, parallelepipeds, cubes, balls, tetrahedra, cylinders, prisms, pyramids as 3D geometries with either tetrahedral or hexahedral mesh elements.

When you use it, 2 files will be generated in your directory :

xlfepp_script.geo This is the input file of GMSH. To simplify its write, we developed a macro file includes in this one. If you look at this file, you will find a very elegant way to define meshes with GMSH.

xlfepp_script.msh This is the real mesh file, generated by a system call to GMSH from the .geo file. This file is loaded by XLIFE++.

Next to this, you can define 2 types of complicated geometries : the so-called "composite" and "loop" geometries.

If you want to define a geometry that XLIFE++ can not directly handle, you can use GMSH directly.

Examples of composite and loop geometries

Please see subsection 6.1.13 for definition of composite geometries and the use of operators + and -, and see subsection 6.1.12 for definition of loop geometries and the use of [surfaceFrom](#) and [volumeFrom](#) routines. Let's see a first example of an ellipse inside a rectangle:

```
Rectangle r(_xmin=-3, _xmax=3, _ymin=-2, _ymax=2, _nnodes=Numbers(33,22), _domain_name="Omega");
Ellipse e(_center=Point(0,0), _xlength=1, _ylength=0.5, _nnodes=11);
Mesh m1(r-e, _triangle, 1, _gmsh);
Mesh m2(r+e, _triangle, 1, _gmsh);
```




Figure 6.30: GMSH view of $m1$ and $m2$

The following example shows how it works in 3D with a parallelepiped hole inside an ellipsoid:

```

Ellipsoid ed1(_center=Point(0.,0.,0.), _v1=Point(3.,0.,0.), _v2=Point(0.,2.,0.),
_v3=Point(0.,0.,1.), _nnodes=16);
Parallelepiped pa1(_v1=Point(-0.5,-0.5,-0.5), _v2=Point(0.5,-0.5,-0.5), _v4=Point(-0.5,0.5,-0.5),
_v5=Point(-0.5,-0.5,0.5), _nnodes=3);
Mesh mesh3dP1Composite(ed1-pa1,_tetrahedron,1,_gmsh);

```




Figure 6.31: GMSH view of a 3d composite geometry (ellipsoid - parallelepiped)




Figure 6.32: GMSH view of the hole of a 3d composite geometry (ellipsoid - parallelepiped)

Let's see now an example with more than 2 components:

```
Strings sn("Gamma_1", "Gamma_2", "Gamma_3", "Gamma_4");
Ellipse e1(_center=Point(0.,0.), _v1=Point(4,0.), _v2=Point(0.,5.), _nnodes=12,
  _domain_name="Omega1", _side_names=sn);
sn[0]="Gamma_5"; sn[1]="Gamma_6"; sn[2]="Gamma_7"; sn[3]="Gamma_8";
Rectangle r1(_xmin=-2., _xmax=2., _ymin=-4., _ymax=4., _nnodes=11, _domain_name="Omega2",
  _side_names=sn);
sn[0]="Gamma_9"; sn[1]="Gamma_10"; sn[2]="Gamma_11"; sn[3]="Gamma_12";
Ellipse e2(_center=Point(1.,2.), _v1=Point(1.5,2.), _v2=Point(1.,3.), _nnodes=12, _side_names=sn);
sn[0]="Gamma_13"; sn[1]="Gamma_14"; sn[2]="Gamma_15"; sn[3]="Gamma_16";
Ellipse e3(_center=Point(0.,0.,0.), _v1=Point(0.5,0.,0.), _v2=Point(0.,1.,0.), _nnodes=12,
  _side_names=sn);
sn[0]="Gamma_17"; sn[1]="Gamma_18"; sn[2]="Gamma_19"; sn[3]="Gamma_20";
Rectangle r2(_xmin=5., _xmax=6., _ymin=0., _ymax=1., _nnodes=6, _domain_name="Omega3",
  _side_names=sn);
sn[0]="Gamma_21"; sn[1]="Gamma_22"; sn[2]="Gamma_23"; sn[3]="Gamma_24";
Disk d1(_center=Point(5.5,0.5,0.), _v1=Point(5.7,0.5,0.), _v2=Point(5.5,0.7,0.), _nnodes=12,
  _side_names=sn);
Mesh mesh2dP1Composite((e1+r1)-(e2+e3)+r2-d1, _triangle, 1, _gmsht);
```




Figure 6.33: GMSH view of complex 2d composite geometry

Let's take an example using segments and circle arcs to define a mesh on a rectangle with rounded corners:

```
Point a(-1.5,-4.); Point b(1.5,-4.); Point c(2.,-3.5); Point d(2.,3.5);
```

```

Point e(1.5,4.); Point f(-1.5,4.); Point g(-2.,3.5); Point h(-2.,-3.5);
Segment s1(_v1=a, _v2=b, _nnodes=21, _domain_name="AB");
CircArc c1(_center=Point(3.5,0.5), _v1=b, _v2=c, _nnodes=5, _domain_name="BC");
Segment s2(_v1=c, _v2=d, _nnodes=11, _domain_name="CD");
CircArc c2(_center=Point(3.5,1.5), _v1=d, _v2=e, _nnodes=5, _domain_name="DE");
Segment s3(_v1=e, _v2=f, _nnodes=21, _domain_name="EF");
CircArc c3(_center=Point(0.5,1.5), _v1=f, _v2=g, _nnodes=5, _domain_name="FG");
Segment s4(_v1=g, _v2=h, _nnodes=11, _domain_name="GH");
CircArc c4(_center=Point(0.5,0.5), _v1=h, _v2=a, _nnodes=5, _domain_name="HA");
Mesh mesh2dP1Loop(planeSurfaceFrom(s1+c1+s2+c2+s3+c3+s4+c4), _triangle, 1, _gmsh);

```




Figure 6.34: GMSH view of rectangular geometry with rounded corners, defined with the `surfaceFrom` routine

You can define composite geometries using loop geometries. Let's take the complex 2d composite example in which we will replace the first rectangle by a rounded rectangle and the disk by a half disk, both defined by the `surfaceFrom` routine:

```

Ellipse e1(_center=Point(0.,0.), _v1=Point(4,0.), _v2=Point(0.,5.), _nnodes=12,
_domain_name="Omega1");
Point a(-1.5,-4.); Point b(1.5,-4.); Point c(2.,-3.5); Point d(2.,3.5);
Point e(1.5,4.); Point f(-1.5,4.); Point g(-2.,3.5); Point h(-2.,-3.5);
Segment s1(_v1=a, _v2=b, _nnodes=21, _domain_name="AB");
CircArc c1(_center=Point(3.5,0.5), _v1=b, _v2=c, _nnodes=5, _domain_name="BC");
Segment s2(_v1=c, _v2=d, _nnodes=11, _domain_name="CD");
CircArc c2(_center=Point(3.5,1.5), _v1=d, _v2=e, _nnodes=5, _domain_name="DE");
Segment s3(_v1=e, _v2=f, _nnodes=21, _domain_name="EF");
CircArc c3(_center=Point(0.5,1.5), _v1=f, _v2=g, _nnodes=5, _domain_name="FG");
Segment s4(_v1=g, _v2=h, _nnodes=11, _domain_name="GH");
CircArc c4(_center=Point(0.5,0.5), _v1=h, _v2=a, _nnodes=5, _domain_name="HA");
Geometry sf1=(surfaceFrom(s1+c1+s2+c2+s3+c3+s4+c4, "Omega2"));
Ellipse e2(_center=Point(1.,2.), _v1=Point(1.5,2.), _v2=Point(1.,3.), _nnodes=12,
_domain_name="Omega3");
Ellipse e3(_center=Point(0.,0.), _v1=Point(0.5,0.), _v2=Point(0.,1.), _nnodes=12,
_domain_name="Omega4");
Rectangle r2(_xmin=5., _xmax=6., _ymin=0., _ymax=1., _nnodes=6, _domain_name="Omega5");
Segment s5(_v1=Point(5.3,0.5), _v2=Point(5.7,0.5), _nnodes=5);
CircArc c5(_center=Point(5.5,0.5), _v1=Point(5.7,0.5), _v2=Point(5.5,0.7), _nnodes=5);
CircArc c6(_center=Point(5.5,0.5), _v1=Point(5.5,0.7), _v2=Point(5.3,0.5), _nnodes=5);
Geometry sf2=planeSurfaceFrom(s5+c5+c6, "Omega6");
Mesh mesh2dP1Composite1((e1+sf1)-(e2+e3)+r2-sf2, _triangle, 1, _gmsh);

```




Figure 6.35: GMSH view of mesh2dP1Composite1

Finally, let's see now an example of complex composite geometry with use of forcing inclusion. Components are defines in example above:

```
Mesh mesh2dP1Composite3(e1+(sf1+(+(e2+e3))+r2+sf2, _triangle, 1, _gmsh);
```




Figure 6.36: GMSH view of mesh2dP1Composite3

Structured mesh with GMSH generator

GMSH allows generating structured and unstructured meshes. Even if XLife++ offers a structured mesh generator, it may be useful to have it with the GMSH generator. To do so, you have an additional argument whose value is `structuredMesh`:

```
Mesh m(Rectangle(_xmin=0., _xmax=2., _ymin=0., _ymax=4., _nnodes=11,  
_side_names=Strings("Gamma_1", "Gamma_2", "Gamma_3", "Gamma_4")), _triangle, 1, _gmsh,  
_structuredMesh);
```

6.5 Open Cascade extension

Open Cascade Technology (OCT)¹ is a third party open source library dedicated to 3D CAD data. It is a powerful library dealing with canonical geometries but providing complex geometrical operations (union, intersection,

¹Trademark @Open Cascade, <https://www.opencascade.com/>

difference of geometries, fillet, chamfer, ...). The standard geometry engine of XLIFE++ provides only union or difference in the case of one geometry included in another one (if detection is easy). So to go further, XLIFE++ provides an interface to OCT. Obviously, OCT must be installed and activated in XLIFE++ (cmake option).



OCT interface is still experimental. Use it with cautious!


When OCT is enabled, it runs only if the user invokes an explicit OCT function. OCT objects (`OCTData` class) are embedded in XLIFE++ geometry objects but are not allocated by default. If an OCT function is invoked, OCT object will be allocated on the fly.

The main interest of OCT interface is to mesh complex object, for instance the intersection of two spheres perforated by a cylinder:

```
Sphere S1(_center=Point(1.,0,0.),_radius=1,_hsteps=0.02,_domain_name="S",_side_names="Sigma");
Sphere S2=translate(S1,1.5,0.,0.); // _side_names "Sigma_2"
RevCylinder C(_center1=Point(1,0.,0),_center2=Point(2.5,0.,0.),_radius=0.3,_hsteps=0.02,
              _domain_name="C",_side_names="Gamma");
Geometry G=(S1^S2)-C; //intersection of spheres minus cylinder
```

At this stage, the geometry G handles only a symbolic description and does not handle any OCT object. It can be not dealt with usual mesh tools of XLIFE++ addressing only the standard gmsh engine. Now invoking the `Mesh` constructor with the mesh generator option `_gmshOC` will produce the creation of OCT objects related to geometries involved (here spheres and cylinder) and an OCT object related to the geometry G that will be exported to GMSH in a particular way.


```
Mesh M(G,_triangle,1,_gmshOC);
```



In this example, the name of domains created by Mesh are quite natural : "Sigma" and "Sigma_2" for the sphere boundaries and "Gamma" for the cylinder boundary. But in some more complex cases, it can be not so intuitive to recover domain names, especially when new faces are created. There is a quite simple way to recover them. Indeed, when meshing with `_gmshOC` generator, 3 files are created in the folder containing the executable file:


- *xlifcpp.brep* containing the *brep* export of the OCT object
- *xlifcpp.geo*, a gmsh script file containing the command to load the *brep* file and some additional commands related to mesh discretization and domain names.
- *xlifcpp.msh*, the mesh file created by GMSH and loaded by XLIFE++ to create the `Mesh` object.

Loading the *xlifepp.geo* in GMSH and configuring it to see curve/surface labels will allow you to identify easier domain names.



The next example shows how powerful is OCT and how XLIFE++ can manage complex geometries:

```
Cone co(_center1=Point(0.,0.,0.),_v1=Point(1.,0.,0.),_v2=Point(0.,1.,0.),_apex=Point(0.,0.,1),
_hsteps=0.3,_side_names="gamma");
Cylinder cy(_center1=Point(0.,0.,0.),_v1=Point(0.7,0.,0.),_v2=Point(0.,0.7,0.),
_center2=Point(0.,0.,7.),_hsteps=1,_side_names="gamma");
Sphere sp(_center=Point(0.,0.,7.),_radius=1.,_hsteps=0.3,_side_names="gamma");
Geometry ant=cy+co+sp;
Real R=30., aR=0.999*R, d=0.2;
Sphere spcor(_center=Point(0.,0.,0.),_radius=R,_hsteps=2,_side_names="sigma");
Geometry cor=toComposite(spcor);
for(number_t i=0;i<8;i++)
for(number_t j=0;j<7;j++)
{
  Real ir = i+d*(2*std::rand() * (1.0 / RAND_MAX)-1),
  jr= j+d*(2*std::rand() * (1.0 / RAND_MAX)-1);
  Real t=pi*(ir/4-1), p=pi_/8*(jr-3);
  Transformation tf = Translation(Point(aR*cos(t)*cos(p),aR*sin(t)*cos(p),aR*sin(p)))
    * Rotation3d(Point(0,0,0),Point(0,0,1),t);
  tf *= Rotation3d(Point(0,0,0),Point(0,1,0),pi_/2-p);
  cor+=transform(ant,tf);
}
Mesh M(cor,_triangle,1,_gmshOC);
```



Available geometrical operations


operation	with OC extension	standard geometry engine
+	merge geometries (fusion)	union of disjoint or included geometries
-	difference of geometries (cut)	make a hole (included geometries)
^	intersection of geometries (common)	not available
%	not managed	force inclusion

Importing brep files

OCT extension provides a new interesting feature : loading a *brep* file in a *Geometry* object and mesh it using the *_gmshOC* generator:

```
Geometry naca( "NACA63-412.brep" );
naca.setOCName(_solid,1,"naca");
naca.setOCName(_face,1,"extrados"); //extrados face
naca.setOCName(_face,2,"intrados"); //intrados face
naca.setOCName(_face,Numbers(3,4),"lateral"); //lateral faces
naca.setOCHstep(Numbers(1,3),0.2);
naca.setOCHstep(Numbers(2,4),0.1);
Mesh(naca,_tetrahedron,1,_gmshOC);
```

In this example, after viewing in GMSH the "NACA63-412.brep" file and identify numbers of elementary objects (solid, face, point), some particular functions (setOCName, setOCHstep, setOCNnode) allow controlling names and mesh size parameters.



6.6 Extrude a mesh

As an alternative to mesh an extruded geometry, it is possible to extrude a 1D or a 2D mesh using the following mesh constructor:

```
Mesh(const Mesh& ms, const Point& O, const Point& D, number_t nbl,
number_t namingDomain=0, number_t namingSection=0, number_t namingSide=0,
const string_t& meshName="");
```

where $\vec{OD}$ defines the direction of extrusion and *nbl* the number of layers of same width (regular extrusion). More precisely, any point *M* of the section mesh is extruded using *nbl* points :

$$M_k = M + O + k * \vec{OD}.$$

When a 1D section, extruded mesh is made with quadrangles. When a 2D triangular mesh section, extruded mesh is made with prisms and when a 2D quadrangular mesh section, extruded mesh is made with hexahedra.

The boundary domains created by the extrusion process come from the boundary domains of the original section. This process is controlled by the 3 parameters `namingDomain`, `namingSection`, `namingSide` taking one of the values 0, 1 or 2, with the following rules:

- 0:** domains are not created
- 1:** one extruded domain is created for any domain of the original section
- 2:** for each layer, one extruded domain is created for any domain of the original section

Be cautious, the side domains of extruded domain are created from the side domains of the given section. Thus, if the given section has no side domains, the extruded domains will have no side domain! The naming convention is the following:

- Domains and side domains keep their name with the extension "_e" or "_e1", "_e2", ..., "_en"
- Section domains have the name of original domains with the extension "_0", ..., "_n"
- When `namingDomain=0`, the full domain is always created and named "Omega".

The following figure illustrates the naming rules of domains.




Figure 6.37: Mesh extrusion, domains naming

For instance, to mesh a tubular domain using the mesh extrusion of a crown:

```
Disk dext(_center=Point(0.,0.), _radius=1.,_nnodes=20, _domain_name="Omega",
         _side_names="Sigma");
Disk dint(_center=Point(0.,0.), _radius=0.5,_nnodes=10,_side_names="Gamma");
Mesh crown(dext-dint,_triangle,1,_gmsh);
Mesh tube(crown,Point(0,0,0),Point(0,0,1),10,1,1,1);
```




Figure 6.38: Tube prismatic mesh from extrusion of a crown mesh

6.7 Split mesh element

Sometimes it may be useful to split elements into elements of another type, for instance to produce mesh of pyramids that are not provided by standard meshing software programs. To do this, a general constructor is offered:

```
Mesh(const Mesh& mesh, ShapeType sh, const string_t name="");
```

where `sh` is the desired shape type.

Up to now, only one splitting process is available: hexahedron of order 1 into six pyramids of order 1:

```
Mesh meshQ1(Cuboid(_xmin=0, _xmax=1, _ymin=1, _ymax=3, _zmin=1, _zmax=5,
    _nnodes=Numbers(3, 5, 9), _side_names=sidenames), _hexahedron, 1,
    _structured, "Q1 mesh of [0,1]x[1,3]x[1,5]");
Mesh meshPyramid(meshQ1, _pyramid, "Py1 mesh of [0,1]x[1,3]x[1,5]");
```

The `Mesh` object passed to the splitting constructor may be any hexahedral mesh. Note that a hexahedron is split into the six pyramids based on the hexahedron faces and the centroid of the hexahedron as tip.

6.8 Loading a mesh from a file

XLIFE++ allows you to read various mesh file formats. The constructor to use is defined as follows:

```
/// constructor from a file
Mesh(const String& filename, const String& meshname, IOFormat mft, Number nodesDim);
```

The arguments are:

`filename` is the name of the mesh file,

`meshname` is the name of the mesh, for log purpose, Default value is empty string.

`mft` defines the mesh format. It can take four values as we can see on the examples hereafter.

`nodesDim` defines minimal number of coordinates of each vertex. Default is 0 for automatic behavior. Normally, you should not have to use this argument.

```

// loading a VTK mesh file
Mesh m1("mesh.vtk", "My Mesh M1", vtk);
// loading a VTU mesh file
Mesh m2("mesh.vtu", "My Mesh M2", vtu);
// loading a GMSH mesh file
Mesh m3("mesh.msh", "My Mesh M3", msh);
// loading a GMSH script file
Mesh m4("mesh.geo", "My Mesh M4", geo);
// loading a MELINA mesh file
Mesh m5("mesh.mel", "My Mesh M5", mel);
// loading a PLY mesh file
Mesh m6("mesh.ply", "My Mesh M6", ply);

```

which create six `Mesh` objects called `m1`, `m2`, `m3`, `m4`, `m5` and `m6`.

- To have more information about the VTK and VTU file formats, please go to <http://www.paraview.org>
- The MELINA file format is the input format of the MELINA finite element library, ancestor of XLIFE++. For more information, please go to <http://anum-maths.univ-rennes1.fr/melina/danielmartin/melina/>
- To have more information on the PLY file format, please go to <http://paulbourke.net/dataformats/ply>.
- To have more information about GMSH, please go to <http://geuz.org/gmsh/>. You will have everything you need about the msh format and about the geo scripts.



If you load a geo file, XLIFE++ will call GMSH to create the corresponding msh file, which is then read. Consequently, GMSH needs to be installed on your computer and the executable file, called `gmsh`, should be found through your PATH environment variable. If GMSH is installed after XLIFE++, XLIFE++ needs to be reinstalled.

6.9 Transformations on meshes

Geometrical transformations on meshes work as on geometries. Please see section 6.2 for definition and use of transformations routines.

Then, if you want to apply a transformation and modify the input object, you can use one of the following functions:

```

/// apply a geometrical transformation on a Mesh
Mesh& Mesh::transform(const Transformation& t);
/// apply a translation on a Mesh
Mesh& Mesh::translate(std::vector<Real> u = std::vector<Real>(3,0.));
Mesh& Mesh::translate(Real ux, Real uy = 0., Real uz = 0.);
/// apply a rotation 2d on a Mesh
Mesh& Mesh::rotate2d(const Point& c = Point(0.,0.), Real angle = 0.);
/// apply a rotation 3d on a Mesh
Mesh& Mesh::rotate3d(const Point& c = Point(0.,0.,0.), std::vector<Real> u =
    std::vector<Real>(3,0.), Real angle = 0.);
Mesh& Mesh::rotate3d(Real ux, Real uy, Real angle);
Mesh& Mesh::rotate3d(Real ux, Real uy, Real uz, Real angle);
Mesh& Mesh::rotate3d(const Point& c, Real ux, Real uy, Real angle);
Mesh& Mesh::rotate3d(const Point& c, Real ux, Real uy, Real uz, Real angle);
/// apply a homothety on a Mesh
Mesh& Mesh::homothetize(const Point& c = Point(0.,0.,0.), Real factor = 1.);
Mesh& Mesh::homothetize(Real factor);

```

```

/// apply a point reflection on a Mesh
Mesh& Mesh::pointReflect(const Point& c = Point(0.,0.,0.));
/// apply a reflection2d on a Mesh
Mesh& Mesh::reflect2d(const Point& c = Point(0.,0.), std::vector<Real> u =
    std::vector<Real>(2,0.));
Mesh& Mesh::reflect2d(const Point& c, Real ux, Real uy = 0.);
/// apply a reflection3d on a Mesh
Mesh& Mesh::reflect3d(const Point& c = Point(0.,0.,0.), std::vector<Real> u =
    std::vector<Real>(3,0.));
Mesh& Mesh::reflect3d(const Point& c, Real ux, Real uy, Real uz = 0.);

```

For instance:

```

Mesh m;
m.translate(0.,0.,1.);

```

However, if you want now to create a new **Mesh** by applying a transformation on a **Mesh**, you should use one of the following functions instead:

```

/// apply a geometrical transformation on a Mesh (external)
Mesh transform(const Mesh& m, const Transformation& t);
/// apply a translation on a Mesh (external)
Mesh translate(const Mesh& m, std::vector<Real> u = std::vector<Real>(3,0.));
Mesh translate(const Mesh& m, Real ux, Real uy = 0., Real uz = 0.);
/// apply a rotation 2d on a Mesh (external)
Mesh rotate2d(const Mesh& m, const Point& c = Point(0.,0.), Real angle = 0.);
/// apply a rotation 3d on a Mesh (external)
Mesh rotate3d(const Mesh& m, const Point& c = Point(0.,0.,0.), std::vector<Real> u =
    std::vector<Real>(3,0.), Real angle = 0.);
Mesh rotate3d(const Mesh& m, Real ux, Real uy, Real angle);
Mesh rotate3d(const Mesh& m, Real ux, Real uy, Real uz, Real angle);
Mesh rotate3d(const Mesh& m, const Point& c, Real ux, Real uy, Real angle);
Mesh rotate3d(const Mesh& m, const Point& c, Real ux, Real uy, Real uz, Real angle);
/// apply a homothety on a Mesh (external)
Mesh homothetize(const Mesh& m, const Point& c = Point(0.,0.,0.), Real factor = 1.);
Mesh homothetize(const Mesh& m, Real factor);
/// apply a point reflection on a Mesh (external)
Mesh pointReflect(const Mesh& m, const Point& c = Point(0.,0.,0.));
/// apply a reflection2d on a Mesh (external)
Mesh reflect2d(const Mesh& m, const Point& c = Point(0.,0.), std::vector<Real> u =
    std::vector<Real>(2,0.));
Mesh reflect2d(const Mesh& m, const Point& c, Real ux, Real uy = 0.);
/// apply a reflection3d on a Mesh (external)
Mesh reflect3d(const Mesh& m, const Point& c = Point(0.,0.,0.), std::vector<Real> u =
    std::vector<Real>(3,0.));
Mesh reflect3d(const Mesh& m, const Point& c, Real ux, Real uy, Real uz = 0.);

```

For instance:

```

Mesh m1;
Mesh m2=translate(m1, 0.,0.,1.);

```

Applying a transformation on a **Mesh** object means applying the transformation on the underlying **Geometry** object and adding the suffix "_prime" to the mesh name and the domain names.

6.10 Using geometrical domain

Related to mesh, the geometric domains are fundamental objects because they are the support of integrals or boundary conditions involved in variational problem. These domains are defined by mesh tools, using names and sidenames in definition of geometries or given as physical domain in 'geo' file.

6.10.1 Retrieving domains

In order to be used in program, the domains have to be 'retrieved' as `Domain` object from mesh:

```
Strings sn("y=0", "y=1", "x=0", "x=1");
Mesh mesh2d(SquareGeo(_origin=Point(0.,0.), _length=1, _nnodes=20,
    _side_names=sn), _triangle, 1, _structured);
Domain omega=mesh2d.domain("Omega");
Domain sigmaM=mesh2d.domain("x=0");
Domain sigmaP=mesh2d.domain("x=1");
Domain gammaM=mesh2d.domain("y=0");
Domain gammaP=mesh2d.domain("y=1");
```

By default, "Omega" is the string name of the main domain of mesh.

It is possible to rename a domain of a mesh:

```
Strings sn("", "", "x=0", "x=1/2-");
Mesh mesh2d(Rectangle(_origin=Point(0.,0.), _xlength=0.5, _ylength=1, _nnodes=Numbers(20,40),
    _side_names=sn), _triangle, 1, _structured);
mesh2d.renameDomain("Omega", "Omega-");
sn[2] = "x=1/2+"; sn[3] = "x=1";
Mesh mesh2d_p(Rectangle(_origin=Point(0.5,0.), _xlength=0.5, _ylength=1, _nnodes=Numbers(20,40),
    _side_names=sn), _triangle, 1, _structured);
mesh2d_p.renameDomain("Omega", "Omega+");
mesh2d.merge(mesh2d_p);
Domain omegaM=mesh2d.domain("Omega-");
Domain omegaP=mesh2d.domain("Omega+");
Domain sigmaM=mesh2d.domain("x=0");
Domain sigmaP=mesh2d.domain("x=1");
Domain gamma=mesh2d.domain("x=1/2- or x=1/2+");
```


In this example, the unit square is split in two domains Ω^+ and Ω^- using the `merge` and `renameDomain` functions. Note that the merging process of meshes concatenates 'same' domain in a new one named "name1 or name2".

6.10.2 Dealing with normals of a domain

Normal vectors may be required in many variational forms, in particular when using BEM like methods. In (bi)linear forms, they appear with symbolic names `_n`, `_nx`, `_ny` that corresponds to real normal vectors. The question is which normal vectors are selected by XLiFE++.

Note that the normal vectors of a domain, say Γ , are computed only if the domain is a manifold, say a surface/curve domain in a 3d/2d space. If they are required, they are automatically computed with the following default rules:

- if Σ is a boundary (or a part of) of a unique domain Ω , the selected normals are the outwards vectors to Ω
- if Σ is a boundary between two domains (an interface), the selected normals are the towards infinite vectors
- if Σ is not a boundary, say an immersed manifold, the selected normals are the towards infinite vectors



When the boundary or the manifold is not closed, the normal orientations are consistent, but the selected orientation is not predictable.

The user can modify the normal orientation by using the member function of `Domain` class:

`setNormalOrientation(OrientationType[, Domain])` where `OrientationType` has one of the following values (default is `_undefOrientationType`):

```
_towardsInfinite , _outwardsInfinite    // for any side domain
_towardsDomain , _outwardsDomain        // for any boundary or interface
```

To change the normal orientation of a side domain `Sigma`, write for instance

```
Sigma.setNormalOrientation(_towardsInfinite); //towards infinite normals
Sigma.setNormalOrientation(_outwardsDomain);  //outwards normals,
//UNSAFE for an interface!
Sigma.setNormalOrientation(_outwardsDomain, Omega); //outwards normals to Omega
```

All normal vectors of an open manifold are oriented consistently, but the global orientation is unpredictable because it depends on the first node encountered. Check the orientation by visualizing the normal vectors (see below). The global orientation may be controlled by using a virtual "interior" point that orients the normal vector related to this interior point:

```
Sigma.setNormalOrientation(_towardsInfinite , Point(0,0));
```

This trick allows dealing with simple open manifolds, but for complex geometries (union of open manifolds for instance) the global orientation of normal vector remains uncontrollable.

For visualization purpose, the normal vectors can be exported to a vtk file using:

```
Sigma.saveNormalsToFile("n_Sigma", _vtk);
```

They can be also collected in a `TermVector` object:

```
Space V1(Omega, P1, "V1"); Unknown u1(V1, "u1", 3);
TermVector Ns = normalsOn(Sigma, u1);
```

The normals are computed by L2 projection on the space W related to the `Unknown` used. More precisely, the normals n in space W are got by solving the problem:

$$\int_{\Sigma} n|t = \int_{\Sigma} n_0|t \quad \forall t \in W$$

where n_0 is the normal to the element faces. If (w_j) denotes the basis of W and N the vector representing the normal in W basis ($n = \sum_j n_j w_j$), the following linear system is solved:

$$\mathbb{A}N = B, \quad \text{with } \mathbb{A} = \int_{\Sigma} w_i |w_j| \text{ and } B_i = \int_{\Sigma} n_0 |w_i|$$

The unknown may be an explicit vector unknown or a scalar unknown if the space is a space of vectors. In the case of a P0 unknown, the normals are normals on element faces with no projection. In the case of Pk Lagrange unknown, the normals are some interpolated normals on Lagrange DoFs.

6.10.3 Map of domains

Some processes require a geometric map between two domains. For instance, to deal with periodic condition related to two side domains:

$$u|_{\Sigma^+} = u|_{\Sigma^-}$$


The elimination process uses the geometric map $F: \Sigma^+ \rightarrow \Sigma^-$. The simple way to define such map is the following:

```
Reals mapPM(const Point& P, Parameters& pa = defaultParameters)
{
    Point Q(P);
    Q(1) -= 1;
    return Q;
}
\dots
defineMap(sigmaP, sigmaM, mapPM);
```

Note that the mapPm function returns a Vector<Real> which is more general than a Point. Respect this prototype !



When dealing with curved domains, generally meshed with P1,P2, ... elements, you can use some natural maps from one domain to the other (think about the scaling transformation of a circle to another circle whereas the circles are approximated by polygons). In that case, points are transported using the given geometrical transformation and an additional projection to guarantee that the image points belong to the arrival domain. Obviously, the projection induces an error related to the mesh size.



It is currently not possible to define two different maps for a pair of domains.

6.10.4 Assign properties to domains

In some problems, physical properties may be different from a domain to other one. This may be managed by differentiating integrals in variational formulation:

$$\int_{\Omega_1} \rho_1(x) u(x) v(x) + \int_{\Omega_2} \rho_2(x) u(x) v(x).$$

But it may be too intricate if there are a lot of domains or integrals. So there is an alternative method consisting in defining a unique function ρ and deal with a unique integral:

$$\int_{\Omega} \rho(x) u(x) v(x)$$

and assign id to domains that are subdomains:

```
Real rho(const Point&P, Parameters& pars=defaultParameters)
{
  Number mat=materialIdFromParameters(pars);
  if(mat==1) return \ldots
  else return \ldots
}
\ldots
Domain omega=mesh2d.domain("omega"); //whole domain
Domain omega1=mesh2d.domain("omega_1"); //subdomain
Domain omega2=mesh2d.domain("omega_2"); //subdomain
omega1.setMaterialId(1);
omega2.setMaterialId(2);
```

6.10.5 Create domain of sides

It may be useful to get the domain of all sides (points, edges, faces) of an existing domain. For instance the set of all faces of a volumic domain, the set of all edges of a surfacic domain. The sides(Domain) function or the Domain::sidesDomain() member function do the job:

```
Mesh msq(SquareGeo(_origin=Point(0.,0.),_length=1.,_nnodes=2,_domain_name="sq",_side_names="bsq"),
         _triangle,1,_structured);
Domain sq=msq.domain("sq"), bsq=msq.domain("bsq");
Domain ssq=sq.sidesDomain(); // edges of square domain
Domain ssq2 = sides(sq); // alternate call
Domain sbsq=bsq.sidesDomain(); // edges of square boundary domain

Mesh mcu(Cube(_origin=Point(0.,0.,0.),_length=1.,_nnodes=2,_domain_name="cu"),
         _hexahedron,1,_structured);
Domain cu=mcu.domain("cu");
Domain scu=cu.sidesDomain(); // faces of cube domain

Mesh msp(Sphere(_center=Point(0.,0.,0.),_radius=1.,_nnodes=2,_domain_name="sph"),
         _triangle,1,_gmsh);
Domain sph=msp.domain("sph");
Domain ssph=sph.sidesDomain(); // edges of sphere domain
```

Note that by applying sidesDomain() on a side domain, you get the sides of sides:

```
Mesh mcu(Cube(_origin=Point(0.,0.,0.),_length=1.,_nnodes=2,_domain_name="cu"),
         _hexahedron,1,_structured);
Domain cu=mcu.domain("cu");
Domain scu=cu.sidesDomain(); // faces of cube domain
Domain sscu=scu.sidesDomain(); // edges of cube domain
```

By default, the name of domain is "sides of *domain.name*", by specifying a string as argument of `sidesDomain()` you can change it.



By using the `internalSides(Domain)` function or the `Domain::internalSidesDomain()` member function, it is also possible to get the domain of internal sides, i.e. the union of all sides excluding the sides located on the boundary (in other words the union of shared sides).

6.10.6 Set operation on domain

There exists two set operations : the union of domains (merge function and + operator) and the difference of two domains (- operator). The merge function accepts up to 6 domains. When there are more than 2 domains to merge, it is more efficient to use the merge function than to use the + operator. The following example illustrates the use of set operations on domains:

```
Rectangle R(_origin=Point(0.,0.), _xlength=1., _ylength=1., _nnodes=31, _domain_name="Omega",
            _side_names={"Gamma1", "Gamma2", "Gamma3", "Gamma4"});
Domain omega=mR.domain("Omega"), gamma1=mR.domain("Gamma1"), gamma2=mR.domain("Gamma2"),
gamma3=mR.domain("Gamma3"), gamma4=mR.domain("Gamma4");
Domain gamma12 = merge(gamma1,gamma2); // union of elements of gamma1 and gamma2
Domain gamma34 = gamma3 + gamma4; // union of elements of gamma3 and gamma4
Domain gamma = merge(gamma1,gamma2,gamma3,gamma4,"gamma"); // union of elements of gamma1, gamma2, gamma3 and gamma4
Domain sigma = sides(omega); // set of all sides of elements of omega
Domain sigma0 = sigma - gamma; // set of all internal sides of elements of omega
Domain d = sigma + omega; // ERROR : elements have not the same dimension
```

6.10.7 Cracking a domain

There exist two ways in XLife++ to crack a domain. The first one consists in using the GMSH capabilities and the other one consists in using the intern cracking tool that it is attached to the `Mesh` class.

Cracking a domain using GMSH capabilities


Theoretically, GMSH allows you to crack domains (1D cracks in 2D meshes, 1D or 2D cracks in 3D meshes). Cracks can be opened or not. A crack is opened when some boundary nodes of the domain to crack are duplicated as the other nodes, else it will be a closed crack.

To notify that the segment has to be cracked, you just call the `crack` routine on it. This is a general routine defining both opened and closed cracks through 2 additional optional arguments. Default behavior is closed cracks. You can call the routine `closedCrack` (only the geometry in argument) to define a closed crack. You can call the routine `openCrack` (the geometry and a domain name) to define an opened crack. In this case, the domain name is the boundary domain of the geometry you want to crack that will be opened. Let's see following examples to understand this.

There are two ways to define a geometry with a crack inside it: the direct one and the indirect one.

Defining cracks directly

This way is the way you should always do to define a crack. A crack is a geometry inside a geometry of bigger dimension. So the geometry to be cracked must be defined as a meshed "hole" inside the container geometry.



```


Point x1(0,0,0), x2(1,0,0), x3(1,1,0), x4(0,1,0), x5(0.2,0.2,0),
        x6(0.8,0.8,0), x7(0.2,0,0), x8(0.8,1,0);
Rectangle rrect8(_v1=x1, _v2=x2, _v4=x4, _domain_name="Omega",
                 _side_names="Gamma");
Segment scrack(_v1=x5, _v2=x6, _nnodes=3, _domain_name="Crack",
                _side_names="Sigma");
openCrack(scrack, "Sigma");
Mesh m(rrect8+scrack, _triangle, 1, _gmsh);

```

Here, it is an opened crack. A side name is given to both ends of the segment. This name will be given to the routine `openCrack` to tell which ends are to be opened. Here, it is both.

Defining cracks indirectly

This way is called indirect, compared to the previous one, insofar as you have to link the geometry you want to crack to the boundaries of the parent geometry and define surfaces from their boundaries:



```

Point x1(0,0,0), x2(1,0,0), x3(1,1,0), x4(0,1,0), x5(0.2,0.2,0),
        x6(0.8,0.8,0), x7(0.2,0,0), x8(0.8,1,0);
Segment s1(_v1=x1, _v2=x7, _domain_name="Gamma");
Segment s2(_v1=x2, _v2=x7, _domain_name="Gamma");
Segment s3(_v1=x3, _v2=x2, _domain_name="Gamma");
Segment s4(_v1=x8, _v2=x3, _domain_name="Gamma");
Segment s5(_v1=x8, _v2=x4, _domain_name="Gamma");
Segment s6(_v1=x4, _v2=x1, _domain_name="Gamma");
Segment s7(_v1=x7, _v2=x5);
Segment s8(_v1=x5, _v2=x6, _nnodes=3, _domain_name="Crack");
Segment s9(_v1=x6, _v2=x8);
crack(s8);
Geometry sf1=surfaceFrom(s7+s8+s9+s5+s6+s1, "Omegal");
Geometry sf2=surfaceFrom(s7+s8+s9+s4+s3+s2, "Omega2");
Mesh m(sf1+sf2, _triangle, 1, _gmsh);

```

Here, it is a closed crack.



In this example, surfaces have different domain names. You can also give the same domain name

Which way is better ?

	direct way	indirect way
1D crack in 2D mesh	100% safe	100% safe
2D crack in 3D mesh	not 100% safe	100% safe
1D crack in 3D mesh	to be tested	to be tested



GMSH team is currently working on improving their crack engine to be 100% whatever the case.

A look at the mesh file

Let's see the resulting mesh file for the indirect example above:

```
$MeshFormat
2.2 0 8
$EndMeshFormat
$PhysicalNames
4
1 1 "Crack"
1 2 "Gamma"
2 3 "Omega1"
2 4 "Omega2"
$EndPhysicalNames
$Nodes
18
1 0.2 0.2 0
2 0.8 0.8 0
3 0.49999999999991927 0.49999999999991927 0
4 0.8 1 0
5 0 1 0
6 0 0 0
7 0.2 0 0
8 1 1 0
9 1 0 0
10 0.49999999999991927 0.49999999999991927 0
11 0.40000000000000001 0.8999999999999999 0
12 0.099999999999935429 0.59999999999998384 0
13 0.6188775510203053 0.8489795918366316 0
14 0.1178571428570276 0.1714285714285426 0
15 0.59999999999991926 0.1 0
16 0.89999999999993543 0.39999999999998387 0
17 0.3811224489791758 0.1510204081631623 0
18 0.8821428571427419 0.8285714285713998 0
$EndNodes
```

Bounds of the cracked domain are not duplicated (nodes 1 and 2), whereas the middle node of the cracked domain is duplicated (nodes 3 and 10):

```
$Elements
36
1 1 2 1 2 1 3
2 1 2 1 2 3 2
3 1 2 2 4 4 5
4 1 2 2 5 5 6
5 1 2 2 6 6 7
6 1 2 2 8 4 8
7 1 2 2 9 8 9
8 1 2 2 10 9 7
9 1 2 1 11 1 10
10 1 2 1 11 10 2
11 2 2 3 7 2 13 3
12 2 2 3 7 1 3 12
13 2 2 3 7 3 11 12
14 2 2 3 7 3 13 11
15 2 2 3 7 2 4 13
16 2 2 3 7 7 1 14
17 2 2 3 7 7 14 6
18 2 2 3 7 5 12 11
19 2 2 3 7 1 12 14
20 2 2 3 7 4 5 11
21 2 2 3 7 4 11 13
22 2 2 3 7 5 6 12
```

```

23 2 2 3 7 6 14 12
24 2 2 4 11 1 10 17
25 2 2 4 11 2 16 10
26 2 2 4 11 10 16 15
27 2 2 4 11 10 15 17
28 2 2 4 11 7 1 17
29 2 2 4 11 2 4 18
30 2 2 4 11 4 8 18
31 2 2 4 11 9 15 16
32 2 2 4 11 7 15 9
33 2 2 4 11 7 17 15
34 2 2 4 11 2 18 16
35 2 2 4 11 8 9 16
36 2 2 4 11 8 16 18
$EndElements

```

Segments are also duplicated. If you're familiar with the msh file format, by reading elements 11 and 24 for instance, we can deduce that domain "Omega1" has geometrical reference 7 and domain "Omega2" has geometrical reference 11. These references will be used with the cracked domain name to name sides of the crack, namely "Crack_7" and "Crack_11".

Cracking a domain using intern tool

The way to crack a domain is very similar to the previous one, except the crack function acts on a mesh and a side domain and not on the geometry:

```

Point x1(0,0,0), x2(1,0,0), x3(1,1,0), x4(0,1,0), x5(0.2,0.2,0),
        x6(0.8,0.8,0), x7(0.2,0,0), x8(0.8,1,0);
Rectangle r(_v1=x1, _v2=x2, _v4=x4, _domain_name="Omega", _side_names="Gamma");
Segment s(_v1=x5, _v2=x6, _nnodes=3, _domain_name="Sigma");
Mesh m(r+s, _triangle, 1, _gmsh); //mesh as usual
Domain sigma=m.domain("Sigma"); //get the crack domain
m.crack(sigma); //mesh is now cracked

```

By default, the crack is not open (end points are not duplicated). By specifying `_openCrack` when calling the crack function, the crack will be open (end points are duplicated):

```

m.crack(sigma, _openCrack);

```

Once the mesh is cracked, the sides of the crack are named `xxx+` and `xxx-` where `xxx` is the name of the original domain supporting the crack. It is possible to crack a domain with few segments, naming the segments with the same name. Even, one can crack a closed domain (for instance a polygon).

This tool is working in 2D and 3D, but fails when trying to crack a domain with a triple point (for instance an Y shape crack).

6.10.8 Having statistics about the mesh quality of a domain

You may want to know statistics about the mesh you use : the minimum, maximum and average value of :

- measure and size of elements
- measure of side of elements

To have these statistics, you have to call `computeStatistics` on each domain you want information :

```

Domain omega=\ldots
omega.computeStatistics();
theCout << omega << endl;

```

`computeStatistics` have an optional boolean argument, whose default value is false, meaning deactivation of the computation of side statistics.

6.10.9 Summary of domain operations

We only list here the stuff interesting users:

Properties		
<code>dom.numberOfElements()</code>	→ Number	number of elements in domain
<code>dom.setNormalOrientation()</code>	→ void	set normal orientation of a side domain
<code>dom.parametrization()</code>	→ Parametrization	access to parametrization if defined
<code>dom.setMaterialId(id)</code>	→ void	associates a material id
<code>dom.setDomainId(id)</code>	→ void	associates a domain id
<code>dom.measure()</code>	→ Real	measure of domain
<code>defineMap(dom1,dom2,m)</code>	→ void	relates dom1 and dom2 with a map
Domain building		
<code>sides(dom)</code>	→ Domain	domain of sides of elements of dom
<code>internalSides(dom)</code>	→ Domain	domain of internal sides of elements of dom
<code>crack(dom1,dom2)</code>	→ Domain	crack domain from both sides of the crack
<code>dom.extendDomain()</code>	→ Domain	extension domain of a side domain
<code>dom.fictitiousDomain()</code>	→ Domain	fictitious domain of a side domain
<code>merge(dom1,dom2, \ldots)</code>	→ Domain	union of n domains with same element dimension
<code>dom1 + dom2</code>	→ Domain	union of 2 domains with same element dimension
<code>dom1 - dom2</code>	→ Domain	difference of 2 domains

6.11 Dealing with parametrizations of geometrical domains

XLIFE++ may associate a `Parametrization` object to each `Geometry` object. It is accessible using the member function `Geometry::parametrization()` :

```
Disk di(_center=Point(0.,0.,0.),_radius=1.,_nnodes=20);
const Parametrization& par=di.parametrization();
const Parametrization& par=di.boundaryParametrization();
```

Parametrization exists for any canonical geometry and also for composite geometry, but in that case it is a `PiecewiseParametrization` object (inheriting from `Parametrization`). It is also possible to access to the parametrization of the boundary. `Parametrization` class offers access to some useful geometrical properties (derivatives, jacobian, curvilinear abscissa curvatures, normal and tangent vectors, ...); see `Parametrization` documentation. `Parametrization` objects are attached to the geometry of a `GeomDomain` object, but they can be accessed straightforward using the same functions:

```
Disk di(_center=Point(0.,0.,0.),_radius=1.,_nnodes=20,domain_name="Omega");
Mesh m(di,_triangle,1,_gmsh);
Domain omega=m.domain("Omega");
const Parametrization& par=omega.parametrization();
const Parametrization& par=omega.boundaryParametrization();
```



Parametrizations are not yet available for geometries coming from OpenCascade.

6.12 A full example with periodic cavities

You want to mesh a rectangular domain, but on the bottom side of the rectangle, you want to have periodic cavities with the following pattern:





Figure 6.39: Definition of the cavity

First, you have to define the first cavity, according to the previous figure:

```
// Definition of the cavity
Real l1=0.06, l2=0.04, l3=0.08, h1=0.05, h2=0.1, s=0.01;
Point po(1.,0.);
Point pa=po+Point(l1,0.);
Point pb=pa+Point(0.,h1);
Point pc=pb+Point(-l2,0.);
Point pd=pc+Point(0.,h2);
Point pe=pd+Point(2.*l2+l3,0.);
Point pf=pe+Point(0.,-h2);
Point pg=pf+Point(-l2,0.);
Point ph=pg+Point(0.,-h1);
Point pi=ph+Point(l1,0.);

Segment s1(_v1=po, _v2=pa, _hsteps=s), s2(_v1=pa, _v2=pb, _hsteps=s),
s3(_v1=pb, _v2=pc, _hsteps=s), s4(_v1=pc, _v2=pd, _hsteps=s),
s5(_v1=pd, _v2=pe, _hsteps=s), s6(_v1=pe, _v2=pf, _hsteps=s),
s7(_v1=pf, _v2=pg, _hsteps=s), s8(_v1=pg, _v2=ph, _hsteps=s),
s9(_v1=ph, _v2=pi, _hsteps=s);

Geometry cavity=s1+s2+s3+s4+s5+s6+s7+s8+s9;
```

When done, you can define the other cavities as results of translations of the first cavity:

```
// Definition of the cavities
```

```

Real cL=2.*l1+l3; // cavity length
Number nbcav=10; // number of cavities
Geometry cavities=cavity;
for (Number n=1;n<nbcav; n++) { cavities+=translate(cavity,n*cL,0.); }

```

Finally, we define borders of the main domain, and mesh the resulting **Geometry** defined with **surfaceFrom**:

```

// full geometry
Real sb=0.05;
Point p1(0.,0.), p2(2.+nbcav*cL,0.), p3(2.+nbcav*cL,1.), p4(0.,1.);
Segment s0(_v1=p1, _v2=p2, _hsteps=Reals(sb,s)),
          s10(_v1=Point(1.+nbcav*cL,0.), _v2=p2, _hsteps=Reals(s,sb)),
          s11(_v1=p2, _v2=p3, _hsteps=sb, _domain_name="SigmaP"),
          s12(_v1=p3, _v2=p4, _hsteps=sb),
          s13(_v1=p4, _v2=p1, _hsteps=sb, _domain_name="SigmaM");

Geometry borders=s0+cavities+s10+s11+s12+s13;

//create mesh
Mesh mesh2d(surfaceFrom(borders,"Omega"), triangle, 1, _gmsh);
Domain omega=mesh2d.domain("Omega");
Domain sigmaP=mesh2d.domain("SigmaP");
Domain sigmaM=mesh2d.domain("SigmaM");

```

7.1 Domains, spaces, unknowns and test functions

XLiFE++ allows you to solve PDE with the finite elements method, and the spectral elements method. Both methods approximate all functions w as follows :

Given a basis of n functions $\varphi_i(x, y, z)$ and $w_i = (w, \varphi_i)$, then $w(x, y, z) \approx \sum_{i=0}^n w_i \varphi_i(x, y, z)$.

The basis functions define the so-called *approximation space* :

$$V_h = \left\{ w, \text{ such as } w = \sum_{i=0}^n w_i \varphi_i(x, y, z) \right\}.$$

We will now see how to define spaces, dealing with finite element spaces and spectral spaces. XLiFE++ is built so that just one object is concerned. **Note that XLiFE++ does not declare essential conditions in space whereas mathematics requires it!**

7.1.1 Domains and finite element spaces

With the finite element method, the basis function φ_i is constructed from the elements having i as a degree of freedom (DoF). It is a *shape function*.

What do we need to define a finite element space ?

- A geometrical definition of the domain where the problem is to be solved;
- A finite element interpolation, such as $P_k, k \in \mathbb{N}$ for instance.

The geometrical definition of the domain consists in a mesh, which is a set of geometrical elements (such as triangles, hexahedra, prisms, ...) whose union describes the domain. Inside the program, this description is handled through an object of type `Mesh`. The definition of such an object is the very first step of the resolution process to the problem.

The different ways XLiFE++ provides to define a `Mesh` are detailed in chapter 6. In order to prepare the second step, namely the construction of the finite element space, we have to declare variables to handle the main domain and eventually the subdomains needed by the problem. This can be seen as an extraction from the mesh of the right information. This is done by means of strings which are the names of the subdomains. Consequently, the user has to know in advance the names of the subdomains.

When the mesh comes from a file, the names of the domains are generally written inside the file. In the case of a GMSH mesh file, a default name is automatically generated by XLiFE++ for each domain whose name is not specified in the file.

When the mesh is built by an internal meshing tool provided by XLiFE++, the name of the main domain is always "Omega". Moreover, if the mesh is built by a structured generator, the boundary names have to be given by the user, in a specific order defined in the documentation of the constructor. But if the mesh is built by a subdivision generator, the names of the subdomains are also automatically generated. So, in any case, the best way for the user to make sure he uses the right names is to run the short following program, which is in fact the minimum mandatory program for XLiFE++ usage:

```
#include "xlife++.h"
using namespace xlifepp;

int main() {

    init(); // initialization

    Number order=1;
    Mesh m(Ball(), _tetrahedron, order, _subdiv, "test"); // for example

    m.printInfo(); // prints mesh information on the terminal
}
```

The output is:

```
Mesh'test' (Ball - Tetrahedron mesh over 8 octants)
space dimension : 3, element dimension : 3
Geometry ball (center = (0,0,0), radius = 1) of shape type ball of dimension 3, BoundingBox
[-1,1]x[-1,1]x[-1,1],
MinimalBox [(-1, -1, -1), (1, -1, -1), (-1, 1, -1), (-1, -1, 1)], names of variable : x, y, z
number of elements : 8, number of vertices : 7, number of nodes : 7, number of domains : 5
domain number 0: Omega (Interior of the domain)
domain number 1: Sigma_1 (Boundary: The sphere centered at vertex 4)
domain number 2: Sigma_2 (Interface: YZ plane)
domain number 3: Sigma_3 (Interface: XZ plane)
domain number 4: Sigma_4 (Interface: XY plane)
```

Now, we can declare the handle variables that will be used just afterwards:

```
Domain omega = m.domain("Omega");
Domain gamma = m.domain("Sigma_1");
```

The definition of a finite element space is done with a key-value system:

key(s)	authorized types / possible values	examples
_domain	Domain	_domain =omega
_FE_type	Lagrange, Hermite, CrouzeixRaviart, Nedelec, NedelecFace, NedelecEdge or Morley	_FE_type =Lagrange, _FE_type =Nedelec, ...
_FE_subtype	standard, GaussLobattoPoints, firstFamily or secondFamily	_FE_subtype =standard, _FE_subtype =firstFamily, ...
_Sobolev_type	L2, H1, Hdiv, Hcurl, Hrot, H2, Hinf or Linf	_Sobolev_type =L2, _Sobolev_type =H1, ...
_order	single unsigned integer	_order =5
_interpolation	P0 to P10, P1BubbleP3, Q0 to Q10, RT_1 to RT_5, NF1_1 to NF1_5, BDM_1 to BDM_5, NF2_1 to NF2_5, N1_1 to N1_5, N2_1 to N2_5	_interpolation =P3, _interpolation =NE1_2, ...
_name	String	_name ="Vh"
_optimizeNumbering, _notOptimizeNumbering	no value	
_withLocateData, _withoutLocateData	no value	

The key **_interpolation** is a shortcut to the set of keys **_FE_type**, **_FE_subtype**, **_Sobolev_type**, **_order**. For instance **_interpolation**=NE1_2 is equivalent to **_FE_type**=Nedelec, **_FE_subtype**=firstFamily, **_order**=2, **_Sobolev_type**=Hcurl



The second family edge or face elements are not yet available on triangle and tetrahedron. Edge or face elements on quadrangle and hexahedron are not yet available.

`_optimizeNumbering` and `_notOptimizeNumbering` drive the activation/deactivation of the DoFs renumbering in order to reduce the bandwidth of matrices. The default behavior is `_optimizeNumbering`.

`_withLocateData` and `_withoutLocateData` drive the precomputation of data related to localization of a point in the mesh. The default behavior is `_withLocateData`.

Here are some examples of FE space construction:

```
//2D examples
Mesh mesh2d(Rectangle(_xmin=0,_xmax=1,_ymin=0,_ymax=1,_nnodes=10),
             _triangle,1,_gmsh);
Domain omega=mesh2d.domain("Omega");
//Lagrange Finite Element spaces
Space V1(_domain=omega, _interpolation=P1, _name="P1", _optimizeNumbering); //with numbering
optimization
Space V2(_domain:=omega, _interpolation=P2, _name="P2", _notOptimizeNumbering); //no numbering
optimization
Space V3(omega, interpolation(_Lagrange, _standard,20,H1),"P20");
FEInterpolation interp=interpolation(_Lagrange,_standard,20,H1);
Space V4(omega,interp,"P20");
//Hdiv Finite Element spaces
Space W1(_domain=omega, _interpolation=RT_1, _name="RT1");
Space W3(omega, interpolation(_RaviartThomas,_standard,3,Hdiv),"RT3");
//Hrot Finite Element spaces
Space R1(_domain=omega, _interpolation=NE1_1, _name="Ned1");
Space R2(_domain=omega, _interpolation=NE1_2, _name="Ned2");
Space R4(omega, interpolation(_Nedelec,_firstFamily,4,Hrot),"Ned4");

//3D examples
Mesh mesh3d(Cube(_origin=Point(0.,0.,0.), _length=1.,_nnodes=n),
             _tetrahedron,1,_gmsh);
Domain omega=mesh3d.domain("Omega");
Space V1(_domain=omega, _interpolation=P1, _name="P1");
Space V3(omega, interpolation(_Lagrange,_standard,3,H1),"P3");
Space W1(_domain=omega, _interpolation=NF1_1, _name="Hdiv_Ned1");
Space R2(_domain=omega, _interpolation=NE1_2, _name="Hrot_Ned2");
```



Note that when using the set of keys `_FE_type`, `_FE_subtype`, `_Sobolev_type_order`, `_FE_subtype` and `_Sobolev_type` are optional.

When dealing with problem with vector unknown where each component is approximated in the same space (for instance $P1 \times P1 \times P1$ for the displacement field in elasticity problem), you have to build a 'vector' unknown on a 'scalar' space; see the [Unknown](#) section.

Some subspaces or trace spaces are automatically created by XLife++. For instance, when an integral on a boundary (Σ) is involved in a bilinear or linear form, the trace space $V|_{\Sigma} = \{v|_{\Sigma}, v \in V\}$ is created. This subspace can be got using the following command:

```
Space& Vs=V|Sigma;
```

7.1.2 Spectral spaces

Spectral spaces are spaces defined from basis functions defined on a mesh domain. Contrary to finite element basis function given by a local definition on elements, the spectral basis functions are given as global functions either by their analytic forms or by a set of interpolated functions (say vectors related to another space).

The definition of spectral spaces is done with a key-value system:

key(s)	authorized types / possible values	examples
_basis	<code>Function</code> , <code>TermVector</code>	_basis =Function(sin_n, "sin_n", ps)
_dim	single unsigned integer	_dim =20, ...
_basis_dim	single unsigned integer	_basis_dim =3, ...
_name	<code>String</code>	_name ="Vh"

Analytic spectral space

Let us see an example :

```
Real sin_n(const Point& P, Parameters& pa = defaultParameters)
{
    Real h = pa("h");           // get the parameter h (user definition)
    Real n = pa("basis index");  // get the index of function to compute
    return sqrt(2. / h) * sin(n * pi * P.x() / h); // computation
}

int main (int argc, char** argv)
{
    Mesh m(\ldots);
    Domain omega=m.domain("Omega");
    Parameters ps(1., "h");
    Number n=10;
    Space sp(_domain=omega, _basis=Function(sin_n, "sin_n", ps), _dim=n, _name="sinus basis");
    \ldots
}
```

To define a spectral basis, you need to define a function of space coordinates with at least one parameter : the basis index. To do so, you have to define a standard C++ function, taking a `Point` and a `Parameters`. The first one contains the space coordinates. The second one contains all parameters needed to define the function. The return type of such function is `Real`. In the example above, you can notice how the parameter "h" is defined and used.

Once you have defined your C++ function, you have to pass it to the list of arguments of the `Space` constructor. To do so, you have to use the `Function` object, taking the name of the function, a string, and the `Parameters` object.

_dim sets the dimension of the spectral space (the size of the spectral basis). **_basis_dim** sets the dimension of basis functions (1 if scalar functions, for instance, that is the default value)

Interpolated spectral space

An interpolated spectral space is defined from a set of interpolated functions, say vectors of another space (`TermVectors`, see **Terms** chapter). The following example shows how it works:

```
int main (int argc, char** argv)
{
    Mesh m(\ldots);
    Domain omega=m.domain("Omega");
    Space V(omega, P1, "V", true); //create FE space
    Unknown u("u", V);           //create FE unknown
    Real h=1;
    Parameters params(h, "h");
    Function sinBasis(sin_n, params);

    TermVectors sinInt(N);        //interpolated functions
    for(Number n=0; n<N; n++)
    {
```

```

sinBasis.parameter("basis index")=n;
sinInt(n+1)=TermVector(u, omega, sinBasis, "c"+tostring(n));
}
Space S(_basis=sinInt, _name="V interpolated sin(n*pi*y)");

```

The `Unknown` object is described in the following section.

Advanced usage

It is possible to manipulate spectral basis by instantiate such objects:

```

SpectralBasisFun sbFun(omega, sinBasis, N, 1);
SpectralBasisInt sbInt(sinInt);

```

Thus, it is possible to evaluate basis functions at a point:

```

Real r;
Point P(1., 0.);
sbFun.function(n, P, r);
sbInt.function(n, P, r);

```

Be cautious, the type of returned argument `r` has to be consistent with the type of basis functions.

7.1.3 Unknowns and test functions

Once you have defined the space, the next step is to define unknowns and test functions on this space.

```

Unknown(Space& sp, const String& name, Dimen d=1);
TestFunction(Space& sp, const String& name, Dimen d=1);

```

According to the problem, you may want to define scalar or vector unknowns or test functions. The third argument is dedicated to this.

In case of a multiple unknowns problem, the order of unknowns may be sensitive. By default, they are sorted by the construction order, using the rank property of unknown:

```

Unknown u(V, "u", 2);
Unknown p(V, "p");
TestFunction v("v", u);
TestFunction q("q", p);
cout<<u.rank()<<" "<<v.rank()<<" "<<p.rank()<<" "<<q.rank();

```

This example gives 1 3 2 4.

It is possible to assign the rank of an unknown at the construction:

```

Unknown u(V, "u", 2, 2); //rank 2
Unknown p(V, "p", 1, 1); //rank 1
TestFunction v(u, "v", 4); //rank 4
TestFunction q(p, "q", 3); //rank 3
cout<<u.rank()<<" "<<v.rank()<<" "<<p.rank()<<" "<<q.rank();

```

Be cautious, rank has to be unique! It is not mandatory that ranks follow.

The `setRanks` function may be used to change the ranks of a collection of unknowns:

```

\ldots
setRanks(u, 1, p, 2, v, 11, q, 12);

```

7.1.4 Dealing with collections

When there is a lot of domains, spaces, unknowns it may be more friendly to work with indexed collection. This is the purpose of the classes `Domains`, `Interpolations`, `Spaces`, `Unknowns` and `TestFunctions`. As an example, suppose you want to deal with 4 domains:

```
Strings sn( "Gamma1", "Gamma2", "Gamma3", "Gamma4" );
Mesh mesh2d( Rectangle( _xmin=0, _xmax=0.5, _ymin=0, _ymax=1, _nnodes=Numbers(3,6),
    _domain_name="Omega", _side_names=sn ), _triangle, 1, _structured );
//get the mesh domains in a Domains object
Domains doms(4);
for( Number i=1; i<=4; i++) doms(i)=mesh2d.domain(i-1);
//create one space by domain (say P1)
Spaces Vs(4);
for( Number i=1; i<=4; i++) Vs(i)=Space(doms(i), _P1, "V_"+tostring(i));
//create unknowns
Unknowns us(4);
for( Number i=1; i<=4; i++) us(i)=Unknowns(Vs(i), "u"+tostring(i));
//create TestFncions
TestFunctions vs=dualOf(us);
```

Other syntaxes are available:

```
Unknown u1(V1, "u1"), u2(V2, "u2"), u3(V3, "u3");
Unknowns us1(u1, u2, u3);
Unknowns us2; us2<<u1<<u2<<u3;
Unknowns usi={u1, u2, u3}; //only in C++2011
```

7.2 Forms

Given a PDE, you have to write a variational formulation. As a result, you have an equality between 2 forms : a bilinear form on the unknown u and the tests function v , generally called a , and a linear form on the test function v , generally called l . Both are defined as linear combination of single or double integrals on operators on unknowns and, in the bilinear case, test functions, and an integration method or a *quadrature rule*.

```
BilinearForm intg(const GeomDomain& dom, const OperatorOnUnknowns& opus, QuadRule qr=
    _defaultRule, Number qro=0);
BilinearForm intg(const GeomDomain& dom, const LcOperatorOnUnknowns& opus, QuadRule qr=
    _defaultRule, Number qro=0);
BilinearForm intg(const GeomDomain& domx, const GeomDomain& domy, const OperatorOnUnknowns& opus,
    QuadRule qr = _defaultRule, Number qro = 0);
BilinearForm intg(const GeomDomain& domx, const GeomDomain& domy, const KernelOperatorOnUnknowns&
    kopus, QuadRule qr = _defaultRule, Number qro = 0);
LinearForm intg(const GeomDomain& dom, const OperatorOnUnknown& opu, QuadRule qr = _defaultRule,
    Number qro = 0);
LinearForm intg(const GeomDomain& dom, const Unknown& u, QuadRule qr = _defaultRule, Number qro =
    0);
LinearForm intg(const GeomDomain& domx, const GeomDomain& domy, const OperatorOnUnknown& opu,
    QuadRule qr = _defaultRule, Number qro = 0);
LinearForm intg(const GeomDomain& domx, const GeomDomain& domy, const Unknown& u, QuadRule qr =
    _defaultRule, Number qro = 0);
```

In simple case, symmetry property of a bilinear form may be deduced from its definition. In some cases, the analysis being too intricate, the symmetry property is not deduced. It is the reason why it is possible to enforce this property in the definition of bilinear form involving integral by specifying as last argument one of the symmetry keywords:

```
_noSymmetry, _symmetric, _skewSymmetric, _selfAdjoint, _skewAdjoint
```

For instance, if A is a symmetric matrix :

```
BilinearForm b = intg(S,u|v); //implicit symmetry
BilinearForm b = intg(S,(A*u)|v,_symmetric); //explicit symmetry
```

Often, bilinear forms are some linear combination of integrals and the symmetry may result of the sum of non-symmetric integrals. In such cases, it is possible to force the symmetry by using the following syntax:

```
BilinearForm d = intg(omega,dx(u)*dy(v))+intg(omega,dy(u)*dx(v)); //considered as non-symmetric!
d.symType()=_symmetric; //defined as symmetric
```



Be cautious, the usage of `symType()` is restricted to single unknown bilinear forms!



Keep in mind that u and v represent shape functions of the space which are real functions!. Thus, there is no reason to conjugate test functions.

7.2.1 Operators on unknowns

XLIFE++ management of operators on unknowns is as close as possible to the mathematical description, few operators are overloaded and a lot of possibilities are offered, For instance:

mathematical expression	XLIFE++ translation	comment
$\nabla(u)$	<code>grad(u)</code>	u unknown
$\nabla(u) \cdot \nabla(v)$	<code>grad(u) grad(v)</code>	u unknown, v test function
$(A * \nabla(u)) \cdot \nabla(v)$	<code>(A*grad(u)) grad(v)</code>	u unknown, v test function, A matrix
$(F(x) * \nabla(u)) \cdot \nabla(v)$	<code>(F*grad(u)) grad(conj(v))</code>	u unknown, v test function, F a function
$u(x)*G(x,y)*v(y)$	<code>u*G*v</code>	u unknown, v test function, G a kernel

Defining functions needs C++ functions with specific prototypes :

```
OUT f1(const Point& P, Parameters& pa = defaultParameters); // scalar form
Vector<OUT> f2(const Vector<Point>& Ps, Parameters& pa = defaultParameters); // vector form
```

The return type OUT can be one of the following: **Real**, **Complex**, **Vector**<**Real**>, **Vector**<**Complex**>, **Matrix**<**Real**> or **Matrix**<**Complex**>.

You can use the function directly in your integral, or define **Function** object such as

```
Function F(f1, "name", params);
```

You can optionally give a name to the **Function** object and a **Parameters** object when needed.

Defining kernels needs also C++ functions with specific prototypes

```
OUT f1(const Point& P, const Point & MParameters& pa = defaultParameters); // scalar form
Vector<OUT> f2(const Vector<Point>& Ps, const Vector<Point>& Ms, Parameters& pa =
defaultParameters); // vector form
```

You can use the function directly in your integral, or define **Kernel** object such as

```
Kernel F(f1, "name", params);
```

You can optionally give a name to the **Kernel** object and a **Parameters** object when needed.

The complete list of operators is in the following, where u is either a scalar or vector unknown, x , y and z are the Cartesian coordinates and n is the normal:

mathematical	built-in functions	unknown
identity	<code>id(u)</code> or <code>u</code>	scalar or vector
∂_t	<code>d0(u)</code> or <code>dt(u)</code>	scalar or vector
∂_x	<code>d1(u)</code> or <code>dx(u)</code>	scalar or vector
∂_y	<code>d2(u)</code> or <code>dy(u)</code>	scalar or vector
∂_z	<code>d3(u)</code> or <code>dz(u)</code>	scalar or vector
∇	<code>grad(u)</code> or <code>nabla(u)</code>	scalar or vector
div	<code>div(u)</code>	vector
curl	<code>curl(u)</code> or <code>rot(u)</code>	vector
∇_τ (surfacic)	<code>gradS(u)</code> or <code>nablaS(u)</code>	scalar or vector
div_τ (surfacic)	<code>divS(u)</code>	vector
curl_τ (surfacic)	<code>curlS(u)</code> or <code>rotS(u)</code>	vector
$\nabla_{abc} = (a\partial_x, b\partial_y, c\partial_z)$	<code>gradG(u, a, b, c)</code> or <code>nablaG(u, a, b, c)</code>	scalar or vector
$\nabla_{abc} \cdot$	<code>divG(u, a, b, c)</code>	vector
$\nabla_{abc} \times$	<code>curlG(u, a, b, c)</code> or <code>rotS(u, a, b, c)</code>	vector

mathematical	built-in functions	unknown
ε	<code>epsilon(u)</code>	vector
ε_{iabc}	<code>epsilonG(u, i, a, b, c)</code>	vector
ε_R	<code>epsilonR(u) = (\varepsilon_{11}, \varepsilon_{11}, \varepsilon_{22}, \varepsilon_{33}, \varepsilon_{32}, \varepsilon_{31}, \varepsilon_{21})</code>	vector
voigtToM	<code>voigtToM(u) = [u1 u6 u5; u6 u2 u4; u5 u4 u3]</code>	vector
$n \cdot$	<code>nx(u)</code> or <code>_n*u</code>	scalar
$n \cdot$	<code>ndot(u)</code> or <code>_n.u</code>	vector
$n \times$	<code>ncross(u)</code> or <code>_n^u</code>	vector
$n \times n \times$	<code>ncrossncross(u)</code> or <code>_n^_n^u</code>	vector
$n \cdot \nabla$	<code>ndotgrad(u)</code> or <code>_n.grad(u)</code>	scalar
$n \times \nabla$	<code>ncrossgrad(u)</code> or <code>_n^grad(u)</code>	scalar
$n \text{ div}$	<code>ndiv(u)</code> or <code>_n*div(u)</code>	vector
$n \times \text{curl}$	<code>ncrosscurl(u)</code> or <code>_n^curl(u)</code>	vector
$[\]$ (jump across)	<code>jump(u)</code>	scalar or vector
$\{ \}$ (mean across)	<code>mean(u)</code>	scalar or vector



`jump` and `mean` operators are to be used relatively to a domain of side elements (interface of domains or set of sides, see `sidesDomain` function). They must be interpreted on a side element S of two elements E_1 and E_2 as

$$[u]_S = u_1 - u_2 \text{ and } \{u\}_S = \frac{1}{2}(u_1 + u_2)$$

where $u_1 = (u|_{E_1})|_S$ and $u_2 = (u|_{E_2})|_S$. The sign of `jump` is sensitive to the choice of the first element. Regarding the context, XLIFE++ may choose the right one, but it is not absolutely safe. Note that for DG approximations, generally the formulation is not sensitive to this choice. For instance

$$\begin{aligned}
\int_S [[u]]_S \cdot \{\nabla v\}_S &= \frac{1}{2} \int_S (u_1 n_1 + u_2 n_2) \cdot (\nabla v_1 + \nabla v_2) = \frac{1}{2} \int_S (u_1 - u_2) (\nabla v_1 \cdot n_1 + \nabla v_2 \cdot n_1) \\
&\quad (n_2 = -n_1) = \frac{1}{2} \int_S (u_2 - u_1) (\nabla v_2 \cdot n_2 + \nabla v_1 \cdot n_2) \\
&= \int_S [u]_S \{\nabla v \cdot n\}_S
\end{aligned}$$

Note that the last expression is the way to take into account such DG term in XLIFE++.



A new and experimental feature allows combining different operations on the unknown u and the test function v inside the same integral:

```
BilinearForm d = intg (omega, grad (u) | grad (v)) + intg (omega, u*v);
BilinearForm d = intg (omega, (grad (u) | grad (v)) + u*v); // new syntax
LinearForm l = intg (omega, v) + intg (omega, dx (v));
LinearForm l = intg (omega, v + dx (v)); // new syntax
```

It is even possible to factorize expressions:

```
BilinearForm d = intg (omega, (dx (u) + dy (u)) * v);
```

Because of the operation order induced by C++ language, parentheses must be added sometimes to help the interpretation of the integral by XLIFFE++. This occurs frequently for low-priority C++ operation such as $|$ and $^$.

7.2.2 Operators on kernel

Similar to operator on unknowns, XLIFFE++ allows to apply some operators on kernel (say $k(x, y)$). The complete list of operators is the following :

mathematical	built-in functions	unknown
identity	<code>id(k)</code> or <code>k</code>	scalar or vector
∇_x	<code>grad_x(k)</code> or <code>nabla_x(k)</code>	scalar or vector
∇_y	<code>grad_y(k)</code> or <code>nabla_y(k)</code>	scalar or vector
div_x	<code>div_x(k)</code>	vector
div_y	<code>div_y(k)</code>	vector
curl_x	<code>curl_x(k)</code> or <code>rot_x(k)</code>	vector
curl_y	<code>curl_y(k)</code> or <code>rot_y(k)</code>	vector
$n_x \cdot$	<code>ntimes_x(k)</code> or <code>_nx*k</code>	scalar
$n_y \cdot$	<code>ntimes_y(k)</code> or <code>_ny*k</code>	scalar
$n_x \cdot$	<code>ndot_x(k)</code> or <code>_nx.k</code>	vector
$n_y \cdot$	<code>ndot_y(k)</code> or <code>_ny.k</code>	vector
$n_x \times$	<code>ncross_x(k)</code> or <code>_nx^k</code>	vector
$n_y \times$	<code>ncross_y(k)</code> or <code>_ny^k</code>	vector
$n_x \times (n_x \times)$	<code>ncrossncross_x(k)</code> or <code>_nx^(_nx^k)</code>	vector
$n_y \times (n_y \times)$	<code>ncrossncross_y(k)</code> or <code>_ny^(_ny^k)</code>	vector

mathematical	built-in functions	unknown
$n_x \cdot \nabla_x$	<code>ndotgrad_x(k)</code> or <code>_nx.grad_x(k)</code>	scalar
$n_y \cdot \nabla_y$	<code>ndotgrad_y(k)</code> or <code>_ny.grad_y(k)</code>	scalar
$n_x \text{div}_x$	<code>ndiv_x(k)</code> or <code>_nx*div_x(k)</code>	vector
$n_y \text{div}_y$	<code>ndiv_y(k)</code> or <code>_ny*div_y(k)</code>	vector
$n_x \times \text{curl}_x$	<code>ncrosscurl_x(k)</code> or <code>_nx^curl_x(k)</code>	vector
$n_x \cdot n_y \cdot$	<code>nxdotny_times(k)</code> or <code>(_nx _ny)*k</code>	scalar or vector
$(n_x \times n_y) \cdot$	<code>ncrossny_dot(k)</code> or <code>(_nx^_ny) k</code>	vector
$(n_y \times n_x) \cdot$	<code>nycrossnx_dot(k)</code> or <code>(_ny^_nx) k</code>	vector
$(n_x \times n_y) \times$	<code>ncrossny_cross(k)</code> or <code>(_nx^_ny)^k</code>	vector
$(n_y \times n_x) \times$	<code>nycrossnx_cross(k)</code> or <code>(_ny^_nx)^k</code>	vector

In operators, the normal vectors `_n`, `_nx`, `_ny` are symbolic ones. They refer to real normal vectors related to the domain involved in integrals where operators appear. See the section 6.10.2 to know how normal vectors are oriented.



When one of the argument is a complex, the "inner product" means a hermitian product.

7.2.3 Available standard kernels

There are currently some kernels available in XLiFE++ for 2D and 3D problems: Laplace and Helmholtz Green functions, and Maxwell Green tensor in 3D:

- The Laplace kernel used for 2D problems is

$$L_{2d}(x, y) = -\frac{1}{2\pi} \log(\|x - y\|),$$

and for 3D we use

$$L_{3d}(x, y) = \frac{1}{4\pi\|x - y\|}$$

- The Helmholtz Green function for 2D problems used is

$$H_{2d}(k; x, y) = \frac{i}{4} H_0^{(1)}(k\|x - y\|),$$

with $H_0^{(1)}$ the first kind Hankel function of order 0. Finally, for 3D problems we use

$$H_{3d}(k; x, y) = \frac{e^{ik\|x - y\|}}{4\pi\|x - y\|}.$$

- The harmonic Maxwell Green tensor for 3D problems is defined as:

$$M_{3d}(k; x, y) = H_{3d}(k; x, y) \mathbb{I}_3 + \frac{1}{k^2} \text{Hess}(H_{3d}(k; x, y)).$$

Examples of declaration of these kernels follow:

```
Kernel GLap2D=Laplace2dKernel();
Kernel GLap3D=Laplace3dKernel();
Parameters pars(k, "k"); // We provide the wavenumber k using a Parameters
Kernel GHelm2D=Helmholtz2dKernel(pars);
Kernel GHelm3D=Helmholtz3dKernel(k);
```

7.2.4 Tensor kernel

Tensor kernel is a kernel of the general form

$$\begin{aligned} K(x, y) &= \sum_{n=1, N} \sum_{m=1, M} \psi_m(x) \mathbb{A}_{mn} \varphi_n(y) \\ &= (\psi_1(x), \dots, \psi_M(x)) \mathbb{A} (\varphi_1(y), \dots, \varphi_N(y))^t. \end{aligned}$$

It is involved in the so-called DtN operator, for instance:

$$Tu = \sum_{n=1, N} \lambda_n(u, \varphi_n)_{L^2(\Sigma)} \varphi_n$$

where a related bilinear form could be

$$b(u, v) = \int_{\Sigma} \int_{\Sigma} Tu v = \int_{\Sigma} \int_{\Sigma} \sum_{n=1, N} \lambda_n u(y) \varphi_n(y) v(x) \varphi_n(x) = \int_{\Sigma} \int_{\Sigma} u(y) K(x, y) v(x).$$

In that case, $\mathbb{A}$ is a diagonal matrix ($\mathbb{A}_{nn} = \lambda_n$).

The construction of such tensor kernel is described in the annex B ([TensorKernel](#) class).

7.2.5 Interpolated function in operator

Interpolated functions are function defined from finite element approximation :

$$f(x) = \sum_{i=1,q} f_i w_i(x)$$

where w_i are some finite element shape functions and f_i are some real/complex scalar/vector coefficients. With Lagrange FE, $f_i = f(x_i)$ where x_i is the node related to the shape function w_i .

In XLiFE++ lib, such function may be represented by a `TermVector` object that handles both a FE space, thus the shape functions, and the coefficients in an array of values. By specifying a `TermVector` object in an operator construction, an interpolated function will be handled.

```
Mesh m(Square(_origin=Point(0.,0.),_length=1.,_nnodes=5,_domain_name="Omega"),
        _triangle,1,_structured);
Domain omega=m.domain("Omega");
Space V(omega,P1,"V"); Unknown uh(V,"u");
TermVector x1(u,omega,_x1,"x1"); // interpolated function
LinearForm l1=intg(omega,x1*u);
LinearForm l2=intg(omega,(x1^3)*u);
```

Such approach may be very useful for non-linear problem when non-linear terms are taken into account at a previous step in an iterative scheme.



For the moment, the way that XLiFE++ processes, consists in transforming the `TermVector` object in a `Function` object that performs the computation of the sum outside any context : first locate the finite element that contains the point x , then evaluate using local interpolation. As the localization algorithm has a log complexity, computation of the interpolated function at a point is not so time expansive, but it is not optimal, in particular when computing integral.

7.2.6 Additional operation in operator

Transpose and conjugate

Some quantities (function or kernel) involved in a bilinear form may have to be transposed or conjugated. XLiFE++ provides 3 operators to do it:

- `tran` to transpose an expression
- `conj` to conjugate an expression
- `adj` to conjugate and transpose an expression

Obviously, transposition has only meaning for functions or kernels returning a matrix! In XLiFE++, the shape functions related to a FE space are real scalar/vector functions, so transpose or conjugate an unknown has no interest and, by the way, is not allowed!

Extension

Some problems require dealing with the extension of a function/kernel, say f or k , from a boundary (say Γ) to its parent domain (say Ω). XLiFE++ provides a particular extension process that extends function/kernel from the boundary Γ to its neighborhood, that is the set of elements that have at least one vertex located onto Γ , say Γ_{ext} . More precisely, the extension formula is:

$$E_{\Gamma}(f)(x) = \sum_{M_i \in \Gamma} f(M_i) w_i(x)$$

where M_i are some mesh vertices and w_i the one order Lagrange shape functions related to the vertex M_i . Such extension vanishes outside Γ_{ext} .

Define an extension is very easy. You have to specify the boundary domain to be extended, if not unique, the domain where you want to do the extension and the variable if you want to extend a kernel :

```
Extension Eg (Gamma) ; //extend from Gamma to elements in its neighborhood
Extension Eg (Gamma, _y) ; //extend from Gamma for variable y
Extension Eg (Gamma, Omega) ; //extend from Gamma to Omega
Extension Eg (Gamma, Omega, _x) ; //extend from Gamma to Omega for variable x
```

The set of elements in the neighborhood of Γ can be explicitly constructed by using the `extendedDomain` member function of `Domain` :

```
Domain Gamma_ext=Gamma. extendDomain () ; //elements having a side on Gamma
Domain Gamma_ext=Gamma. extendDomain (true) ; //elements having a vertex on Gamma
```

Finally, to use extension in bilinear form, write for instance

```
Extension Eg (Gamma, Omega) ;
BilinearForm a=intg (Omega, u*Eg (f) *v) ; //extension of a function
Eg. var=_y;
BilinearForm a=intg (Gamma, Omega, u*Eg (k) *v) ; //extension of a kernel along y
```



The computation are automatically restricted to elements of the extended domain, so you do not have to restrict yourself.

Be cautious, when applying an extension to an object involving kernel derivatives; for instance

$$E_{\Gamma,x}[dy(k)](x,y) = \sum_{M_i \in \Gamma} dy(k)(M_i, y) w_i(x)$$

$$E_{\Gamma,x}[dx(k)](x,y) = \sum_{M_i \in \Gamma} dx(k)(M_i, y) w_i(x) + \sum_{M_i \in \Gamma} k(M_i, y) dx(w_i)(x).$$

Summary of main operator syntaxes

In the following:

- `val` represents any constant value, that is a real or a complex value, a real or a complex vector or a real or a complex matrix,
- `fun` represents a `Function` object or an explicit C++ function
- `opfun` represents an `OperatorOnFunction` object, say `difop(Function)`; only few differential operators are available
- `ker` represents a `Kernel` object or an explicit C++ function
- `opker` represents an `OperatorOnKernel` object, say `difop(Kernel)`; only few differential operators are available
- `tv` represents a `TermVector` object
- `aop` represents an algebraic operator, one of `*` `|` `^` `%`

[val/fun/opfun/tv aop] [difop] (Unknown) [aop val/fun/opfun/tv]	→ opu
opu [aop opu]	→ opus
opu aop ker/opker [aop opu]	→ kopus

7.2.7 Integration method

When defining a linear or a bilinear form, the user may specify the integration method or a list of integration methods to use. Currently the following objects are available:

- **QuadratureIM**: quadrature methods based on quadrature points and weights, see quadrature rule in the next section
- **IntegrationMethods**: specific methods to integrate singular kernel in bilinear form, see details in the next section

To use it in a computation, specify an integration object in the definition of the form:

```
QuadratureIM quadIM(Gauss_Legendre,2);           //standard quadrature method
BilinearForm blf=intg(omega,uv,quadIM);
BilinearForm blf=intg(omega,uv,Gauss_Legendre,2); //shortcut syntax
//for singular integrals
IntegrationMethods ims(Sauter_Schwab,3,0.,Gauss_Legendre,3);
BilinearForm blf=intg(sigma,sigma,u*G*v,ims);
IntegrationMethods imr(Gauss_Legendre,3);
LinearForm lf=intg(sigma,G*u,imr,U);
```

Note that integration method is attached to the integral definition. So you can mix different integration methods in a bilinear form :

```
BilinearForm blf = intg(omega,grad(u)|grad(v),Gauss_Lobatto,1)
+ intg(omega,u*v,Gauss_Legendre,2);
```

Using mixed integration methods is generally slower than using the same integration method!



It is not mandatory to specify an integration method in form; a default one is chosen according to the order of unknown interpolations, the order of differential operators involved and the fact that there are functions in operator on unknowns. For FE form, we use the minimal quadrature rule for shapes involved in domain which integrates exactly the polynomials of order

$$k = (deg(u) - order(dif(u))) * [deg(u)] * [(deg(v) - order(dif(v))) * [deg(v)]]$$

where $deg(u)$ (resp. $deg(v)$) is the degree of polynomials used by u -interpolation (resp. v -interpolation), $order(dif(u))$ (resp. $order(dif(v))$) is the order of differential operator applied to u (resp. v). $[]$ means an optional coefficient.

The table of the best rules is given in the developer's documentation.

Quadrature rules

To perform computation of integrals over reference elements, XLI++ provides a lot of quadrature formulae of the form :

$$\int_{\hat{E}} f(\hat{x}) d\hat{x} \approx \sum_{i=1,q} \omega_i f(\hat{x}_i)$$

where $(\hat{x}_i)_{i=1,q}$ are quadrature points belonging to reference element $\hat{E}$ and $(\omega_i)_{i=1,q}$ are quadrature weights. Up to now, there exist quadrature formulae for unit segment $]0,1[$, for unit triangle, for unit quadrangle (square), for unit tetrahedron, for unit hexahedron (cube), for unit prism and for unit pyramid. The following tables give the list of quadrature rule available:

General rules

	Gauss-Legendre	Gauss-Lobatto	Grundmann-Muller	symmetrical Gauss
segment	any odd degree	any odd degree		
quadrangle	any odd degree	any odd degree		odd degree up to 21
triangle	any odd degree		any odd degree	degree up to 10
hexahedron	any odd degree	any odd degree		odd degree up to 11
tetrahedron	any odd degree		any odd degree	degree up to 10
prism				degree up to 10
pyramid	any odd degree	any odd degree		degree up to 10

Particular rules

	nodal	miscellaneous
segment	P1 to P4	
quadrangle	Q1 to Q4	
triangle	P1 to P3	Hammer-Stroud 1 to 6
hexahedron	Q1 to Q4	
tetrahedron	P1, P3	Stroud 1 to 5
prism	P1	centroid 1, tensor product 1,3,5
pyramid	P1	centroid 1, Stroud 7

The developer documentation gives more details on quadrature rules and indicates what best rules (in terms of number of quadrature points) are selected when only shape and degree are specified. Generally for low degree ($d \leq 3$) a specific rule is selected, for intermediate degree ($4 \leq d \leq 10$) a symmetrical Gauss rule is selected and for high degree a quadrature rule working at any degree (Gauss-Legendre or Grundman-Muller) is chosen.

How to choose the quadrature rule ?

By using `intg` with a specific pair of arguments:

- `QuadRule` qr, to give the quadrature rule formulae (possible values are Gauss_Legendre, Gauss_Lobatto, nodalQuadrature, miscQuadrature, Grundmann_Moller or symmetrical_Gauss),
- `Number` qro, to give the quadrature rule degree:

```
BilinearForm a=intg(Omega,u*v,Gauss_Legendre,4);
```

When no rule and degree are given, the degree is determined by looking the degree of polynomials involved in the (bi)linearform taking into account derivative operators and the existence of an additional user function. For instance, the following bilinear form in P^k finite element space

$$\int_{\Omega} f u v$$

will ask for a quadrature rule of degree $d = 3k$ while the following bilinear form

$$\int_{\Omega} \nabla u \cdot \nabla v$$

will ask for a quadrature rule of degree $d = 2(k - 1)$.

Once the degree d is determined, XLiFE++ chooses the best quadrature rule available for degree d and element shapes involved in the mesh domain.



The user choice is always a priority even his choice leads to under integration. In doubt, let XLiFE++ work for you!

Integration methods for integral equation or integral representation

Integral equation involves singular kernels. To deal with the singularity in integrals, some particular methods are proposed to users. `LenoirSallesxx` classes compute in an analytic way integrals involving 2D or 3D Laplace kernel but with low order finite elements (P0 or P1) whereas there are methods for any finite element order but specific problem dimension such as `SauterSchwabIM` for 3D problems and `DuffyIM` for 2D problems. Currently, only $\log(r)$ in 2D and r^{-1} in 3D singularities are addressed.

`SauterSchwabIM`¹ class addresses computation of integral

$$\int_{\Gamma} \int_{\Sigma} K(x, y) dx dy$$

where Γ and Σ are 2D domains (in 3D) (partition of triangles) and $K(x, y)$ a kernel having possibly a singularity of type $1/||x - y||$. This technique is well adapted for most second order PDE in 3D. It uses Gauss-Legendre quadrature on segment. When creating such method, you may specify the quadrature order on segment:

```
SauterSchwabIM ssIM(5);
```

The default order is 3. Sauter-Schwab method works for any finite element on triangle.



The Sauter-Schwab method consist in transforming the integral over a triangle pair to some integrals over the unity cube of $\mathbb{R}^4$ and then computing each integral using a 4 tensor product of standard quadrature formula on segment. As a consequence, the number of points where the kernel is evaluated grows as a power 4 of the number of quadrature points used on segments. So increasing the order of quadrature on segment may be very time expansive.

`DuffyIM`² class addresses computation of integral

$$\int_{\Gamma} \int_{\Sigma} K(x, y) dx dy$$

where Γ and Σ are 1D domains (in 2D) (partition of segments) and $K(x, y)$ a kernel having possibly a singularity of type $\log(||x - y||)$. This technique is well adapted for most second order PDE in 2D. Duffy transform is used to compute integrals involving segments sharing only one vertex (say adjacent elements) and t^p transform method is used to compute self-influence coefficients (same segments). By default, $p = 5$.

When creating such method, you may specify the quadrature order on segment:

```
DuffyIM dufIM(5);
```

The default order is 6. It is possible to specify different orders It is possible to choose different quadrature orders depending on whether the case is adjacent or self-influence :

```
DuffyIM dufIM(10,8);
```

A full constructor allows to specify different quadratures regarding the directions x or y , the geometrical configuration of both segments (self influence or adjacent), the order p of t^p transform. For instance, to use a very accurate quadrature (required in case of P2 curved element):

```
DuffyIM dufim(_GaussLegendreRule,20,_GaussLegendreRule,20,
_GaussLegendreRule,60,_GaussLegendreRule,60,7);
```

Duffy method works for any finite element on 1D element.



The **DuffyIM** class addresses only singular configurations. User has to provide some regular quadratures for regular configurations.

LenoirSalles2dIM and **LenoirSalles3dIM**³ classes address computation of integral

$$\int_{\Gamma} \int_{\Sigma} p(x) K(x, y) q(y) dx dy$$

or

$$\int_{\Gamma} \int_{\Sigma} p(x) \partial_{n_y} K(x, y) q(y) dx dy$$

where Γ and Σ 2D domains in 3D (partition of triangles) or 1D domains in 2D (partition of segments), $K(x, y)$ the Laplace kernel and p, q are either piecewise constant functions or piecewise linear functions. It deals only the case of elements sharing at least one vertex. So for elements that are not close to, a standard quadrature has to be used. These classes do not manage any parameter:

LenoirSalles3dIM ls2 ;
LenoirSalles2dIM ls3 ;

LenoirSalles2dIR and **LenoirSalles3dIR** classes address computation of integral

$$i(x) = \int_{\Gamma} K(x, y) q(y) dy$$

or

$$i(x) = \int_{\Gamma} \partial_{n_y} K(x, y) q(y) dy$$

where Γ is either a 2D domain in 3D (partition of triangles) or a 1D domain in 2D (partition of segments), $K(x, y)$ the Laplace kernel and q is an either piecewise constant function or piecewise linear function. These classes do not manage any parameter:

LenoirSalles3dIR ls2 ;
LenoirSalles2dIR ls3 ;

CollinoIM class is a wrapper to an integration method developed by F. Collino to deal with some integrals involved in 3D Maxwell BEM when using Raviart-Thomas elements of order 1 (triangle). More precisely, it can compute the integrals:

$$\int_{\Gamma} \int_{\Gamma} \left(k H(k; x, y) w_j(y) \cdot w_i(x) - \frac{1}{k} H(k; x, y) \operatorname{div} w_j(y) \operatorname{div} w_i(x) \right)$$

and

$$\int_{\Gamma} \int_{\Gamma} (\nabla_y H(k; x, y) \times w_j(y)) \cdot w_i(x),$$

where $(w_i)_{i=1,n}$ denote the Raviart-Thomas shape functions and $H(k; x, y)$ the Green function of the Helmholtz equation (wave number k) in the 3D free space. For instance, to compute the first integral, write

```

Space RTh(_domain=Gamma, _interpolation=RT_1, _name="RTh");
Unknown U(RTh, "U"); TestFunction V(U, "V");
IntegrationMethods imc(CollinoIM(_computeI1,3,64,12,3.));
Kernel H = Helmholtz3dKernel(k);
BilinearForm ac = intg(Gamma, Gamma, k*(U*H|V) - (1./k)*(div(U)*H*div(V)), imc);
TermMatrix S(ac);

```

Note the non-standard expression of the bilinear form that incorporates a linear combination of kernel operator on unknowns. Use this syntax ONLY in this context! The parameters involved in the `CollinoIM` object correspond to the default values.

Define several integration methods

Computing integral with kernel is a costly business because of the kernel singularity. But in fact, this singularity is effective only in particular situations : when two elements share at least one vertex in BEM computation or when the point is too close to an element in IR computation. This is the reason why XLife++ provides a way to choose different integration methods regarding a geometric criterion: the relative distance between the centroids of elements

$$dr(E_i, E_j) = \frac{\|C_i - C_j\|}{\max(\text{diam}(E_i), \text{diam}(E_j))}$$

or the relative distance between a point and the centroid of element

$$dr(x, E_i) = \frac{\|x - C_i\|}{\text{diam}(E_i)}.$$

The `IntegrationMethods` class collect integration methods with two additional information:

- the bound value b telling the integration method is applied when $dr \leq b$
- the part of the function concerned by the integration method, one of `_allFunction`, `_regularPart`, `_singularPart`, the default value is `_allFunction`.


There is a lot of way to define an `IntegrationMethods` object. Here are given some classical forms:

```

IntegrationMethods ims1(Sauter_Schwab,3,0.,defaultQuadrature,5);
IntegrationMethods ims2(Duffy,5,0.,Gauss_Legendre,10,1.,
                        Gauss_Legendre,5,2.,
                        Gauss_Legendre,3);
IntegrationMethods ims3(Lenoir_Salles_3d, Gauss_Legendre,5);
IntegrationMethods imsh(LenoirSalles2dIR(), _singularPart, theRealMax,
                       QuadratureIM(_GaussLegendreRule,4), _regularPart, theRealMax);

```

For instance, the definition of `ims2` corresponds to the following choice:



Beware of the definition of an `IntegrationMethods` object. In particular, check that all the cases are handled.

7.2.8 Integral calculation tools

Besides integration methods related to finite element computations, XLiFE++ provides some general tools to approximate 1D integrals:

$$\int_a^b f(t) dt.$$

Uniform rectangle, trapeze and Simpson methods

XLiFE++ handles the uniform rectangle, trapeze, Simpson method ($h = \frac{b-a}{n}$) :

$$\begin{aligned} \text{rectangle} &: \int_a^b f(t) dt \sim h \sum_{i=0, n-1} f(a + ih) \\ \text{trapeze} &: \int_a^b f(t) dt \sim \frac{h}{2} \left(f(a) + 4 \sum_{i=1, n/2} f(a + (2i-1)h) + 2 \sum_{i=1, n/2-1} f(a + 2ih) + f(b) \right) \quad (n \text{ even}) \\ \text{Simpson} &: \int_a^b f(t) dt \sim \frac{h}{3} \left(f(a) + 2 \sum_{i=1, n-1} f(a + ih) + f(b) \right) \end{aligned}$$

with f a real or complex function. They respectively integrate exactly P0 polynomials, P1 polynomials and P3 polynomials and approximate the integral with order 1, 2 and 3.

For each method, three template functions (with names `rectangle`, `trapz`, `simpson`) are provided according to the user gives the values of f on a uniform set of points, the function f or a function f with some parameters (e.g. trapeze method):

```
Real f(Real t) {return t*t;}
Complex fp(Real t, Parameters& pars)
{
    Int p=pars("p");
    return pow(t,p)*exp(i*t);
}
\dots
Number n=100;
Real intf = trapz(f,0,1,n);           //int_[0,1]f(t)dt
Parameters pa(2,"p");
Complex intfp = trapz(fp,pa,0,1,n);    //using parameters
Vector<Real> vf(n+1);
Real h=1./n;
for(Number k=0;k<=n; k++) vf[k]=f(k*h);
Real intf_v = trapz(vf,h);            //using values instead of function
```

For advanced users, there exists also functions using iterators.

Adaptive trapeze

XLiFE++ provides also an adaptive trapeze method using the improved trapeze method $(0.25(b-a)(f(a) + 2f((a+b)/2) + f(b)))$ to get an estimator. The user has to give its function (with parameters if required), the integral bounds a tolerance factor (10^{-6} if not given):

```
Real intf = adaptiveTrapz(f,0,1);      //int_[0,1]f(t)dt with 1E-6 as tolerance
Parameters pa(2,"p");
Complex intfp = adaptiveTrapz(fp,pa,0,1,1E-4); //using parameters and a tolerance
```



Because at the first step, the adaptive method uses 5 points uniformly distributed, the result may be surprising if unfortunately the function takes the same value at these points!

Discrete fast Fourier transform (FFT)

XLiFE++ provides the standard 1D discrete fast Fourier transform with 2^n values:

$$g_k = \sum_{j=0, n-1} f_j e^{-2i\pi \frac{jk}{n}}.$$

FFT and inverse FFT are computed using some functions addressing real or complex vectors of size 2^n :

```
Number ln=6, n=64;
Vector<Complex> f(n), g(n), f2(n);
for (Number i=0; i<n; i++) f[i]=std::sin(2*i*pi/(n-1));
fft(f,g); ifft(g,f2); // f2 should be close to f
// or
Vector<Complex> fhat=fft(f), fihat=ifft(f);
```



If the vector you give is not of 2^n length, `fft/ifft` computation will use only the first 2^n values with 2^n the greater value less than the vector size. Remember that even the input vector is a real vector the output is always a complex vector.

Advanced users can also use some functions `fft/ifft` addressing iterators that can handle any collection of real or complex values. See the dev documentation.

Filon's method for oscillatory integrals

Up to now, only one method is provided to compute 1D oscillatory integrals based on the Filon's method. It is designed to compute an approximation of the following oscillatory integral:

$$I(x) = \int_0^T f(t) e^{-ixt}$$

where f is a slowly varying function with real or complex values.

Considering a uniform grid $t_n = n dt$, $\forall n = 0, N$ and an interpolation space on this grid, say $\text{vect}(w_n)_{n=0,N}$ where w_n are polynomial on each segment $[t_{n-1}, t_n]$; the Filon's method consists in interpolating the function f :

$$f(t) = \sum_{n=1,N} a_n w_n(t).$$

Substituting f by its interpolation in integral and collecting terms in a particular way, the integral $I(x)$ is thus approximated as follows:

$$I_N(x) = dt \sum_{j=1,p} C_j(x) \sum_{n=1,N} f(t_n^j) \exp^{-ixt_{n-1}} + dt^2 \sum_{j=1,p} C'_j(x) \sum_{n=1,N} f'(t_n^j) \exp^{-ixt_{n-1}}$$

where $C_j(x)$ and C'_j are coefficients of the form $\int_0^1 \tau_j(s) \exp^{-ixs} ds$ with τ_j some shape functions on the segment $[0, 1]$ and t_n^j the support of the j^{th} DoF on the segment $[t_{n-1}, t_n]$. The second sum in I_N appears only when using Hermite interpolation; for Lagrange interpolation, $C'_j(x) = 0$.

The `FilonIM` class provides mainly two constructors that pre-compute the values of f and f' , a function that computes the integral at x (may be a complex value). In constructors the `ord_` corresponds to the interpolation used: 0 for Lagrange P0, 1 for Lagrange P1 and 2 for Hermite P3, `f` and `df` (if Hermite Filon is used) are some standard C++ functions of a real argument:

```
FilonIM(number_t ord, T(f)(Real), real_t tf, number_t N)
FilonIM(number_t ord, T(f)(Real), T(df)(real_t), real_t tf, number_t N);
Complex compute(S& x) const; //compute I(x)
Complex operator()(S& x) const //compute I(x)
void print(ostream& os) const; //print FilonIM on stream
};
```

This class is quite easy to use, for instance to compute the integral

$$I(x) = \int_0^{10} e^{-t} e^{-ixt}$$

by the P1-Filon method, define first a C++ function returning the value of f as a `Complex`, create a `FilonIM` object with your own parameters and finally call it passing an x value:

```
Complex f(Real x) {return Complex(exp(-x),0.);}
\dots
FilonIM fim(0, f, 10, 100);
Complex y = fim(0.5);
```

To invoke Hermite P3 Filon method, define also the derivative of f :

```
Complex f(Real x) {return Complex(exp(-x),0.);}
Complex df(Real x) {return Complex(-exp(-x),0.);}
\dots
FilonIM fim(2, f, df, 10, 100);
Complex y = fim(0.5);
```



The P0 Filon method is of order 1, the P1 Filon is of order 2 while the Hermite P3 Filon is of order 4. The Hermite P3 Filon is less stable than the Lagrange Filon methods!

By default, `FilonIM` class is designed for complex value functions. In fact, this class is an alias of a template class that supports also real value functions. To explicitly use the real version of `FilonIM` class, you have to instantiate a `FilonIMT<Real>` object and pass to it some real value functions!

7.2.9 Define bilinear form involving unknowns on different meshes

It is possible to deal with a single integral involving unknowns on different meshes. Consider the following XLIFFE++ example:

```
Rectangle rect(_xmin = -1, _xmax = 1, _ymin = -1, _ymax = 1, _hsteps=0.1, _domain_name = "Omega");
Mesh meshR(rect, _triangle);
Segment seg(_v1 = Point(-2./3, 1./3), _v2=Point(2./3, 1./3), _hsteps=0.1, _domain_name = "Gamma");
Mesh meshS(seg, _segment);
Domain omega=meshR.domain("Omega");
Domain gamma=meshS.domain("Gamma");
Space V(_domain=omega, _interpolation=P1, _name="V");
Unknown u(V, "u"); TestFunction v(u, "v");
Space S(_domain=gamma, _interpolation=P0, _name="S");
Unknown p(S, "p"); TestFunction q(p, "qv");
BilinearForm a=intg(gamma, u*q);
```

The test function q is consistent with the domain γ because q belongs to the FE space S defined from γ but u is not because γ is not related to the space V . Nevertheless, XLIFFE++ can deal with by constructing a "fictitious" domain (named γ_F) made of elements of ω intersecting γ .

It works also with two domains of same dimension:

```
Rectangle rect(_xmin = -1, _xmax = 1, _ymin = -1, _ymax = 1, _hsteps=0.1, _domain_name = "Omega");
Mesh meshR(rect, _triangle);
Rectangle rect_i(_xmin = -0.5, _xmax = 0.5, _ymin = -0.5, _ymax = 0.5, _hsteps=0.1, _domain_name = "Omega_i");
Mesh meshRi(rect_i, _triangle);
Domain omega=meshR.domain("Omega");
Space V(_domain=omega, _interpolation=P1, _name="V");
Unknown u(V, "u"); TestFunction v(u, "v");
Domain omegai=meshRi.domain("Omega_i");
Space Vi(_domain=omegai, _interpolation=P1, _name="Vi");
Unknown ui(Vi, "ui"); TestFunction vi(ui, "vi");
BilinearForm ai=intg(omegai, u*vi);
```

7.2.10 Dealing with non-standard bilinear form - advanced usage -

In some cases, the bilinear form you want to deal with, cannot be expressed using standard operators of XLI++ or involved operations that are not yet available in XLI++. This section explains how to use the `UserBilinearForm` class that handles bilinear form managing particular function doing the computation of elementary matrices. For such bilinear form, the matrix computation algorithms bypass the quadrature machinery used classically and call the function attached to `UserBilinearForm` object.

First, a function computing the elementary matrices have to be defined. It has the following prototype:

```
void blfFun(BlfDataComputation& blfd)
{ ... }
```

where the `BlfDataComputation` class handles some information related to the elements concerned by the elementary matrix computation:

```
class BlfDataComputation
{public :
    const Element* elt_u , *elt_v;    // never null pointer (FEM)
    const Element* elt_u2,*elt_v2;    // may be 0
    const GeomElement* sidelt;        // may be 0 (DG case)
    RealMatrix*      matel;           // real elementary matrix
    ComplexMatrix*  cmatel;          // complex elementary matrix
}
```

`elt_u`, `elt_v` are pointers to some finite elements. They may be different if unknown space and test function space are different or if it is a BEM bilinear form (double integral). `elt_u2`, `elt_v2` are pointers to other finite elements when more are involved. This is the case of discontinuous Galerkin computation on a side element (`sidelt`) shared by `elt_u` and `elt_u2`. From `elt` you have access to the underlying `GeomElement` object that handles the `GeomMapData` giving access to the geometric map from reference element to actual geometric element; in particular the jacobian matrix, the inverse of jacobian matrix, the differential element can be extracted from this object. The following simple example shows how to compute the elementary matrix related to $\nabla u \cdot \nabla v$ when using 2D P1 finite element:

```
void blfGradGrad(BlfDataComputation& blfd)
{ if (blfd.matel==0) blfd.matel=new RealMatrix(1,1); // allocate if not yet allocated
  const Element* elt=blfd.elt_u;
  if (elt==0) return; //no computation
  GeomMapData& md = *elt->geomElt_p->meshElement()->geomMapData_p; //access to geometric map
  Real dx=0.5*md.differentialElement;
  RealMatrix& invJ=md.inverseJacobianMatrix;
  RealMatrix C=dx*invJ*tran(invJ);
  RealMatrix G(2,3,0.);
  G(1,1)=1;G(2,2)=1;G(1,3)=-1;G(2,3)=-1; // gradient of 2D-P1 reference shape functions
  *blfd.matel=tran(G)*C*G;
}
```

Because of explicit usage of pointers and references, be careful ! Other information can be extracted from element, see the developer documentation related to the `Element` class.

Once the function computing the elementary matrix is given, the user bilinear form can be defined:

```
Mesh ms(Rectangle(_xmin=0.,_xmax=1.,_ymin=0.,_ymax=1.,_nnodes=10,_domain_name="Omega"),
        _triangle, 1,_structured,_alternateSplit);
Domain omega=ms.domain("Omega");
Space V(omega, Lagrange, 1, "H");
Unknown u(V, "u"); TestFunction v(u, "v");
bool invJ=true, nor=false;
BilinearForm ublf=userBlf(omega,u,v,blfGradGrad,_FEComputation,_symmetric, invJ, nor);
```

The bilinear form is constructed using the `userBlf` function indicating

- the geometric domain concerned (may be two domains if a double integral),
- the unknown and test function involved,
- the function computing elementary matrices,
- the type of computation : `_FEComputation`, `_IEComputation`, `_DGComputation`,
- a symmetry property : `_noSymmetry`, `_symmetric`, ... ,
- a boolean telling if the inverse of jacobian must be computed and a boolean telling if the normal vector must be computed.

The user bilinear form can be used as other bilinear forms. For instance to compute the related matrix associated to:

```
BilinearForm ublf=userBlf(omega,u,v,blfGradGrad,_FEComputation,_symmetric, invJ, nor);
TermMatrix K(ublf,"K");
```

Note that the matrix K related to the user bilinear form `ublf` is the same as that obtained using the standard bilinear form `intg(omega,grad(u)|grad(v))`.

7.3 Essential conditions

Essential conditions are conditions that appear in spaces involved in variational problem. The most common one is the Dirichlet condition on a boundary : $u = 0$ on Γ (homogeneous) or $u = g$ on Γ (non-homogeneous). But there are others : transmission condition on a boundary, periodic condition between two boundaries, null average on a domain, ... **XLIFE++** provides a symbolic description of such conditions based on operator's stuff already described.

The general syntax of an essential condition is the following

$$(a1 \otimes op1(u1))|D1 +/- (a2 \otimes op2(u2))|D2 = f$$

where

- $a1, a2$ are some constants
- $\otimes$ is any algebraic operator ($*$, $|$, $\%$, $\wedge$)
- $op1, op2$ are some operators on unknown
- $u1, u2$ are some unknowns
- $D1, D2$ are some domains
- f is a constant or a function

Some classic scalar expressions are :

$u D = 0$	homogeneous Dirichlet condition
$u D = f$	non-homogeneous Dirichlet condition
$u1 D - u2 D = 0$	homogeneous transmission condition
$u D1 - u D2 = 0$	homogeneous periodic condition
$u D1 - g * u D2 = 0$	quasi periodic condition (g function)

Obviously, syntax supports more than conditions that the program can really deal with !



As the operator priority rules are the C++ rules, omitted parenthesis may induce some hazardous compilation errors. In doubt, use parenthesis.

To declare essential condition, users have to instantiate `EssentialConditions` object, which handles a set of conditions:

```
Strings sn("y=0", "y=1", "x=0", "x=1");
Mesh mesh2d(Square(_origin=Point(0.,0.), _length=1, _nnodes=10, _side_names=sn), _triangle, 1,
_structured);
Domain omega=mesh2d.domain("Omega");
Domain sigmaM=mesh2d.domain("x=0");
Domain sigmaP=mesh2d.domain("x=1");
Space V(_domain=omega, _interpolation=P1, _name="V");
Unknown u(V, "u");
EssentialConditions ecs = (u|sigmaM = 1);
```

or using a function:

```
Real un(const Point& P, Parameters& pa = defaultParameters)
{
    return 1.;
}

EssentialConditions ecs = (u|sigmaM = un);
```

To concatenate conditions, use the operator & :

```
EssentialConditions ecs = (u|sigmaM = 1) & (u|sigmaP = 1) ;
```

It is possible to mix conditions. Here is a case with two unknowns related by a transmission condition:

```
\ldots
Domain sigmaM=mesh2d.domain("x=0");
Domain sigmaP=mesh2d.domain("x=1");
Domain gamma=mesh2d.domain("x=1/2- or x=1/2+");
Space VM(_domain=omegaM, _interpolation=P2, _name="VM");
Unknown uM(VM, "u-");
Space VP(_domain=omegaP, _interpolation=P2, _name="VP");
Unknown uP(VP, "u+");
EssentialConditions ecs = (uM|sigmaM = 1) & (uP|sigmaP = 1)
& ((uM|gamma) - (uP|gamma) = 0);
```

To deal with periodic condition, the map related to the two domains involved is required:

```
Vector<Real> mapPM(const Point& P, Parameters& pa = defaultParameters)
{
    Point Q(P);
    Q(1) -= 1;
    return Q;
}
\ldots
Domain omega=mesh2d.domain("Omega");
Domain sigmaM=mesh2d.domain("x=0");
Domain sigmaP=mesh2d.domain("x=1");
Domain gammaM=mesh2d.domain("y=0");
Domain gammaP=mesh2d.domain("y=1");
Space V(_domain=omega, _interpolation=P1, _name="V");
Unknown u(V, "u");

defineMap(sigmaP, sigmaM, mapPM);
EssentialConditions ecs = (u|gammaM = 0) & (u|gammaP = 0)
& ((u|sigmaP) - (u|sigmaM) = 0);
```



XLiFE++ uses a very powerful process to deal with essential condition: all constraints are merged in a unique linear constraints' system which is reduced using a QR algorithm. This process is able to detect redundant or conflicting constraints. When some are redundant, they are deleted. When some are in conflict, they are also deleted but the right-hand side related components are averaged. For instance, this occurs when two Dirichlet conditions are not compatible at the intersection of two boundaries. In both cases a warning message is handled. It is the responsibility of user to check possible conflict. The QR algorithm stops whenever the pivot (max of modulus of coefficients of a matrix column) is below a tolerance set by default to $100\epsilon_{mach} \approx 2.10^{-14}$ in double precision. It may happen that this tolerance factor to be too small, it can be changed:

```
EssentialConditions ecs = ...;
ecs.redundancyTolerance(1.e-10);
```



Contrary to the mathematical point of view, in XLiFE++ the essential conditions are NOT attached to spaces but to algebraic representation of bilinear forms (see next section). This choice avoids defining multiple spaces.

Advanced usage

Most of essential conditions (except moment condition) are expressed as punctual relations. More precisely, the symbolic expression $op(u)|_D$ is translated as

$$op(u)(M_i) = \sum_j u_j op(w_j)(M_i), \text{ for some points } M_i \in D.$$

When using a Lagrange approximation, points M_i are simply the support of the Lagrange DoFs belonging to the domain D . When non Lagrange element are concerned, virtual point supports, often defined in the reference element, are used. If there is no virtual point support, mesh nodes of the domain are used.

Using points that are shared by two elements (vertices for instance) may cause some troubles when operator or approximation involved is not continuous across element. To bypass this difficulty, it is possible to use internal points of elements instead of boundary points by modifying the property `ecMethod` of the essential condition:

```
EssentialCondition ec = (ncross(u) | gamma = 0);
ec.ecMethod = _internalNodeEC;
EssentialConditions ecs = ec;
```

Be cautious, do not confuse `EssentialCondition` dealing with one condition and `EssentialConditions` dealing with several conditions.

Using internal nodes generates more punctual relations than using DoF points, but the reduction process deals with very well.

8

Solving the problem

Now, from the previous symbolic representation, we go to the algebraic representation of the problem, that is to say the representation of the problem in terms of matrices and vectors.

8.1 Algebraic representation

The algebraic representation consists in representation in terms of vectors and matrices of linear and bilinear forms, say :

$$L_i = l(\tau_i) \text{ and } A_{ij} = a(w_j, \tau_i)$$

where $(w_j)_{j=1,n}$ and $(\tau_i)_{i=1,m}$ are respectively the basis of finite space V (unknown space) and W (test function space).

XLiFE++ provides two fundamental classes to deal with such vectors and matrices:

- **TermVector** class which handles vector and space stuff (linear form, unknowns, DoF numbering, ...)
- **TermMatrix** class which handles matrix and spaces stuff (bilinear form, unknowns, DoF numbering, ...)

These two classes support either single unknown or multiple unknowns representation. Multiple unknowns vector or matrix are represented by single unknown blocks:

$$L = \begin{bmatrix} L_{v_1} \\ L_{v_2} \\ \dots \end{bmatrix} \text{ and } A = \begin{bmatrix} A_{v_1 u_1} & A_{v_1 u_2} \\ A_{v_2 u_1} & A_{v_2 u_2} \\ \dots & \dots \end{bmatrix}$$

where u_1, u_2 stands for unknowns and v_1, v_2 stands for test functions.



Unknowns correspond to matrix columns and test functions to matrix rows!

8.1.1 Representing linear and bilinear forms

The algebraic representation of a linear form or a bilinear form is simply done by specifying forms in **TermVector** or **TermMatrix**:

```
Mesh mesh2d(Square(_origin=Point(0.,0.), _length=1, _nnodes=20), _triangle, 1, _structured);
Domain omega=mesh2d.domain("Omega");
Space V(_domain=omega, _interpolation=P1, _name="V");
Unknown u(V, "u");
TestFunction v(u, "v");

LinearForm fv=intg(omega, f*v);
TermVector F(fv, "F");

BilinearForm auv=intg(omega, grad(u) | grad(v));
TermMatrix A(auv, "A");
```

Naming them using a string is more convenient for printing purpose.

For multiple unknowns forms, the syntax is the same:

```
Domain omega1=mesh2d.domain("Omega1"); Domain omega2=mesh2d.domain("Omega2");
Space V1(_domain=omega1, _interpolation=P1, _name="V1"), V2(_domain=omega2, _interpolation=P1,
    _name="V2");
Unknown u1(V1, "u1"); Unknown u2(V2, "u2");
TestFunction v1(u1, "v1"); TestFunction v2(u2, "v2");

LinearForm fv = intg(omega1, f*v1) + intg(omega2, f*v2);
TermVector F(fv, "F");

BilinearForm auv=intg(omega1, grad(u1)|grad(v1))+intg(omega2, grad(u2)|grad(v2));
TermMatrix A(auv, "A");
```

As previously mentioned, essential conditions are not attached, neither to space nor to bilinear form, but directly to `TermMatrix`. You have to specify them when you construct a `TermMatrix` from bilinear form:

```
BilinearForm auv=intg(omega, grad(u)|grad(v));
EssentialConditions ecs= (u|sigmaM = 1) & (u|sigmaP = 1);
TermMatrix A(auv, ecs, "A");
```



Essential conditions are never attached to a `TermVector`! When solving a system involving essential conditions, the `TermVector` representing the right-hand side of the system is automatically corrected to take into account essential conditions effects.

When defined, `TermVector` and `TermMatrix` are automatically computed, except if the option `_notCompute` is set in definition of `TermMatrix` or `TermVector`.



The computation algorithms find the minimal representation of matrices. It means that the size of matrix is equal to the number of unknown DoFs (and test function DoFs) involved in the computation. For instance, a mass matrix on a boundary involve only DoFs supported by the boundary.



The value type of matrix (real or complex) is managed by `TermMatrix` and `TermVector`. The user has not to deal with that, except in an advanced usage.

Definition of `TermMatrix` or `TermVector` supports some optional arguments to be inserted in any order before the optional name argument:

$$\text{TermMatrix}(bf, [ecs_u, [ecs_v, [option, [option, \dots, [name]]]])$$

where *bf* is the bilinear form, *ecs_u* and *ecs_v* possible essential conditions, and *option* any of

- **_compute**, **_notCompute** : to manage the automatic computation of the `TermMatrix`
- **_assembled**, **_unassembled** : to manage the automatic assembling of the matrix; not assembled implies not computed
- **_nonSymmetricMatrix**, **_symmetricMatrix**, **_selfAdjointMatrix**, **_skewSymmetricMatrix**, **_skewAdjointMatrix** : to enforce symmetry property when bilinear form has such symmetry and XLIFF++ has not detected it.
- **_csRowStorage**, **_csColStorage**, **_csDualStorage**, **_csSymStorage**, **_denseRowStorage**, **_denseColStorage**, **_denseDualStorage**, **_skylineSymStorage**, **_skylineDualStorage** : to enforce the storage if the default one chosen by XLIFF++ is not well suited

- `_pseudoReductionMethod`, `_realReductionMethod`, `_penalizationReductionMethod` : to indicate the method to deal with essential condition.

8.1.2 Dealing with essential conditions

Up to now, only pseudo reduction method is available for any essential condition and penalization method for Dirichlet condition. If necessary, it is possible to change the diagonal coefficient (by default 1) of the pseudo eliminated block matrix by invoking the `ReductionMethod` object:

```
BilinearForm auv=intg(omega, grad(u) | grad(v));
EssentialConditions ecs= (u|sigmaM = 0);
TermMatrix A(auv, ecs, ReductionMethod(_pseudoReduction, 10.), "A");
```

To use the penalization method, change the method in the `ReductionMethod` object:

```
BilinearForm auv=intg(omega, grad(u) | grad(v));
EssentialConditions ecs= (u|sigmaM = 0);
TermMatrix A(auv, ecs, ReductionMethod(_penalizationReduction, 10000.), "A");
```

The penalization method adds α to the diagonal coefficients related to DoFs where the Dirichlet conditions act.

Dealing with eigen problems

When dealing with eigen problems be very cautious when there are some essential conditions. Up to now, only the pseudo-reduction method is available to take into account some essential conditions. Just recall that essential conditions are expressed in terms of a linear constraints' system which is reduced to a minimal form using a QR factorization, say

$$U_e = g_e + C * U_r$$

where e stands for n_e eliminated DoFs, r for n_r reduced DoFs and $\mathbb{M}$ is an $n_e \times n_r$ matrix.

The pseudo-reduction of a matrix, say $\mathbb{A}$, consists in using the previous constraints' system for all rows corresponding to reduced DoFs and replacing rows corresponding to eliminated DoFs by the constraints' system, possibly scaled by a factor α . After reduction, the matrix formally looks like

$$\begin{bmatrix} \alpha \mathbb{I} & \alpha \mathbb{C} \\ 0 & \mathbb{A}_{rr} \end{bmatrix}$$

When $\mathbb{C}$ is a null matrix (Dirichlet condition for instance), the eigen vectors are well computed but may be spoiled by the artificial part added to recover constraints. For instance, if the smallest eigen values are required, you can shift these artificial eigen values by choosing the scale factor α large enough:

```
BilinearForm auv=intg(omega, grad(u) | grad(v));
BilinearForm uv=intg(omega, u*v);
EssentialConditions ecs= (u|Gamma=0);
TermMatrix A(auv, ecs, ReductionMethod(_pseudoReduction, 1000.));
TermMatrix M(uv, ecs); // not scaled !
EigenElements eigs(A, M, _nev=10, "SM");
```

When $\mathbb{C}$ is not a null matrix (case of transmission or periodic condition for instance), the previous reduction is no longer working. Another scaling parameter (β) is available in the `ReductionMethod` object. It corresponds to the following generalized scaling :

$$\begin{bmatrix} (\alpha + \beta) \mathbb{I} & \alpha \mathbb{C} \\ 0 & \mathbb{A}_{rr} \end{bmatrix}.$$

Now choosing $\alpha = 0$, the matrix will be reduced to a correct matrix for searching eigen values

$$\begin{bmatrix} \beta \mathbb{I} & 0 \\ 0 & \mathbb{A}_{rr} \end{bmatrix}.$$

```

BilinearForm auv=intg(omega, grad(u) | grad(v));
BilinearForm uv=intg(omega, u*v);
EssentialConditions ecs = (u|Gamma) -(u|Sigma)=0;
TermMatrix A(auv, ecs, ReductionMethod(_pseudoReduction, 0., 1000.));
TermMatrix M(uv, ecs, ReductionMethod(_pseudoReduction, 0., 1));
EigenElements eigs(A, M, _nev=10, "SM");

```

Although the eigen system has been "reduced" by "eliminating" some DoFs, the eigen vectors well satisfy the essential conditions because the `applyEssentialConditions` function has been automatically called to recover the essential conditions.

8.1.3 Delay computation

If you choose to declare the `TermMatrix` with the `_notCompute` option, its computation may be done later using the `compute` command:

```

BilinearForm auv=intg(omega, grad(u) | grad(v));
TermMatrix A(auv, _notCompute, "A");
...
compute(A);

```

`TermMatrix` and `TermVector` manages some additional parameters and a lot of facilities are provided. Let us go to details.

8.1.4 TermVector in details

`TermVector` represents either a linear form on discrete space or any element of space as vector of components on the space basis.

It has a default constructor and one from linear form with options:

```

TermVector(name);
TermVector(LinearForm, opt1, opt2, opt3, name);

```

`opt1`, `opt2`, `opt3`, `name` are optional arguments:

```

Reals f(const Point& P, Parameters& pa = defaultParameters)
{return Reals(2, -1.);}
...
Strings sn(4, "");
...
Mesh mesh2d(Square(_origin=Point(0.,0.), _length=1, _nnodes=4, _side_names=sn),
             _triangle, 1, _structured);
Domain omega=mesh2d.domain("Omega");
Space V(_domain=omega, _interpolation=P1, _name="V");
Unknown u(V, "u", 2); TestFunction v(u, "v");
LinearForm fv=intg(omega, f | v);

TermVector B(fv, "B");

```

It may be useful to `project` a `\class{TermVector}` defined on a `space $V_1$` and a `domain $\Omega_1$` on an other `space $V_2$` and an `'other' domain $\Omega_2$`. It can be an `interpolation` process when spaces are based on Lagrange `elements`:

$$u^1 = \sum_i U_1(i) w_i^1 \rightarrow u^2 = \sum_i U_1(i) w_i^2$$

In the previous example, the `TermVector B` is derived from a linear form defined on a vector test function.

The constructors of `TermVector` from linear forms compute automatically the algebraic representation except if the option `_notCompute` is specified. In that case, the `TermVector` object may be computed later using the `compute` function:

```
Reals f(const Point& P, Parameters& pa = defaultParameters)
{return Reals(2, -1.);}
...
Strings sn(4, "");
Mesh mesh2d(Square(_origin=Point(0.,0.), _length=1, _nnodes=4,
_side_names=sn), _triangle, 1, _structured);
Domain omega=mesh2d.domain("Omega");
Space V(_domain=omega, _interpolation=P1, _name="V");
Unknown u(V, "u", 2);
TestFunction v(u, "v");
LinearForm fv=intg(omega, f|v);
TermVector B(fv, _notCompute, "B"); //do not compute B
...
compute(B); //now compute B
```



If a `TermVector` object is already computed, the `compute` function does not re-compute it! If you want to re-compute it, you have to change its computation status :

```
B.computed()=false;
```

A `TermVector` may be constructed from values of a function f on a geometric domain. It is available only for FE Lagrange unknown: the vector is built with components $f(M_i)$ for any node M_i in the domain:

```
TermVector(Unknown, GeomDomain, T, String name)
```

The `T` argument may be a function (C++ function, `Function` object or `SymbolicFunction` object) or a constant value:

```
Reals f(const Point& P, Parameters& pa = defaultParameters)
{return P;}
...
Space V(_domain=omega, _interpolation=P1, _name="V");
Unknown u(V, "u", 2); // vector unknown
TermVector B(u, omega, f, "B"); // from C++ function
Unknown v(V, "v"); // scalar unknown
TermVector F(v, omega, x_1*x_2, "F"); // from SymbolicFunction
TermVector G(v, omega, 1., "G"); // from constant
```

For non Lagrange interpolation, there exists an extended `TermVector` constructor from a function f and its derivative functions if required that is

$$\pi f = \sum_i d_i(f) w_i$$

where $(d_i)_i$ are the degrees of freedom (viewed as distributions) and $(w_i)_i$ the related shape functions. It works as follows :

```
Real fx(const Point& P, Parameters& pa = defaultParameters) {return P(1);}
Vector<Real> gx(const Point& P, Parameters& pa = defaultParameters)
{return {Vector<Real> g(2,0.); g(1)=1.; return g;}}
Vector<Real> g2x(const Point& P, Parameters& pa = defaultParameters)
{return {Vector<Real> g(3,0.);}}
...
TermVector ux(u, omega, Function(fx), Function()); //order 0 DoFs
TermVector vx(u, omega, Function(fx), Function(gx)); //order 0/1 DoFs involved
TermVector wx(u, omega, Function(fx), Function(gx), Function(hx)); //order 0/1/2 DoFs involved
```

Passing first order derivatives of f , say $(\partial_x f, \partial_y f, [\partial_z f])$ as a vector is mandatory for interpolation involving DoF with first order derivatives (e.g. Morley element) and passing second order derivatives of f , say $(\partial_{xx} f, \partial_{yy} f, \partial_{xy} f, [\partial_{zz} f, \partial_{xz} f, \partial_{yz} f])$ as a vector is only mandatory for interpolation involving DoF with second order derivatives (e.g. Argyris element). For a Lagrange interpolation, this constructor produces the same `TermVector` as the constructor `TermVector F(v, omega, Function(fx))`. It is also working for vector unknowns; in that case derivatives must be given as a unique vector collecting all the derivatives for each component $(\partial_x f_1, \partial_y f_1, [\partial_z f_1], \partial_x f_2, \partial_y f_2, [\partial_z f_2], \dots)$.



Do not confuse the "nodal" `TermVector` constructor ($f(M_i)$) with the "DoF" `TermVector` constructor ($d_i(f)$) that coincide in case of Lagrange DoFs. In case of non Lagrange DoFs, use the "DoF" `TermVector` constructor without omitting the derivative function, even a void one if it is not required! For instance, for Nedelec elements :

```
Vector<Real> fE(const Point& P, Parameters& pa = defaultParameters) {return P;}
...
Space V(_domain=omega, _interpolation=NE1_1, _name="V", _notOptimizeNumbering); // Nedelec space
Unknown e(V, "e");
TermVector ex(e, omega, Function(fE), Function());
```

There are also a copy constructor and a constructor assigning a constant value from another `TermVector`:

```
TermVector(TermVector, name);
template <typename T> TermVector(TermVector, T, name);
```

`TermVector` can be constructed from one or two `TermVector` by applying a C++ function or a symbolic function. C++ function has to be of the following forms:

```
Real fun(const Real& x1);
Real fun(const Real& x1, const Real& x2);
Complex fun(const Complex& x1);
Complex fun(const Complex& x1, const Complex& x2);
```

For instance, to build a new `TermVector` that is the square of another one:

```
Real fsq(const Real& x1) {return x1*x1;}
...
TermVector F(intg(omega, u*v));
TermVector F2(F, fsq); // from C++ function
TermVector F2(F, x_1^2); // from symbolic function
```

Finally, by using algebraic operators $+$ $-$ $*$ $/$ $^$ and standard mathematical function `abs`, `real`, `imag`, `complex`, `sqrt`, `squared`, `sin`, `cos`, `tan`, `sinh`, `cosh`, `tanh`, `exp`, `log`, `log10`, ... on `TermVector`'s, new `TermVector` may also be constructed:

```
TermVector F(intg(omega, u*v));
TermVector G = sqrt(F) + abs(F);
```



It is possible to mix single unknown scalar `TermVector` and single unknown vector `TermVector` in some operations but only one single unknown vector `TermVector` is allowed. In that case, the result is a single unknown vector `TermVector` where the operation has been performed on each component of the input single unknown vector `TermVector`. For instance if X is a single unknown scalar `TermVector` and Y a single unknown vector `TermVector`, you can do

```
TermVector Z= X*X*Y;
```

but not

```
TermVector Z= X*Y*Y;
```

When many `TermVector`'s are involved, they have to be of the same size!

Concatenate some scalar `TermVector`'s into a one vector `TermVector` is also possible by using the following construction process:

```
Space V(_domain=omega, _interpolation=P1, _name="V"); //P1 Lagrange space
Unknown u(V, "V"); //scalar unknown
TermVector V1(u, omega, 1.); //a scalar TermVector (1,1,...)
TermVector V2(u, omega, 2.); //another scalar TermVector (2,2,...)
Unknown u2(V, "V", 2); //vector unknown
TermVector W(u2, V1, V2); //vector TermVector ([1,2],[1,2],...)
```

This process works only for single unknown `TermVector`.

In case of a multiple unknowns vector, an unknown block may be extracted as follows:

```
Space V(_domain=omega, _interpolation=P1, _name="V"), H(_domain=omega, _interpolation=P0,
_name="V");
Unknown u(V, "u", 2), p(W, "p");
LinearForm fv=intg(omega, f|u)+intg(omega, p);
TermVector B(fv);
TermVector B_u=B(u); //extract u part
```

Unknown is used as index and the returned `TermVector` is a copy of the extracted block.

It is possible to do algebraic operations (`+=`, `-=`, `*=`, `/=`, `+`, `-`, `*`, `/`) on `TermVector`:

```
Space V(_domain=omega, _interpolation=P1, _name="V");
Unknown u(V, "u");
LinearForm fvo=intg(omega, f*u);
LinearForm fsv=intg(sigma, g*u);
TermVector Bo(fvo, "Bo");
TermVector Bs(fvs, "Bs");
TermVector B=2*Bo+3*Bs;
```



If `TermVector`'s have not been computed, the operations have no effect!



In order to be more efficient, the linear combination of `TermVector`'s is delayed up to the assign (`=`) operation or a constructor operation. It means that some expression may not be evaluated and produce warning/error message related to `LcTerm` class.

```
TermVector W=U+V; // Ok
theCout << U+V; // NOT EVALUATED
```

Besides, it is possible to convert `TermVector`:

```

Space V(_domain=omega, _interpolation=P1, _name="V");
Unknown u(V, "u");
LinearForm fv=intg(omega, f*u);
TermVector B(fv, "B");

B.toAbs();
B.toReal();
B.toImag();
B.toComplex();

```

Be cautious, once it is converted it is not possible to go back.

In some circumstances, it may be useful to restrict a `TermVector` to a smaller domain. Use the member function `onDomain` or the operator `|`:

```

Space V(_domain=omega, _interpolation=P1, _name="V"); Unknown u(V, "u");
TermVector B(u, omega, x_1); // TermVector on omega
TermVector Bg = B.onDomain(gamma); // TermVector on gamma, boundary of omega
TermVector Bg = B|gamma; // same

```

At contrary, a `TermVector` may be extended to a larger domain along the following formula:

$$f|_{\Omega}(M) = f|_{\Gamma}(g(M)) * h(M)$$

where g is a map from Ω to Γ and h a function specifying how to do the extension ($h = 1$ means a constant extension). There are mainly two user's functions:

```

TermVector extension(const TermVector& f, const Function& g, const GeomDomain& dom, const
Unknown& u); //constant extension
TermVector extension(const TermVector& f, const Function& g, const GeomDomain& dom, const
Unknown& u, const Function& h);

```

The next example shows how to do, for instance, a radial extension :

```

Real fcos(const Point& P, Parameters& pa = defaultParameters)
{ return cos(2*atan2(P(2), P(1))); }
Vector<Real> g(const Point& P, Parameters& pa = defaultParameters)
{ Real r=norm(P);
  if(r==0.) return P;
  return P/r; }
Complex e(const Point& P, Parameters& pa = defaultParameters)
{ Real r=norm(P);
  if(r==0.) return 0.;
  return exp(i_*pi_*(r-1))/r; }
...
Point A(1.,0.,0.), B(2.,0.,0.), C(0.,2.,0.), D(0.,1.,0.), O(0.,0.,0.);
Segment s1(_v1=A, _v2=B, _hsteps=0.1), s2(_v1=C, _v2=D, _hsteps=0.1);
CircArc c1(_center=O, _v1=D, _v2=A, _hsteps=0.1, _domain_name="gamma"),
c2(_center=O, _v1=B, _v2=C, _hsteps=0.1);
Geometry cour=surfaceFrom(s1+c2+s2+c1, _domain_name="omega");
Mesh meshc(cour, _triangle, 1, _gmsh, "quarter of crown");
Domain omega=meshc.domain("omega"), sigma=meshc.domain("sigma");
Space V(omega, P1, "V"); Unknown u(V, "u");
TermVector f(u, sigma, fcos, "tv");
TermVector extf=extension(f, Function(m), omega, d, Function(e));
saveToFile("extf", extf);

```




Figure 8.1: Radial extension

Note that it is also possible to extend analytical function :

```
TermVector extension(const Function& f, const Function& g, const GeomDomain& dom, const Unknown& u);
TermVector extension(const Function& f, const Function& g, const GeomDomain& dom, const Unknown&
u, const Function& h);
```



Up to now, the unknown u must be related to a Lagrange interpolation space.

The merging of two `\class{TermVector}` living on different `domains` of a same `mesh` is also available :

```
\begin{lstlisting}
TermVector B1(u, omega1, x_1); // TermVector on omega1
TermVector B2(u, omega2, x_1); // TermVector on omega2
TermVector B=merge(B1, B2); // merging
```



On DoFs shared by the two domains, the merged value is those of the first domain. This behavior is different from the addition of two `TermVector` living on different domains where the value of shared DoFs is the sum of the values.

Inner/hermitian product and standard norms are provided:

```
Complex innerProduct(TermVector, TermVector);
Complex hermitianProduct(TermVector, TermVector);
Complex operator|(TermVector, TermVector);

Real norm(TermVector, Number l=2);
Real norm1(TermVector);
Real norm2(TermVector);
Real norminfy(TermVector);
```

Notice that inner and hermitian product return always a complex even if vectors are real!

Some general information may be retrieved, using the following member functions:

```
TV.valueType() // value type (_real or _complex)
TV.size() // size counted in scalar
TV.nbDofs() // size counted in DoFs
```

```
TV.nbDofs(u) // number of DoFs related to unknown u
```

Some member functions give useful access to part of a **TermVector** object:

```
TermVector U=TV(u); // access to u part as a TermVector
Reals V; TV.asVector(V); // reinterpret TermVector as a raw Vector
TermVector W=TV.onDomain(Sigma); // restrict to domain Sigma
W=TV|Sigma; // restrict to domain Sigma
Value val=TV.getValue(u, n); // access to n-th component of unknown u (n>=1)
TV.setValue(u,n,3.); // set value of n-th component of unknown u
TV.setValue(Sigma,0.); // set to 0 the values on Sigma
Value val=TV.evaluate(u, P); // evaluate at point P
Real v;
TV(P,v); // evaluate at point P
TV(u,P,v); // evaluate at point P, specifying unknown
```

Finally, a **TermVector** may be printed or saved into a file:

```
LinearForm fv=intg(omega, f*u);
TermVector B(fv, "B");

theCout << "vector B " << B;
B.print(cout);
saveToFile("file.dat",B,_vtk);
```

In this example, B is saved to a file in vtk format (format of paraview software). Other available formats are `_vtu` (PARAVIEW XMK format) and `_raw` (only values are saved);

Summary of main **TermVector** operations

A function marked $\diamond$ means that its usage is restricted to single unknown **TermVector**.

Constructors	
TermVector(LinearForm[, EssentialCondition][, option][, option]...[, name])	→ TermVector
TermVector(Unknown, Domain, value[, name]) $\diamond$	→ TermVector
TermVector(Unknown, Domain, Function[, name])	→ TermVector
TermVector(Unknown, Domain, Function, Function [,Function][, name])	→ TermVector
TermVector(Unknown, Domain, SymbolicFunction[, name]) $\diamond$	→ TermVector
TermVector(Unknown, Domain, VariableName[, name]) $\diamond$	→ TermVector
TermVector(TermVector, value[, name]) $\diamond$	→ TermVector
TermVector(TermVector[, TermVector], Function[, name]) $\diamond$	→ TermVector
TermVector(TermVector[, TermVector], SymbolicFunction[, name]) $\diamond$	→ TermVector
TermVector(Unknown, TermVector[, TermVector][, name]) $\diamond$	→ TermVector

Accessors	
TermVector.name()	→ String
TermVector.valueType()	→ ValueType
TermVector.size() counted in scalar	→ Number
TermVector.nbDoFs() counted in DoFs	→ Number
TermVector.numberOfUnknowns()	→ Number
TermVector.asRealVector() $\diamond$	→ RealVector
TermVector.asComplexVector() $\diamond$	→ ComplexVector
TermVector.Dof(Unknown, number)	→ Dof
TermVector(Unknown)	→ TermVector

Modifiers	
TermVector.compute()	
TermVector.toAbs()/ toReal()/ toImag()/ toComplex()	→ TermVector
TermVector.setUnknown(Unknown) $\diamond$	

Operations	
[scalar][*]TermVector[+-][scalar][*]TermVector...	→ TermVector
TermVector*TermVector component product ◊	→ TermVector
TermVector/TermVector component division ◊	→ TermVector
TermVector^p component exponent ◊	→ TermVector
abs/real/imag (TermVector)	→ TermVector
sqrt/squared (TermVector) ◊	→ TermVector
sin/cos/tan/sinh/cosh/tanh (TermVector) ◊	→ TermVector
asin/acos/atan/asinh/acosh/atanh (TermVector) ◊	→ TermVector
exp/log/log10 (TermVector) ◊	→ TermVector
norm/norm1/norm2/norminf (TermVector)	→ Real
innerProduct/hermitianProduct(TermVector,TermVector)	→ Complex
TermVector TermVector	→ Complex

Value management	
TermVector.getValue(Unknown, number)	→ Value
TermVector.setValue(Unknown, number, val)	
TermVector.setValue(number, val) ◊	
TermVector.setValue(Unknown, Domain, T)	
TermVector.setValue(Domain, T) ◊	
TermVector.setValue(Unknown, Domain, Function)	
TermVector.setValue(Domain, Function) ◊	
TermVector.setValue(Unknown, Domain, TermVector)	
TermVector.setValue(Domain, TermVector) ◊	
TermVector.evaluate(Unknown, Point)	→ Value
TermVector.evaluate(Point) ◊	→ Value
TermVector(Unknown, Point, T)	→ T
TermVector(Point, T) ◊	→ T

Domain operations	
TermVector.mapTo(GeomDomain, Unknown, [errOutDom])	→ TermVector
merge(TermVector, TermVector)	→ TermVector
TermVector Domain	→ TermVector
normalsOn(GeomDomain, Unknown)	→ TermVector
setColor(GeomDomain, TermVector, ColoringRule)	

Output
ostream << TermVector
TermVector.print([ostream])
saveToFile(FileName, TermVector, [termVector], [IOFormat], [withDomains])
plot(TermVector, [IOFormat])

8.1.5 TermMatrix in details

TermMatrix is the algebraic representation of a bilinear form, say a matrix. It supports different types of storage and possibly, has to take into account essential conditions. So there are different constructors of **TermMatrix** from bilinear forms:

```
//no essential condition
TermMatrix(BilinearForm, opt1, opt2, opt3, name);
//same essential condition on unknown and test function
TermMatrix(BilinearForm, EssentialConditions, opt1, opt2, opt3, name);
//different essential conditions on unknown and test function
TermMatrix(BilinearForm, EssentialConditions, EssentialConditions, opt1, opt2, opt3, name);
```

opt1, opt2, opt3 are any options picked in the list

- **_compute**, **_notCompute**, **_assembled**, **_unassembled**

- `_nonSymmetricMatrix`, `_symmetricMatrix`, `_selfAdjointMatrix`, `_skewSymmetricMatrix`, `_skewAdjointMatrix`
- `_csRowStorage`, `_csColStorage`, `_csDualStorage`, `_csSymStorage`, `_denseRowStorage`, `_denseColStorage`, `_denseDualStorage`, `_skylineSymStorage`, `_skylineDualStorage`
- **`_pseudoReductionMethod`**, `_realReductionMethod`, `_penalizationReductionMethod`

and `name` is an optional string used for printing purpose.

Some examples of `TermMatrix` construction:

```
Strings sidenames("y=0", "y=1", "x=0", "x=1");
Square sq(_origin=Point(0.,0.), _length=1, _nnodes=20, _side_names=sidenames);
Mesh mesh2d(sq, _triangle, 1, _structured);
Domain omega=mesh2d.domain("Omega"), gamma=mesh2d.domain("x=0");
Space V(_domain=omega, _interpolation=P1, _name="V");
Unknown u(V, "u"); TestFunction v(u, "v");
BilinearForm auv=intg(omega, grad(u) | grad(v)), muv=intg(omega, u*v);

TermMatrix A(auv); //simplest constructor
EssentialConditions ecs= (u|gamma = 0);
TermMatrix A0(auv, ecs, "A0"); //with ess. condition and naming
TermMatrix M(muv, _notCompute); //defined but not computed
```

The computation algorithm chooses the well adapted matrix storage, generally compressed sparse storage or dense storage, taking into account symmetry property of the matrix. Using option, the storage method may be imposed at construction :

```
BilinearForm auv=intg(omega, grad(u) | grad(v));
TermMatrix A(auv, ecs, _skylineSymStorage, "A");
```

The available matrix storage are:

- the compressed sparse storage `_cs`, generally the best one in terms of memory size
- the skyline storage `_skyline`, required by direct solvers
- the dense storage `_dense`

Each of these storages has different internal storages (say access) : `_row`, `_col`, `_dual`, `_sym`.



The storage may be changed after computation by using the `setStorage` function. Be cautious, some storage conversions may be time expensive.

It is also possible to construct void matrix, copy of matrix, diagonal matrix from `TermVector` or standard vector and matrix of the form $G(M_i, P_j)$ where G is a kernel and M_i and P_j belongs to some geometrical domains:

```
TermMatrix(name);
TermMatrix(TermMatrix, name);
TermMatrix(TermVector, name);
TermMatrix(Unknown, Domain, Vector<T>, name);
TermMatrix(Unknown, Domain, Unknown, Domain, OperatorOnKernel, name);
```

For particular purpose, construction of `TermMatrix` from a real/complex scalar `Matrix` is available:

```
RealMatrix H(10, _hilbertMatrix); //standard matrix
TermMatrix A(H, "Hilb_10"); //converted to a TermMatrix
```

Note that the `TermMatrix` involves abstract unknowns named `#u_n` and `#v_m` where `m`, `n` is the size of the matrix. It is also possible to specify `Unknown/TestFunction` when building a `TermMatrix` from a `Matrix` or a `std::vector` and matrix dimensions:

```
TermMatrix A(u,v,H, "Hilb_10"); //converted to a TermMatrix with unknowns (u,v)
```

Matrix dimensions must be consistent with the dimensions of the unknown spaces!

In case of multiple unknowns bilinear form, block matrix may be extracted using unknowns as index:

```
BilinearForm auv=intg(omega1,grad(u1)|grad(v1))+intg(omega2,grad(u2)|grad(v2));
TermMatrix A(auv);
TermMatrix A11=A(u1,v1);
```

The **TermMatrix** result is a copy of the extracted block!

Users can print the matrix and its storage, and save it to file in dense (`_dense`) or coordinate format (`_coo`). The coordinate format (`i,j,val`) is well adapted to export sparse matrix to Matlab.

```
BilinearForm auv=intg(omega1,grad(u1)|grad(v1))+intg(omega2,grad(u2)|grad(v2));
TermMatrix A(auv, "A");

verboseLevel(30);
A.print(out);
out<<A;
A.viewStorage(out);
A.saveToFile("matA.dat",_coo);
```

As matrices are memory consuming, it is possible at any time to deallocate the memory allocated by a matrix:

```
BilinearForm auv=intg(omega,grad(u)|grad(v));
BilinearForm muv=intg(omega,u*v);
TermMatrix A(auv, "A"), M(muv, "M");
...
clear(A,M);
```

Only memory used to store matrix values is deallocated. It means that **clear** has no effect on a matrix that has not been computed!

TermMatrixs may be combined using standard algebraic operators (`+=`, `-=`, `*=`, `/=`, `+`, `-`, `*`, `/`)

```
BilinearForm kuv=intg(omega,grad(u)|grad(v)),
             muv=intg(omega,u*v),
             mguv=intg(sigma,u*v);
TermMatrix K(kuv, "A"),
             M(muv, "M"),
             Mg(mguv, "Mg");

M*=3;
K+=M;
TermMatrix A=K-3*M+Mg;
```

The sum (resp. the difference) of **TermMatrix**s involves a complex algorithm : sum is done by unknown blocks (nothing is done with a void block) and for each block, the common DoFs numbering is searched, then the sum is performed. This process may induce the construction of a new matrix storage. When combining more than two matrices, it is better to write the summation in one step rather than in several steps.

Summing **TermMatrix**s is equivalent to sum bilinear forms in a new one and compute it :

```
BilinearForm auv=kuv-3*muv+mguv;
TermMatrix A(auv, "A");
```

Regarding memory consuming and time performance, this method is better.

Product of **TermMatrix** and **TermVector** are provided using the `*` operator:

```

TermMatrix A(auv, "A");
TermVector L(luv, "L");
TermVector AL=A*L;

```

Matrix and vector must have compatible unknowns, but some may be omitted (void blocks are ignored).



When test function is used to construct matrix and vector, this compatibility rule in product **TermMatrix** $\times$ **TermVector** implies that the matrix column unknowns should be the same as vector unknowns. This rule may be too boring. It is the reason why a permissive behavior is allowed : **TermVector** unknowns may be the dual unknowns of test functions, in other words the matrix row unknowns. It requires that test functions are declared as dual of unknowns !

To conclude this section we give the example of the Helmholtz problem in waveguide using Dirichlet to Neuman map as transparent boundary condition. This example illustrates multiple uses of algebraic operators on **TermMatrix**.

```

//define spectral space to deal with DtN
Number N=10;
Space Sp(_domain=sigmaP, _basis=Function(cosny, params), _dim=N, _name="cos(n*pi*y)");
Unknown phiP(Sp, "phiP");
Complexes lambda(N);
for (Number n=0; n<N; n++) lambda[n]=sqrt(Complex(k*k-n*n*pi*pi/(h*h)));
//define TermMatrix with no DtN
BilinearForm auv=intg(omega, grad(u) | grad(v)) - k*k*intg(omega, u*v);
TermMatrix A(auv, _csDualStorage, "A");
//construct DtN TermMatrix using matrix product
BilinearForm euv=intg(sigmaP, phiP*v),
               fuv=intg(sigmaP, u*phiP);
TermMatrix E(euv, "E"), F(fuv, "F");
TermMatrix L(phiP, sigmaP, lambda, "L"); //diagonal matrix
TermMatrix ELF=E*L*F;
TermMatrix A2=A-i*ELF;

```

This DtN approach using product of matrices was the MELINA approach. In XLIFE++ it is better to use **TensorKernel** approach :

```

Number N=10;
Space Sp(_domain=sigmaP, _basis=Function(cosny, params), _dim=N, _name="cos(n*pi*y)");
Unknown phiP(Sp, "phiP");
Complexes lambda(N);
for (Number n=0; n<N; n++) lambda[n]=sqrt(Complex(k*k-n*n*pi*pi/(h*h)));
TensorKernel tkp(phiP, lambda);
BilinearForm auv = intg(omega, grad(u) | grad(v)) - k*k*intg(omega, u*v)
                 - i*intg(sigmaP, sigmaP, u*tkp*v);
TermMatrix A(auv, "A");

```

Advanced usage

- When computing eigen values of a **TermMatrix** with essential conditions that have been reduced using the pseudo reduction method, you may be annoyed by spurious eigen values corresponding to the residual diagonal block. These eigen values may be shifted by modifying the diagonal coefficient of this residual block:

```

EssentialConditions ecs = (u|sigma=0);
TermMatrix A(auv, ecs, ReductionMethod(_pseudoReduction, 100.) "A"); //shift by 100

```

- It may be useful to access to one particular coefficient of the **TermMatrix** and change it. For computed **TermMatrix** that has not moved to its global representation, matrix coefficient can be accessed from either

its row and column numbers or its row and column DoFs. If the `TermMatrix` is a multiple unknowns matrix, a pair of unknowns has to be specified. Let us give a simple example with single unknown `TermMatrix`:

```
Space V(_domain=omega, _interpolation=P1, _name="V"); Unknown u(V, "u"); TestFunction v(u, "v");
TermMatrix M(intg(omega, u*v));
Real m11 = M.getValue(1,1).asReal(); //get M_11 as a real
M.setValue(1,1,0.); //set M_11 to 0
M.setRow(1,2,0.); //set row 1 and row 2 to 0
```



Be care, the type of the given value has to be consistent with the type of the matrix coefficients !

- As the row or column numbers of the matrix are related to the DoFs order of space or subspace, the matrix coefficients can also be accessed using explicit DoFs. In the following example where `omega` is assumed to be the square unit, the DoF nearest the point (0.5,0.5) is located and then used to access to the matrix coefficient:

```
Space V(_domain=omega, _interpolation=P1, _name="V"); Unknown u(V, "u"); TestFunction v(u, "v");
TermMatrix M(intg(omega, u*v));
Dof d = V.locateDof(Point(0.5,0.5));
Real mdd = M.getValue(d,d).asReal(); //get M_dd as a real
```

- Once `TermMatrix` is computed, unknowns/testfunctions may be changed as long as the new unknowns/testfunctions are defined on the space of the original unknowns/testfunctions. Indeed, numbering and matrix coefficients are NOT recomputed.

```
Space V(_domain=omega, _interpolation=P1, _name="V");
Unknown u(V, "u"); TestFunction v(u, "v");
Unknown p(V, "p"); TestFunction q(p, "q");
TermMatrix M(intg(omega, u*v));
M.changeUnknown(p); // u->p
M.changeTestFunction(q); // v->q
M.changeUnknowns(p,q); // u->p, v->q
```

There also exists a general `changeUnknowns` function that addresses multiple unknowns/testfunctions `TermMatrix`, $(u1, u2, \dots) \rightarrow (p1, p2, \dots), (v1, v2, \dots) \rightarrow (q1, q2, \dots)$:

```
A.changeUnknowns(Unknowns(u1,u2,...), Unknowns(v1, v2, ...), Unknowns(p1,p2,...), Unknowns(q1,q2,...));
```

8.1.6 HMatrix

In the context of integral equation, HMatrix method consists in using a hierarchical representation (tree) of the BEM matrix, each tree node being either a real submatrix (leaf) or a virtual submatrix addressing up to four nodes :





Figure 8.2: Hierarchical matrix

Then some sub-matrices may be "compressed" to save memory and time computation. The matrix may be not squared and therefore the sub-matrices too.

The hierarchical structure of Hmatrix is based on clusters of row indices or column indices (in FE context, clusters of DoFs supported by mesh domains):



Cluster of points

Clustering of triangles using centroids

When building the tree structure of the HMatrix by a recursive division algorithm that travels the row and column clusters, some a priori geometrical rules are used to know if a sub-matrix will be compressed later, say **admissible** sub-matrix. When a sub-matrix is admissible, it is not divided. Up to now only the following boxes rule is available :

Admissibility rule

A sub-matrix is admissible if the bounding box B_r of the row cluster node and the bounding box B_c of the column cluster node satisfy:

$$\text{diam}(B_r) \leq 2\eta \text{dist}(B_r, B_c).$$

Default value of η is 1.

If a sub-matrix is admissible then it can be compressed using several methods. All the methods proposed try to get a low rank approximation of the original sub-matrix of the form:

$$UDV^*$$

where U is an $m \times r$ matrix, V is an $n \times r$ matrix and D is an $r \times r$ diagonal matrix. The rank of a such matrix is at most r . So it is a low rank representation of an $m \times n$ matrix if r is small compared to m, n .

The Singular Value Decomposition (SVD) gives an exact "approximation" of an $m \times n$ matrix. So, from the Eckart–Young–Mirsky theorem, approximate matrix of low rank can be produced by keeping a few largest singular values. Because, this approach requires a full SVD computation that is expansive, alternative methods are based on random SVD which consists in capturing the matrix range using only few gaussian random vectors and doing an SVD on a smaller matrix. Nevertheless, these approximate SVD methods still require the full computation of the matrix, so adaptative cross approximation (ACA) methods computing only some rows and columns of the matrix are faster but less robust.

The figure 8.3 shows an example of structure of a BEM HMatrix (2500×2500) computed by XLiFE++:




Figure 8.3: HMatrix with a sphere cluster, non-admissible blocks are in red

How to involve HMatrix computation ?

By default, XLiFE++ build BEM matrix in dense storage. To involve HMatrix storage (and computation) XLiFE++ uses a special integration method in the bilinearform describing the BEM term : the `HMatrixIM` object that can be handled as follows

```
HMatrixIM him(clmeth, minrow, mincol, hmapp, rank, im);
```

or

```
HMatrixIM him(clmeth, minrow, mincol, hmapp, eps, im);
```

where

- `clmeth`: the clustering method, one of `_regularBisection`, `_boundingBoxBisection`, `_cardinalityBisection`, `_uniformKdtree`, `_nonuniformKdtree`
- `minrow`, `mincol`: the minimum size of sub-matrix, more precisely a sub-matrix is divided if it is not admissible and if its number of rows/columns is greater than `minrow/mincol`
- `hmapp`: the approximate matrix methods, one of `_noHMAproximation`, `_svdCompression`, `_rsvdCompression`, `_r3svdCompression`, `_acaFull`, `_acaPartial`, `_acaPlus`
- `rank`: the desired rank of approximate matrix

- `eps`: the desired precision of approximated matrix
- `im`: an integration method for double integral

The figure 8.4 illustrates the difference between clustering bisection methods with a disk mesh of 1673 points and at most 10 points by box; different colors correspond to different tree node levels.




Figure 8.4: clustering of a disk mesh using regular (left), bounding box (middle), cardinality (right) bisection methods.

and the figure 8.5 shows the cluster get when using the kdtree (quadtree in 2D) methods with at most 5 nodes by box.




Figure 8.5: clustering of a disk mesh using kdtree methods - `_uniformKdtree` (left) and `_nonuniformKdtree`(right).

When specifying `_noHMApproximation` all the sub-matrices (admissible and not admissible) are computed and not compressed. There is no real advantage, except that the assembly appears to be faster than the standard assembly in dense matrix, in particular when multi-threading is enabled.

`_svdCompression` corresponds to some truncated svd either a rank truncature when rank is given or an eps truncature (keep all singular values greater than `eps`).

`_rsvdCompression` uses random svd methods that are faster than full svd methods. As svd methods, user can choose either a rank truncature or an eps truncature. `_r3svdCompression` is a more sophisticated random svd that does only eps truncature; do not choose `_r3svdCompression` with a rank parameter!

`_acaFull`, `_acaPartial`, `_acaPlus` are adaptative cross approximation methods that use some rows and columns of the matrix to build a low rank matrix. `_acaFull` method requires all the row and the columns of the matrix, so it gives good approximates, but it is not of a great interest compared to the random svd methods. `_acaPartial` and `_acaPlus` (an improvement of `_acaPartial`) are more interesting because they use only

several rows and columns of matrix, saving time computation of BEM coefficients. But they are less robust!

The following XLIFE++ gives some examples of how to compute BEM HMatrix:

```
//mesh sphere and define domain, space, unknown
Mesh meshd(Sphere(_center=Point(0.,0.,0.),_radius=1.,_nnodes=9,
    _domain_name="Omega"),_triangle,1,_subdiv);
Domain omega=meshd.domain("Omega");
Space W(_domain=omega,_interpolation=P0,_name="V",_notOptimizeNumbering);
Unknown u(W,"u"); TestFunction v(u,"v");
//define kKernel, integration method and HMatrix parameters
Kernel G=Laplace3dKernel();
SauterSchwabIM ssim(5,5,4,3,2.,4.);
HMatrixIM him(_cardinalityBisection, 20, 20,_acaplus,0.00001,ssim);
//compute single layer matrix
BilinearForm alf=intg(omega,omega,u*G*v,him);
TermMatrix A(alf,"A");
//compute double double layer matrix
BilinearForm blf=intg(omega,omega,u*ndotgrad_y(G)*v,him)-0.5*intg(omega,u*v);
TermMatrix B(blf,"B");
```

Note that when adding a sparse FE matrix and a HMatrix, the result is a HMatrix. This is only possible if integrals are supported by the same domain. Indeed, FE matrix addresses non-admissible blocks of the HMatrix. Be care when combining some matrices.



HMatrix integration method (**HMatrixIM**) is only available for double integral (BEM). Do not use with a single integral bilinearform!



When building **HMatrixIM** object passing clustering parameters, the row and column clusters will be computed when computing HMatrix, and referenced by your **HMatrixIM** object. As the row and column clusters are not re-computed if they have been built, do not re-use your **HMatrixIM** object in a bilinear form having another domain support than this you have first involved. If you want to re-use it on a different domain, call the **clear** method that frees the row and column cluster:

```
HMatrixIM him(_cardinalityBisection, 20, 20,_acaplus,0.00001,ssim);
BilinearForm alf=intg(omega,omega,u*G*v,him);
TermMatrix A(alf,"A"); //row and column clusters are built
him.clear(); //deallocates row and column clusters
```



HMatrix does not work yet for problems with vector unknown!

The figure 8.6 and 8.7 give an idea of the efficiency of the aca+ and r3svd methods compared to the computations done with a dense matrix.




Figure 8.6: assembly time for different HMatrix approximate methods

We note that the assembly computation time with Hmatrix and no approximation is better than the computation time get with dense matrix. Is due to a better parallelization of HMatrix assembly. The ACA+ methods is significantly faster than the other methods!




Figure 8.7: matrix/vector product time for different HMatrix approximate methods



HMatrix supports the matrix/vector product, so it may be used with iterative methods, but it is not supported by direct linear solvers !

8.1.7 Projector

Sometimes, it may be useful to project an element of one FE space, say V to another FE space, say W . XLiFE++ deals with projection based on a bilinear form, say $a(.,.)$, defined on both projection spaces. The projection

$w \in W$ of $v \in V$ is the solution of

$$a(w, \tilde{w}) = a(v, \tilde{w}) \quad \forall \tilde{w} \in W.$$

Let $(w_i)_{i=1,n}$ a basis of W and $(v_i)_{i=1,m}$ a basis of V , the above problem is equivalent to the matrix problem:

$$\mathbb{A} W = \mathbb{B} V$$

where $\mathbb{A}_{ij} = a(w_j, w_i)$, $\mathbb{B}_{ij} = a(v_j, w_i)$, $v = \sum_{i=1,m} V_i v_i$ and $w = \sum_{i=1,n} W_i w_i$. The bilinear form should be symmetric and positive on the space W in order to the matrix $\mathbb{A}$ be invertible. The most simple example is the L^2 projection related to the bilinear form:

$$a(w, \tilde{w}) = \int_{\Omega} w \tilde{w} d\Omega.$$

Projection operations are related to the `Projector` class. Let us see how to construct such `Projector` object :

```
Mesh mesh2d(Rectangle(_xmin=0,_xmax=1,_ymin=0,_ymax=1,_nnodes=6,
                     _side_names="Gamma"), _triangle,1,_structured);
Domain omega=mesh2d.domain("Omega"), gamma = mesh2d.domain("Gamma");
// create some spaces
Space V1(_domain=omega, _interpolation=P1, _name="V1", _notOptimizeNumbering);
Unknown u1(V1,"u1"); TestFunction v1(u1,"v1");
Space V2(_domain=omega, _interpolation=P2, _name="V2", _notOptimizeNumbering);
Unknown u2(V2,"u2");
Space N1(_domain=omega, _interpolation=NE1_1, _name="N1", _notOptimizeNumbering);
Unknown n1(N1,"n1"); // Nedelec FE
// create some L2 projectors
Projector P2toP1(V2,V1,_L2Projector,"P2toP1");
Projector N1toP1(N1,1,V1,2,_L2Projector,"N1toP1");
```

Note the particular construction of the N1 to $V1 \times V1$ projector. Because the space $V1 \times V1$ does not exist, you have to give the size of the vector unknowns (1 for N1, 2 for P1) related to spaces.

The projector types available are `_L2Projector`, `_H1Projector`, `_H10Projector` associated respectively to the L^2 , H^1 and H_0^1 inner product. Be cautious, H^1 and H_0^1 projectors are not consistent with some FE spaces (e.g. P0)! It is also possible to use your own bilinear form :

```
BilinearForm myblf=intg(gamma,u1*v1)+intg(omega,u1*v1);
Projector P1toP2(V1,V2,myblf,"P1toP2");
```

It may happen that you want to restrict your projection to a subdomain:

```
Projector P2toP1_Gamma(V2,V2,gamma,_L2Projector,"P2toP1_Gamma");
```

When a `Projector` is constructed, the matrix $\mathbb{A}$ and $\mathbb{B}$ are computed and the matrix $\mathbb{A}$ is factorized. So you can compute the projection of some `TermVector`'s:

```
TermVector B2(u2,omega,fx2,"B2"); // fx2 user function
TermVector B1=P2toP1(B2,u1);
```

By specifying the unknown `u1` as second argument, the result `B1` will have `u1` as unknown. It is also possible to omit the unknown argument or to pass the `TermVector` result as argument:

```
TermVector B1=P2toP1(B2);
TermVector B1b;
P2toP1(B2,B1b);
```

When no unknown is given, XLI++ will choose the first unknown that has been defined on result space.

You can also compute some standard projections without managing in an explicit way a `Projector` object:

```
TermVector B1=projection(B2,V1);
```

In that case the `Projector` object is constructed in the back and kept in memory.



You can only project a single unknown `TermVector`. If your `TermVector` has multiple unknowns, extract the part related to the unknown of interest before projection.

Sometimes, it may be interesting to build the matrix $\mathbb{A}^{-1}\mathbb{B}$:

```
TermMatrix P21 = P2toP1.asTermMatrix(u2,u1,"P21");
```

To save memory, the original matrices $\mathbb{A}$ and $\mathbb{B}$ are destroyed. Be careful, the matrix $\mathbb{A}^{-1}\mathbb{B}$ is a dense matrix (column dense storage), so it may waste a lot of memory.

Finally, as almost objects of XLIFE++, you can print a `Projector`

```
P2toP1.print(cout);
cout<<P2toP1;
```

Interpolation versus projection

When involved spaces are Lagrange spaces, an interpolation process may be used to 'project' a `TermVector` U^1 defined on a space V^1 and a domain Ω^1 on an other space V^2 and an 'other' domain Ω^2 :

$$U_i^2 = \sum_j U_j^1 w_j^1(f(M_i^2))$$

with f a mapping from Ω^2 to Ω^1 . Obviously, $f(\Omega^2)$ should intersect Ω^1 !

To realize such operations, XLIFE++ offers the `TermVector::mapTo` function or its external form:

```
TermVector TermVector::mapTo(Domain dom2, Unknown& u2, bool useNearest=false,
                             bool errorOnOutDom=true, Function* fmap=0,
                             Real tol=theLocateToleranceFactor); // default = 0.1
TermVector mapTo(TermVector& tv1, Domain dom2, Unknown& u2, bool useNearest=false,
                bool errorOnOutDom=true, Function* fmap=0,
                Real tol=theLocateToleranceFactor);
```

where the unknown $u2$ handles the space $V2$. $fmap=0$ means $f = Id$. This function uses an interpolation process requiring the localization of elements in Ω_{mega1} including Ω_{mega2} nodes. In fact, this localization process can work in two ways:

- considering a true inclusion ($useNearest=false$) with two possible behaviors when inclusion fails: stop on error if $errorOnOutDom=true$ else returns a 0 value.
- considering an approximated inclusion ($useNearest=true$): if node M_i^2 is not included in any element of Ω^1 , the nearest element E_k^1 in Ω^1 is searched and the projection $Q_i^k = \Pi_{E_k^1} M_i^2$ is computed. If $|Q_i^k - M_i^2| \leq \tau |E_k^1|$ (τ the locate tolerance factor) then Q_i^k is used to compute the V^1 interpolation. If the projection Q_i^k is too far, regarding the $errorOnOutDom$ status, the program stops on error or returns a 0 value.

Few situations may be considered:

- $\Omega^1 = \Omega^2$ on a same mesh but $V^1 \neq V^2$, in that case $f = Id$. This case is involved when dealing with two different Lagrange interpolations on a same domain.
- $\Omega^1 = \Omega^2$ but defined on different meshes (mandatory $V^1 \neq V^2$), in that case $f = Id$. For instance, this case is involved when you want to build some convergence curves versus the mesh size! The next figure illustrates the mapping of a `TermVector` from a P2 approximation on a P2 mesh to a P1 approximation on a P1 mesh. Note that some P2 nodes are outside the P1 mesh and, as a consequence, the process involves a projection.




Figure 8.8: Mapping TermVector P1 to P2 (P1 mesh in black and P2 mesh in red)

- $\Omega^1 = f(\Omega^2)$. This case is very useful to transport a `TermVector` from a domain to an other one even the meshes do not match.

The following XLIFE++ program shows various ways to map a `TermVector`:

```
//P2 Lagrange approximation on P2 mesh of a disk, h = 0.1
Disk disk_ref(_center = Point(0., 0.), _radius = 1., _hsteps = 0.1, _domain_name = "Omega");
Mesh mesh_ref(disk_ref, _triangle, 2, _gmsh);
Domain Omega_ref = mesh_ref.domain("Omega");
Space V_ref(_domain = Omega_ref, _interpolation = P2, _name = "V_ref");
Unknown u_ref(V_ref, "u_ref"); TestFunction v_ref(u_ref, "v_ref");

//P2 Lagrange approximation on P1 mesh of a disk, h=0.2
Disk disk(_center = Point(0., 0.), _radius = 1., _hsteps = 0.2, _domain_name = "Omega",
_side_names = "Gamma");
Mesh mesh(disk, _triangle, 2, _gmsh);
Domain Omega = mesh.domain("Omega");
Space V(_domain = Omega, _interpolation = P2, _name = "V");
Unknown u(V, "u"); TestFunction v(u, "v");
BilinearForm auv = intg(Omega, grad(u) | grad(v));
LinearForm lv = intg(Omega, v);
EssentialCondition ecs = (u | Gamma = 0);
TermMatrix A(auv, ecs, "A");
TermVector F(lv, "F");
TermVector U = directSolve(A, F);
Parameters pars; pars << Parameter(&U, "U");

// various ways to map U to Uref
TermVector Uref_m=U.mapTo(Omega_ref,u_ref,true, false,0); // using mapTo function
TermVector Uref_i(u_ref, Omega_ref, Function(eval, pars)); // using evaluate
defineMap(Omega_ref,Omega,Function(Idmap),true);
TermVector Uref_p=projection(U,V_ref); // using projection

// external functions
Real eval(const Point &P, Parameters &pa = defaultParameters)
{ const TermVector &U = *reinterpret_cast<const TermVector*>(pa("U").get_p());
  return U.evaluate(P,true,false).asReal();}
Vector<real_t> Idmap(const Point &P, Parameters &pa = defaultParameters)
{ return P;}
```

8.2 Linear Solvers

After a problem is well-defined in the form of `Term`: `TermMatrix` and `Vector`, it can be easily solved with a direct solver or with an iterative solver. XLIFE++ provides a wide set of linear equation solvers. The following

section explains some simple steps to make use of these solvers.

8.2.1 Direct solvers

Because direct solvers involve some complicated algorithms to solve very large linear systems through LDLt or LU factorization, a prerequisite to call them is to have `TermMatrix` factorized. It can be done like below:

```
TermMatrix LD; // Create a new TermMatrix to store factorized result
ldltFactorize(A, LD); // LDLt-Factorize the TermMatrix
```

Then the linear system is solved with a very simple code

```
TermVector X = factSolve(LD, B);
```

The `TermVector` U is returned as a solution of the solver. Or a `TermMatrix` can be factorized into LU before being solved

```
TermMatrix LD; // Create a new TermMatrix to store factorized result
luFactorize(A, LD); // LU-Factorize the TermMatrix
TermVector X = factSolve(LD, B);
```

Factorization and solving may be called in one time:

```
TermVector X = luSolve(LD, B);
```

The available factorizations and direct solvers are

- LDLt factorization and solver (for symmetric matrix): functions `ldltFactorize`, `ldltSolve`
- LDLstar factorization and solver (for self-adjoint matrix): functions `ldtstarFactorize`, `ldlstarSolve`
- LU factorization and solver (for any matrix): functions `luFactorize`, `luSolve`
- umfpack factorization and solver (for any matrix) if umfpack is installed and configured: `umfpackFactorize`, `umfpackSolve`
- Gauss elimination with pivoting for matrix stored in dense format: `gaussSolve`
- Schur method on 2x2 `TermMatrix`: `schurSolve`
- lapack solver for matrix stored in dense format if lapack is installed and configured: `lapackSolve`
- magma solver for matrix stored in dense format if magma lib is available: `magmaSolve`

LDLt, LDLstar and LU move matrix to skyline storage and may fail even if the matrix is invertible (no pivoting strategy)! Umfpack is most powerful because it works with compressed sparse storage and has pivoting strategy.

Be sure of symmetry property of your matrix before calling LDLt or LDLstar methods. If you are not, call generic direct solver `directSolve` which performs tests before calling the well adapted method:

```
TermMatrix Af; // create a new TermMatrix to store factorized result
factorize(A, Af); // factorize the TermMatrix
TermVector X = factSolve(Af, B); //solve factorized linear system

TermVector X = directSolve(A, B); //same in one call
```

The behavior of `directSolve` is the following:

- if matrix is dense : use lapack solver if available else use XLIFFE++ gauss solver
- if matrix is sparse (compressed or skyline) use umfpack if available else use XLIFFE++ factorization method

Note that direct solver may induce storage conversion so the `TermMatrix` storage may be modified. if you want not, specify `true` as last argument of solver functions:

```
TermVector X = directSolve(A, B, true); //keep original matrix
```

The right-hand side is never modified.



UMFPACK solver is always faster than XLIFE++ solvers but lapack solver may be slower than the XLIFE++ gauss solver if non optimized lapack-blas libraries are used.

Most solvers support multiple right-hand sides given as a `TermVectors` or a `std::vector<TermVector>`:

```
TermVectors Bs;
\dots
TermVectors Xs = directSolve(A, Bs);
```

The `factSolve` and `directSolve` functions can also be used with a `TermMatrix` right-hand side, say $\mathbb{B}$. Thus, they produce a `TermMatrix` which is $\mathbb{A}^{-1}\mathbb{B}$. Even both the matrices $\mathbb{A}$ and $\mathbb{B}$ are sparse matrix, the matrix $\mathbb{A}^{-1}\mathbb{B}$ is not sparse. It is stored using a column dense storage.

```
TermMatrix invM1M2=directSolve(M1,M2,_keep);
TermMatrix Id(M1,_idMatrix,"Id");
TermMatrix invM1=directSolve(M1,Id,_keep);
TermMatrix invM1=inverse(M1);
```

Note that `inverse(M1)` is strictly equivalent to `directSolve(M1, Id, _keep);`.



Up to now, the usage of `factSolve`, `directSolve` functions with a `TermMatrix` as right-hand side and `inverse` is restricted to single unknown `TermMatrix`.

8.2.2 Iterative solvers

Unlike direct solvers, the iterative ones are delivered with very simple interface. In contrast to direct solvers, iterative methods approach the solution gradually, rather than in one large computational step. Up to now, there are several built-in iterative solvers of XLIFE++:

- Conjugate Gradient (CG, CGS, BiCG, BiCGStab)
- Generalized Minimal RESidual (GMRes, Standard or Restarted)
- Quasi Minimal Residual (QMR)
- Successive Over Relaxation (SOR, SSOR)

These methods can be called with a preconditioner (SOR and SSOR excepted)

How to define a preconditioner ?

To define a preconditionner, use the class `PreconditionerTerm`:

```
TermMatrix A;
Real omega;
PreconditionerTerm precondition(A,_ssorPrec, omega);
```

The `PreconditionerTerm` constructor takes 3 arguments:

- The matrix used to build the precondition matrix.
- The type of preconditioner. Possible values are:

`_luPrec` the precondition matrix will be a LU precondition of the input matrix given
`_ldltPrec` the precondition matrix will be a LDLt precondition of the input matrix given
`_ldlstarPrec` the precondition matrix will be an LDL* precondition of the input matrix given
`_ssorPrec` the precondition matrix will be a SSOR precondition of the input matrix given
`_diagPrec` the precondition matrix will be a diagonal precondition of the input matrix given
`_embeddedPrec` the precondition matrix will be the input matrix given, with no transform

Its default value is `_embeddedPrec`

- the relaxation parameter when SSOR precondition. It is optional, and its default value is 1.0

How to call an iterative solver ?

To invoke an iterative solver and make use of it, the easiest way is to call external functions:

```
TermVector U = iterativeSolve(A, B, _solver=_cg); // Solve with default initial guess X0=0
```

The available solvers (through their keys to the `_solver` parameter) are: `_bicg`, `_bicgstab`, `_cg`, `_cgs`, `_gmres` and `_qmr`.

There are shortcuts specific to each solver:

```
TermVector U = cgSolve(A, B);
```

The available functions are `bicgSolve`, `bicgstabSolve`, `cgSolve`, `cgsSolve`, `gmresSolve`, `qmrSolve`. They all call the general function `iterativeSolve`.

All these functions take parameters in the following orders:

1. the matrix A (`TermMatrix`)
2. the right-hand side B (`TermVector`)
3. optionally the initial guess X0 (`TermVector`)
4. optionally the preconditioner P (`PreconditionerTerm`)
5. optionally one or more key-value parameters, among the following:

`_solver` Only for routine `iterativeSolve`. This parameter is not optional.
`_tolerance` tolerance of the iterative solver. Default value is 1e-4 on 32 bits configurations, 1e-8 on 64 bits configurations.
`_maxIt` Maximum number of iterations. Default value is relative to the size of the linear system.
`_verbose` verbose level. Default value is 0.
`_name` the name of the `TermVector` solution computes by the routines. Default value is "U".
`_omega` Only for routines `sorSolve` and `ssorSolve`, the relaxation parameter.
`_krylovDim` Only for routine `gmresSolve`, the krylov dimension. Default value is the size of the linear system (for use of Standard GMRes). If it is set and lesser than the maximum number of iterations, it will be the Restarted GMRes.

An advanced use of solvers would be to instantiate an iterative solver object and call it using operator `()`:

```
CgSolver mySolver; // Define an iterative solver object
TermVector U = mySolver(A,B,X0); // Solve the system with initial guess X0
```

For iterative solver objects, you can use the same keys as seen previously (`_solver` excepted, as it is meaningless here).

```
CgSolver mySolver(_tolerance=1.e-04, _maxIt=20);
TermVector U = mySolver(A,B,X0); // Solve the linear problem
```

In the code above with double precision, the tolerance is made looser than default, for a faster solution with a convergence error being 10^{-4} . Nevertheless, the solver will cease after 20 iterations even if the solution has not been converged. It is a big disadvantage of the iterative solvers: they do not always “just work”. Different problems do require different iterative solver settings, depending on the nature of the governing equation being solved. However, the advantage of the iterative solvers is their memory usage, which is significantly less than a direct solver for the same sized problems. Look at the example “Helmholtz problem with CG solver” to know more how to write code with iterative solvers.

Advanced usage

The usage of iterative solvers presented above concerns `TermMatrix` and `TermVector` objects. This may be not adapted to some situations where the operators involved are not such objects or require some complex operations. In fact, iterative solvers are objects that support any kind of operator on vector and vector classes. The following example illustrates how to use the GMRES solver using your own operator class that implements a product of `TermMatrix`:

```
// operator class to deal with TermMatrix product
class myOperator
{
    const TermMatrix *A1_p, *A2_p; //pointers to TermMatrix
public:
    myOperator(const TermMatrix& A,const TermMatrix& B)
        : A1_p(&A), A2_p(&B) {}
};

void multMatrixVector(const myOperator& A,const TermVector& X,TermVector& R)
{R=(*A1_p) * () (*A2_p)*X);} //product A1*(A2*X)
\dots
//assume TermMatrix A1, A2 built and TermVector B built
myOperator A(A1,A2);
GmresSolver gmres; // Gmres solver object | more compact call
TermVector X=gmres(A,B); // | TermVector X=Gmres() (A,B);
```



Be cautious when dealing with large structures. In particular, use pointers or references to avoid unnecessary copy.

If you plan to use other matrix operator/vector classes, you will have to define additional stuff. The operator class, say `Mat`, must propose the following functions:

```
ValueType Mat::valueType() // returning type (real_t or complex_t)
void multMatrixVector(const Mat&,const Vec&,Vec&) // all solvers
void multVectorMatrix(const Vec&,const Mat&,Vec&) // for Bicg and Qmr solvers
// SOR requires also
void Mat::sorLowerMatrixVector(const Vec&,Vec&,Real) const; // [w*D + L] * x
void Mat::sorUpperMatrixVector(const Vec&,Vec&,Real) const; // [w*D + U] * x
// SSOR requires also
void Mat::sorDiagonalMatrixVector(const Vec&,Vec&,Real) const; // [w*D] * x
void Mat::sorLowerSolve(const Vec&,Vec&,Real) const; // [D/w + L] x = b
void Mat::sorUpperSolve(const Vec&,Vec&,Real) const; // [U/w + U] x = b
```

The `TermVector` and `Vector` classes of XLiFE++ may be used in iterative solvers without any additional stuff. However, if you want to deal with your own vector class, say `Vec`, the following functions have to be defined:

```
Vec::Vec(const Vec&) // copy constructor
Vec& Vec::operator*=(Real) // X*=a
Vec& Vec::operator*=(Complex) // X/=a
Vec& Vec::operator*=(Complex) // X*=a
Vec& Vec::operator*=(Real) // X/=a
Vec& Vec::operator+=(const Vec&) // X+=Y
Vec& Vec::operator-=(const Vec&) // X-=Y
```

```
Real Vec::norm2() // |X|2
Complex dotRC(const Vec&, const Vec&); // X.Y
Complex hermitianProduct(const Vec&, const Vec&); // X|Y = X.conj(Y)
```

Even if your class is related to real value vector, complex versions are required for compilation reasons, but they will not be used!

To use your own preconditioning class, say `Prec`, the minimal requirements are:

```
Prec::precondMatrix_p // pointer to an object of Mat class
Vec Prec::solver(Vec&) // solution of P*x = b
```

8.3 Eigen solvers

XLiFE++ currently provides a built-in solver which targets Hermitian and non-Hermitian eigenvalue problems, standard or generalized, and a wrapper to the well known external library ARPACK via its companion package ARPACK++. The internal solver is provided in case ARPACK is not available (see subsection 1.4.3) ; as far as possible, the latter should be preferred.

In the following, we will denote the problems using the generic form:

- $Ax = \lambda x$, for a *standard* eigenvalue problem,
- $Ax = \lambda Bx$, for a *generalized* eigenvalue problem.

The couple (λ, x) is called an eigen pair, and consists of an eigenvalue λ and the corresponding eigenvector x . The nature of the problem to be solved is determined by the matrix A : real or complex, symmetric or not, etc. Both solvers can be used in a rather uniform way, although some parameters may be specific to one package or the other. The calling sequence requires a few mandatory arguments ; some optional ones are provided by the user in the form “_key = value”.

In the following, we describe some features common to both solvers, targeting in particular the result object. Then the parameters governing the computation are described for the built-in solver, followed by those related to ARPACK, including a special *help paragraph* that is worth to be mentioned right now. At last, two special sections are devoted to post-computation information retrieving and an advanced usage of ARPACK.

8.3.1 How to call an eigen solver ?

Given two suitable `TermMatrix` objects A and B , corresponding to the mathematical operators A and B above, a few eigen elements can be computed as the result of one of the generic calling sequence:

```
EigenElements ees = eigenSolve(A); // standard eigenvalue problem
EigenElements eeg = eigenSolve(A, B); // generalized eigenvalue problem
```

In this example, 10 (the default number) eigen pairs are computed from the unique knowledge of the mandatory arguments A , or A and B ; the other parameters are left to their default values. The function `eigenSolve` automatically selects ARPACK if it is available, or the internal solver otherwise.

Remark.

The user may choose himself by adding the argument `_solver=_intern` or `_solver=_arpack`.

If they are present, the other parameters, given in the form “_key = value”, are checked and passed to the specific solver. Moreover, when ARPACK is used, some of them may be *modified* to benefit from experience feedback. Also, ARPACK requires the RHS matrix B to be hermitian to ensure the convergence of the computation. When this does not seem to be the case, the original generalized problem is automatically *transformed* into a standard problem. Whenever such a decision is made or a parameter is modified, an information message is printed on the terminal and in the main print file of XLiFE++.

The user has always direct access and full control over the parameters (which are *never modified in this case*) by using the specific functions: the function `eigenInternSolve` provides direct access to the built-in solver, while `arpackSolve` uses ARPACK. With these functions, the statements in the previous example would become:

```
// specific call to internal engine
EigenElements eesi = eigenInternSolve(A);    // standard eigenvalue problem
EigenElements eegi = eigenInternSolve(A, B); // generalized eigenvalue problem

// specific call to Arpack engine
EigenElements eesa = arpackSolve(A);        // standard eigenvalue problem
EigenElements eega = arpackSolve(A, B);     // generalized eigenvalue problem
```

8.3.2 Results

All these functions store their result in an `EigenElements` object that holds two containers:

- `values`, containing the list of the found eigenvalues,
- `vectors`, containing the list of the corresponding eigenvectors.

The eigenvectors are always computed together with the eigenvalues. Both containers have the same size which can be obtained with the member function `numberOfEigenValues`. The list `values` is in fact a vector of complex numbers (even if the problem is real symmetric), and `vectors` is a vector of `TermVector` objects. Given an `EigenElements` object `eeg`, these containers can be used directly by `eeg.values` and `eeg.vectors` with the standard C++ syntax; alternatively, some member functions are available to extract the eigen pairs using their number, starting at 1. Their names are simply `value` and `vector`. For example, the following code prints the computed eigenvalues stored in `eeg`, the real part and the imaginary part being separated with a white space if they are complex:

```
if (eeg.isReal()) // eigenvalues and eigenvectors are real
    for (int i=1; i <= eeg.numberOfEigenValues(); i++) {
        cout << eeg.value(i).real() << endl;
    }
else {
    // eigenvalues or eigenvectors may not be real
    for (int i=1; i <= eeg.numberOfEigenValues(); i++) {
        cout << eeg.value(i).real() << " " << eeg.value(i).imag() << endl;
    }
}
```

The type of the eigenvalues depends on the problem. It can be retrieved by the member function `isReal`, as shown above, which returns `true` if the problem is real symmetric, `false` otherwise.

The eigenvalues are always returned as complex numbers, even if the problem is real symmetric in which case the imaginary parts are set to 0. The eigenvectors are real if the problem is real symmetric, complex otherwise. By default, the eigenvalues are sorted by increasing module; the eigen pairs are internally stored according to this order. There are several sorting possibilities which can be specified by the `_sort` key (see below).

The eigenvectors can be easily used in the following of the program, since they are available as `TermVector` objects. They can also be saved individually into a file using one of the output format, in order to be plotted afterwards. The statement:

```
saveToFile("V1", eeg.vector(1), _vtk);
```

creates the file `V1_0mega.vtk`, whose name is build from the prefix given by the user and the name of the domain where the solution is computed; the suffix is automatically appended according to the output format (here `.vtk`).

Moreover, an `EigenElements` object can be saved in multiple files in a single statement:

```
saveToFile("EV", eeg, _vtk);
```

The names of all the created files will begin with the same prefix given as first argument (here EV). The eigenvalues will be written in the file EV_eigenvalues and the i^{th} eigenvector will be written in the file EV_i_DomainName.ext, where DomainName will be replaced with the domain name and the extension depend on the chosen format (here .vtk). The eigenvalues are printed in the file EV_eigenvalues from the first one to the last one according to the chosen sorting criterion ; the eigenvectors are printed in files whose numbers follow the same order.

8.3.3 Calling sequence

Let's recall that the functions `eigenSolve`, `eigenInternSolve` and `arnpackSolve` have two main calling sequences according to the kind of problem to define. The arguments can be:

- **A, _key1=value1, ... _keyN=valueN**, in the case of a *standard* eigenvalue problem,
- **A, B, _key1=value1, ... _keyN=valueN**, in the case of a *generalized* eigenvalue problem.

The arguments **A** and **B** are `TermMatrix` objects. The others (key, value) pairs are not mandatory. They are used to specify some particular settings. They can be given in any order and their list is given in the corresponding sections below.

Optional parameters for the built-in eigen solver in details

The built-in eigen solver accepts the following keys:

_nev (integer) number of eigen elements to be computed. The default value is 10.

_which (string) specifies which part of the spectrum is to be scanned. The default value is "LM", for largest magnitude. The other possible value is "SM", for smallest magnitude.

_sigma (real or complex) shift value σ used in the spectral transformation in order to scan a portion of the spectrum around σ .

_mode (enumeration) Two computational modes are implemented:

- The block Krylov-Schur method, based on Krylov decomposition with Rayleigh quotient ably reduced to Schur form, and suitable for hermitian and non hermitian eigenvalue problems. To call it, use the value `_krylovSchur`. This is the default.
- The block Davidson method, suited only for hermitian problems and sometimes faster than the block Krylov-Schur algorithm. To call it, use the value `_davidson`.

_tolerance (real) precision of the computation. The default value is 1e-6.

_maxIt (integer) maximum number of iterations. The default value is 10000.

_verbose (integer) verbosity level. The default value is the value used in the main frame.

_sort (enumeration) sort criterion. The default value is `_incr_module`, which means "by increasing module". One can also sort by increasing real part (`_incr_realpart`) and by increasing imaginary part (`_incr_imagpart`) ; conversely, one can sort by decreasing order by selecting one of `_decr_module`, `_decr_realpart` or `_decr_imagpart`.

Examples:

The following call computes the 20 eigenvalues of largest magnitude (and the corresponding eigenvectors) of a generalized eigenvalue problem using the block Davidson method:

```
Number nev = 20;
EigenElements ee = eigenInternSolve(A, B, _nev=nev, _which="LM", _mode=_davidson);
```

The following call computes `nev` eigenvalues around the complex shift value $2.5 + i$ (and the corresponding eigenvectors) of a generalized eigenvalue problem using the block Krylov-Schur method:

```
Complex sig = (2.5, 1.);
EigenElements ee = eigenInternSolve(A, B, _nev=nev, _sigma=sig);
```

Optional parameters for ARPACK solver in details

The ARPACK solver accepts the following keys:

_nev (integer) number of eigen elements to be computed. The default value is 10.

_which (string) specifies which part of the spectrum is to be scanned. The default value is "LM", for largest magnitude. The possible values are:

Value	Description
BE	eigenvalues from both ends of the spectrum
LA	eigenvalues with the largest algebraic value
SA	eigenvalues with the smallest algebraic value
LM	eigenvalues with the largest magnitude
SM	eigenvalues with the smallest magnitude
LR	eigenvalues with the largest real part
SR	eigenvalues with the smallest real part
LI	eigenvalues with the largest imaginary part
SI	eigenvalues with the smallest imaginary part

For symmetric problems, **_which** must set to be one of LA, SA, LM, SM or BE. For real nonsymmetric and complex problems, the alternatives are LM, SM, LR, SR, LI and SI.

_sigma (real or complex) shift value σ used in the spectral transformation in order to scan a portion of the spectrum around σ .

_mode (enumeration) when a shift is specified (thanks to **_sigma**), some additional computational modes are available. In order to activate one of them, one of the following keywords should be specified:

- **_buckling** or **_cayley** for the Buckling mode or the Cayley mode, for a generalized real symmetric problem,
- **_cshiftRe** or **_cshiftIm** for the complex shift invert mode, for a generalized real nonsymmetric problem.

_tolerance (real) precision of the computation. The default value is set by ARPACK to the machine epsilon.

_maxIt (integer) maximum number of iterations. The default value is computed by ARPACK.

_ncv (integer) number of Arnoldi vectors to be computed. It must be less than the dimension of the problem. The default value is computed by ARPACK. When **eigenSolve** is used, this default value is a little improved for small/intermediate linear systems.

_convToStd parameter specified to force the conversion of a generalized problem into a standard one. This key does not take any value: it is present or absent (any assigned value is ignored).

_forceNonSym parameter specified to force to use a nonsymmetric computational mode, although the problem is symmetric. This key does not take any value: it is present or absent (any assigned value is ignored).

_verbose (integer) verbosity level. The possible values are 0 or 1, and the default value is 0, which means no output trace.

_sort (enumeration) sort criterion. The default value is `_incr_module`, which means “by increasing module”. One can also sort by increasing real part (`_incr_realpart`) and by increasing imaginary part (`_incr_imagpart`); conversely, one can sort by decreasing order by selecting one of `_decr_module`, `_decr_realpart` or `_decr_imagpart`.

For a better understanding of all those parameters, one should know that ARPACK classifies the eigenvalue problems first as standard or generalized problems, and second according to the matrix A which can be real symmetric, real nonsymmetric or complex. This makes six categories that all own at least two main computational modes called "regular" and "shift and invert". The "regular" mode is automatically selected if no shift is given. Some additional particular shifted computational modes exist for generalized problems; this is summarized in the following table:

Kind of problem	Computational mode	Relevant parameters
<i>Standard</i> , real symmetric, nonsymmetric or complex	Regular	<code>_which</code>
	Shift and invert	<code>_sigma</code>
<i>Generalized</i> real symmetric	Regular	<code>_which</code>
	Shift and invert	<code>_sigma</code>
	Buckling	<code>_sigma</code> , <code>_mode=_buckling</code>
	Cayley	<code>_sigma</code> , <code>_mode=_cayley</code>
<i>Generalized</i> real nonsymmetric	Regular	<code>_which</code>
	Real shift and invert	<code>_sigma</code>
	Complex shift and invert (Re)	<code>_sigma</code> , <code>_mode=_cshiftRe</code>
	Complex shift and invert (Im)	<code>_sigma</code> , <code>_mode=_cshiftIm</code>
<i>Generalized</i> complex	Regular	<code>_which</code>
	Shift and invert	<code>_sigma</code>



Hypotheses. For a generalized eigenvalue problem:

- if A is real, the matrix B is required to be real symmetric positive semi-definite, except in regular mode where it should be real symmetric positive definite. In buckling mode, the real symmetric matrix A is required to be positive semi-definite while B is only required to be real symmetric indefinite;
- if A is complex, the matrix B is required to be hermitian positive semi-definite, except in regular mode, where it should be positive definite. Notice that B may still be real and symmetric.

It should be noticed that the parameters `_nev`, `_tolerance`, `_maxIt`, `_ncv` and `_verbose` can be used in any case. On the contrary, `_which` and `_sigma` are mutually exclusive; the latter takes precedence over the former. Moreover, `_mode` indicates a particular shifted computational mode, and as such is ignored if it is used without `_sigma`.

For generalized problems, the shifted modes require the computation of $(A - \sigma B)^{-1}x$ (see the table in the section **Advanced usage of ARPACK** below). When A is real nonsymmetric and σ is complex, $(A - \sigma B)^{-1}$ is complex, but the internal computation steps of the algorithm are performed in real arithmetic (the vector x is real). This saves memory requirements and computation time. This is the reason why the user should specify

which part of the operator $(A - \sigma B)^{-1}$, real or imaginary, must be taken into account. Both strategies lead to comparable results (see ARPACK's documentation). The parameter `_mode` should be set to `_cshiftRe` to select $\Re((A - \sigma B)^{-1})$; it should be set to `_cshiftIm` to select $\Im((A - \sigma B)^{-1})$, and in this case obviously, the imaginary part of σ should not be null.

The parameter `_convToStd` can be used to convert the generalized problem $Ax = \lambda Bx$ into the standard one $B^{-1}Ax = \lambda x$. This feature increases the number of computational modes available. This is done internally with the help of a so-called user-class in a way described in the section **Advanced usage of ARPACK** below.



When the function `eigenSolve` is called to solve a generalized problem, tests are performed to check the hypotheses given above. Thus, if it happens that they do not seem to be fulfilled, the conversion into a standard problem is automatically done and an information message is printed.

In the same spirit, `_forceNonSym` is a switch useful to allow the computational modes of the real nonsymmetric case to be used for a real symmetric problem ; indeed, it may happen that the symmetric algorithms fail, and using the nonsymmetric algorithms can be helpful to obtain a solution. As a last resort, we can also use the complex algorithms, but the entries of the matrix A should be first converted to complex (to achieve that, see the second example in the section **Advanced usage of ARPACK** below).

Example:

The following call computes the 20 eigenvalues of smallest magnitude (and the corresponding eigenvectors) of a standard eigenvalue problem using the regular mode, with a prescribed tolerance:

```
Number nev = 20;
EigenElements ee = arpackSolve(A, _nev=nev, _which="SM", _tolerance=1.e-12);
```

♠ *Some hints about the parameters.*

The convergence of the algorithms highly depends on the data. The ideal situation is when there is no multiplicity and the eigenvalues are well separated, which is rarely the case in practice. Here are some hints to help convergence to occur.

In regular mode, ARPACK is better used to search for eigenvalues of largest magnitude (this is why "LM" is the default value of the parameter `_which`). Thus, as far as possible, the problem should be written to use this mode. It may happen that the eigenvalues of smallest magnitude are hard to compute ; in this case, try using the shifted mode which is generally very powerful.

If there is multiplicity or the eigenvalues are clustered, consider decreasing or on the contrary increasing the number of requested eigenvalues.

The number of iterations is by default computed by ARPACK and is generally large enough ; if convergence is not attained, the tolerance (`_tolerance`) or the number of Arnoldi vectors (`_ncv`) should be modified in priority. By default, ARPACK sets the tolerance parameter to the machine epsilon which insures the computation to be performed with the highest possible precision. This represents the relative precision on the computed eigenvalues. It sometimes happens that this stopping criterion is unattainable, and the tolerance value should be increased. On the other hand, a too loose value may lead the algorithm to miss some eigenvalues.

The last parameter that can be tuned is the number of Arnoldi vectors generated by the algorithm at each iteration. This parameter can greatly influence the convergence of the algorithm ; it is related with the dimension of the subspaces associated to the eigenvalues. It must be greater than the number of wanted eigenvalues `nev` and less than the problem dimension `n`. By default, ARPACK sets it to $\min(2 \cdot \text{nev} + 1, n - 1)$. Increasing this value may facilitate the convergence ; on the other hand, this increases the computational time and the memory consumption.

To sum up, here are some actions that can be undertaken to get convergence, listed in the order it is advisable to try them :

1. if possible, use a formulation of the eigenvalue problem in order to use the default "LM" computation mode,

2. change the number of requested eigenvalues (`_nev`),
3. change the computation mode (`_which`, `_sigma`, `_mode`, `_convToStd`, `_forceNonSym`),
4. increase the number of Arnoldi vectors (`_ncv`),
5. increase the tolerance (`_tolerance`), which will lose precision.

Retrieving post-computation information

After a computation with ARPACK, one can inquire about information related to this *last* computation. The simplest way to get this information is to call the function

```
String arEigInfos();
```

which gathers the main information into a string and returns it. This string can then be printed out. To do that, `arEigInfos` calls external functions whose names are the names of the true ARPACK++ function names prefixed with `ar` (the true ARPACK++ functions are member functions that should be used in conjunction with an ARPACK object; these are external functions that can be directly used alone). The available functions are the following:

```
bool arParametersDefined();
```

which returns `true` if all internal variables were correctly defined, `false` otherwise.

```
int arConvergedEigenvalues();
```

which returns the number of eigenvalues found. This is the same value as the one provided by the member function `numberOfEigenValues` already seen in the **Results** section above.

```
int arGetMaxit();
```

which returns the maximum number of Arnoldi update iterations allowed.

```
int arGetMode();
```

which returns the computational mode used as described in the following table:

Value	Mode
1	regular mode (standard problems)
2	regular inverse mode (generalized problems)
3	shift and invert mode. For real nonsymmetric generalized problems, this option can also mean that a complex shift is being used but, in this case the operator is $\Re((A - \sigma B)^{-1})$
4	buckling mode (real symmetric generalized problems) or shift and invert mode with complex shift and the operator is $\Im((A - \sigma B)^{-1})$ (real nonsymmetric generalized problems)
5	Cayley mode (real symmetric generalized problems)

```
std::string arGetModeStr();
```

which returns a user-friendly string describing the computational mode used. This function does not exist in ARPACK and has been written in complement to the previous one which gives a rather raw information.

```
int arGetIter();
```

which returns the number of Arnoldi update iterations actually taken by ARPACK to solve the eigenvalue problem.

```
int arGetN();
```

which returns the dimension of the eigenvalue problem.

```
int arGetNcv();
```

which returns the number of Arnoldi vectors generated at each iteration.

```
int arGetNev();
```

which returns the number of required eigenvalues. The number of eigenvalues actually found, however, is given by the function `arConvergedEigenvalues`.

```
std::complex<double> arGetShift();
```

which returns the shift σ used to define the spectral transformation. This one is a slightly modified version of the original ARPACK's one in that it returns a complex value ; so if the problem is real symmetric, only the real part is relevant. If the problem is being solved in regular mode, this function will return 0.0. To avoid any confusion in this case, the user should call the function `arGetMode` before this one.

```
double arGetShiftImag();
```

which returns the imaginary part of the shift when the shift and invert mode is being used to solve a real nonsymmetric problem. This value is also returned as the imaginary part of the previous function.

```
double arGetTol();
```

which returns the stopping tolerance used to find the eigenvalues. It corresponds to the relative accuracy of the computed eigenvalues.

```
std::string arGetWhich();
```

which returns the part of the spectrum the user is seeking for. The returned string is one of those used in conjunction with the parameter `_which` above.

♠ *A full example.*

The following program computes the smallest eigenvalues of the Laplace operator on a segment with Neumann conditions. The approximation is made with the finite element method using a single element, the segment $[0, \pi]$, with an interpolation degree $k = 60$. The quadrature rule has degree $2k + 1$. The expected eigenvalues are the square of the integers, i.e. 0, 1, 4, 9, 16, 25, 36, 49, etc. Two computational modes are shown. After the call to `arpackSolve`, information about the computation done are retrieved and printed, as long as the converged eigenvalues and the corresponding eigenvectors.

```
#include "xlife++.h"
using namespace xlifepp;

int main(int argc, char** argv) {
    init(argc, argv, _lang=en); // mandatory initialization of XLiFE++

    theCout << " Eigenvalues of the 1D Laplace operator with Neumann conditions\n";
    theCout << " =====\n";

    Number nbint=1; // number of intervalls
    Number dk=60;   // interpolation degree
    theCout << "Interpolation degree = " << dk << endl;

    // mesh : segment [0, pi]
    Segment seg(_xmin=0, _xmax=pi, _nnodes=nbint+1);
    Mesh zeroPi(seg, 1);
    Domain omega = zeroPi.domain("Omega");

    Space Vk(_domain=omega, _FE_type=Lagrange, _FE_subtype=GaussLobattoPoints, _order=dk,
             _Sobolev_type=H1, _name="Vk");
    Unknown u(Vk, _name="u");
    TestFunction v(u, _name="v");

    Number qrodeg = 2*dk+1;
    BilinearForm muv = intg(omega, u * v, _quad=defaultQuadrature, _order=qrodeg),
                auv = intg(omega, grad(u) | grad(v), _quad=defaultQuadrature, _order=qrodeg);
    // Compute the Stiffness and Mass matrices
    TermMatrix S(auv, _name="auv"), M(muv, _name="muv");

    // The eigenvalue problem writes S x = l M x
    // Compute the nev first eigenvalues with smallest magnitude with Arpack
    Number nev = 8;
    EigenElements areigs = arpackSolve(S, M, _nev=nev, _which="SM");
    // Other computational mode choice, here more powerfull:
    // EigenElements areigs = arpackSolve(S, M, _nev=nev, _sigma=0.5);

    theCout << arEigInfos();

    theCout << "Eigenvalues : " << endl;
    Number nconv = areigs.numberOfEigenValues();
    for (Number i = 0; i < nconv; i++) { theCout << std::setprecision(17) <<
        areigs.value(i+1).real() << endl; }

    saveToFile("Sy", areigs, matlab);
}
```

The output produced by this program is the following:

```
Eigenvalues of the 1D Laplace operator with Neumann conditions
=====
Interpolation degree = 60
computing FE term intg_#Omega grad(u) | grad(v), using 1 threads : done
```

```

computing FE term intg_#Omega u * v, using 1 threads : done

Summary of last Arpack computation:
Number of eigenvalues (requested / converged): 8 / 8
Computational mode: regular inverse mode (generalized problem)
Part of the spectrum requested: SM
Problem size = 61, Tolerance = 1.11022e-16
Nb_iter / Nb_iter_Max = 443 / 800, Number of Arnoldi vectors = 17
Eigenvalues :
1.6569854567517169e-10
0.99999999999869593
4.0000000000087512
9.0000000000560245
16.000000000016872
25.000000000006708
36.000000000077279
48.999999999728566

```

If we comment the line containing the first call to `arpackSolve` using regular computational mode and uncomment the second one using a shift, the last part of the output is the following:

```

Summary of last Arpack computation:
Number of eigenvalues (requested / converged): 8 / 8
Computational mode: shift and invert mode
Shift used: (0.5,0)
Problem size = 61, Tolerance = 1.11022e-16
Nb_iter / Nb_iter_Max = 4 / 800, Number of Arnoldi vectors = 17
Eigenvalues :
9.5701224722688494e-14
0.9999999999997693
4.0000000000003446
8.999999999997247
15.99999999999394
25.000000000000259
35.99999999999922
48.99999999999908

```

We can observe that the eigenvalues are numerically close to the previous ones. It's worth noting that the first one, which is expected to be 0, is better approximated with the shifted computational mode, and the number of iterations is reduced from 443 to 4. Indeed, using a shifted mode is often suitable since the convergence is attained faster than with the "SM" mode, but this is not a general rule and this depends on the problem. Moreover, the choice of the shift should be made manually and carefully since every eigenvalue is forbidden. Here, in order to retrieve the eigenvalues of smallest magnitude, the value 0.5 has been chosen, which lies between the first two eigenvalues.

The last statement of the program produces nine files ; their names are `Sy_eigenvalues`, which contains the eigenvalues, and `Sy_i_Omega.m` with `i` equal to 1, 2...8, which contain the components of the eigenvectors, one eigenvector per file. Of course, the two computational modes give the same eigenvectors, possibly with a change in the sign. They are shown on the following figure (obtained as described in section 9.3):




Figure 8.9: First eigenvectors of Laplace operator on a segment with Neumann conditions.

8.3.4 Advanced usage of ARPACK

The way the function `arpackSolve` is to be used, as presented so far, is sufficient if the operator A can be expressed as a linear combination of `TermMatrix` objects, or more frequently as a unique `TermMatrix` object built from a combination of bilinear forms. However, when the definition of the operator involves other algebraic operations, like the computation of the inverse of a matrix for example, the above process cannot be used.

Indeed, it requires the creation of a specific object containing the sequence of operations needed to define the operator. In other words, the user has to write a class describing the way the operator can be computed.



This strategy is used internally in XLiFE++ when the function `eigenSolve` is called to transform a generalized problem into a standard one when the matrix B is not hermitian.

In the following, we give some general guidelines, followed by additional technical features shown on a first example ; two other examples complete the description of the practical implementation. In order to benefit from the following paragraphs, the user should know some fundamentals of the C++ programming language.

♠ General guidelines.

In order to get rid of the technicalities of ARPACK++ and to help to the creation of the user class, a general frame has been prepared that involves the creation of an intermediate placeholder object whose type is `ArpackProb`,

designed to hold the characteristics of the true ARPACK object internally created. The definition of the user class should be made in coherence with the ARPACK computational mode chosen, hold in the `ArpackProb` object. To summarize this, the user has to:

1. create a so-called user class to define the operators of the problem (this requires some programming work),
2. use it to create an `ArpackProb` intermediate object (this is straightforward),
3. call `arpackSolve` with this object as unique argument.

ARPACK++'s usage made here imposes the user class to define some matrix-vector products related to the computational mode chosen. The required products are described in the documentation of ARPACK++ and are summarized in the following table. The name of the member functions, `MultOPx`, `MultBx` and `MultAx`, are the generic names used in the documentation of ARPACK++. They have been kept here to make things easier and should be left unchanged in our context:

Kind of problem		Computational mode	Matrix-vector products	Member fcts to use
Standard	all	Regular	$y \leftarrow Ax$	MultOPx
		Shift and invert	$y \leftarrow (A - \sigma Id)^{-1} x$	MultOPx
Generalized	real symmetric	Regular	$y \leftarrow B^{-1} Ax ; x \leftarrow Ax$ $y \leftarrow Bx$	MultOPx MultBx
		Shift and invert	$y \leftarrow (A - \sigma B)^{-1} x$ $y \leftarrow Bx$	MultOPx MultBx
		Buckling	$y \leftarrow (A - \sigma B)^{-1} x$ $y \leftarrow Ax$	MultOPx MultBx
		Cayley	$y \leftarrow (A - \sigma B)^{-1} x$ $y \leftarrow Ax$ $y \leftarrow Bx$	MultOPx MultAx MultBx
	real nonsymmetric	Regular	$y \leftarrow B^{-1} Ax$ $y \leftarrow Bx$	MultOPx MultBx
		Real shift and invert	$y \leftarrow (A - \sigma B)^{-1} x$ $y \leftarrow Bx$	MultOPx MultBx
		Complex shift and invert (real part)	$y \leftarrow \Re((A - \sigma B)^{-1}) x$ $y \leftarrow Ax$ $y \leftarrow Bx$	MultOPx MultAx MultBx
		Complex shift and invert (imag part)	$y \leftarrow \Im((A - \sigma B)^{-1}) x$ $y \leftarrow Ax$ $y \leftarrow Bx$	MultOPx MultAx MultBx
	complex	Regular	$y \leftarrow B^{-1} Ax$ $y \leftarrow Bx$	MultOPx MultBx
		Shift and invert	$y \leftarrow (A - \sigma B)^{-1} x$ $y \leftarrow Bx$	MultOPx MultBx

In order to help to the definition of the user class, we have found convenient to create it as a derived class of `ARStdFrame<real_t>`, `ARStdFrame<complex_t>`, `ARGenFrame<real_t>` or `ARGenFrame<complex_t>`, depending on the nature of the problem, *standard* or *generalized*, and its type, *real* or *complex*. As their name suggests, these classes are frames prepared to facilitate the definition of the matrix-vector product(s) required by the computational mode chosen. They are abstract classes that declare the matrix-vector products `MultOPx`, `MultBx` and `MultAx` as virtual functions that the user must provide. They have a unique constructor whose prototype is:

```
template<class K_> ARStdFrame(const TermMatrix& charMat) ;
template<class K_> ARGenFrame(const TermMatrix& charMat) ;
```

The unique argument is a so-called characteristic matrix that allows to retrieve information about the context of the problem such as its dimension and the associated unknowns. In practice, it is one of the matrices involved in the definition of the operator A . Those two classes derive themselves from the class `ARInterfaceFrame` that provides, in addition, the member function

```
int GetN();
```

which returns the dimension of the problem to be solved.

We will now show how all this takes place and give further details on an example.

♠ User class example 1.

We consider again the problem of the Laplace operator on a segment with Neumann conditions (see the previous section). This problem is written and solved there as a generalized eigenvalue problem $Sx = \lambda Mx$. Now, assume we want to write this problem as a standard eigenvalue problem $M^{-1}Sx = \lambda x$, which is correct since the mass matrix M is invertible. We are facing to the operator $A = M^{-1}S$ that cannot be handled in the framework presented in the previous sections. Thus, we write a special class `StdNonSym` whose definition is the following:

```
class StdNonSym: public ARStdFrame<Real> {
public:
    /// constructor
    StdNonSym(TermMatrix& S, TermMatrix& M);

    /// destructor
    ~StdNonSym() { delete fact_p; }

    /// matrix-vector product required : y <- inv(M)*S * x
    void MultOPx(Real *x, Real *y);

private:
    /// pointers to internal data objects
    const LargeMatrix<Real> *matS_p, *matM_p;
    /// pointer to temporary factorized matrix M
    LargeMatrix<Real>* fact_p;
}; // end of Class StdNonSym =====
```

This class contains three member functions: a constructor (with two arguments which are the two matrices needed to define the problem), the destructor and the matrix-vector product required, whose name is `MultOPx`, as mentioned in the previous table.

Since we plan to use the regular computational mode, the function `MultOPx` should compute the result y of $M^{-1}Sx$ for a given x . This is done in two steps: first compute $z = Sx$, second solve $My = z$ using a Cholesky factorization of M which is symmetric positive definite. The function `MultOPx` may be called many times during the computation, so the Cholesky factorization of M has to be computed once and stored. This is done in the constructor through the initialization of the pointer `fact_p`, along with the initialization of the two other pointers `matS_p` and `matM_p` (see below).

The destructor's unique role is to free the memory allocated to store the Cholesky factorization. Let's now describe the constructor and the matrix-vector product in more details. The implementation is the following:

```
/*!
Assumptions (not checked) :
  S real
  M real symmetric positive definite
*/
StdNonSym::StdNonSym(TermMatrix& S, TermMatrix& M)
: ARStdFrame(S), matS_p(&S.matrixData()->getLargeMatrix<Real>()),
  matM_p(&M.matrixData()->getLargeMatrix<Real>()) {
```

```

fact_p = newSkyline(matM_p);
ldltFactorize(*fact_p);
}
/// Matrix-vector product  $y \leftarrow inv(M) * S * x$ 
void StdNonSym::MultOPx(Real *x, Real *y) {
    array2Vector(x, lx);
    std::vector<Real> Sx(GetN());
    multMatrixVector(*matS_p, lx, Sx);
    // Solve linear system. Matlab equivalent: ly = matM_p \ Sx;
    (fact_p->ldltSolve)(Sx, ly); // store the solution into ly
    vector2Array(ly, y);
}

```

Since `StdNonSym` derives from `ARStdFrame`, the `ARStdFrame` constructor is first called, passing S as the characteristic matrix, and the pointers `matS_p` and `matM_p` are initialized. They hold the addresses of the low level `LargeMatrix` objects containing the effective real data values. The reason is that the algebraic operations are attached to the `LargeMatrix` class with the adequate storage type. Then the Cholesky factorization of M is computed in two steps: first record in the pointer `fact_p` the result of `newSkyline`, i.e. the address of a copy of the matrix M stored in skyline storage type, second call the function `ldltFactorize` to compute the Cholesky factorization.

The prototype of the function `MultOPx` is imposed by ARPACK. Each of the two arguments is the address of a C-style array. But the algebraic operations provided by XLIFE++ require operands whose type are `std::vector`. Thus, the data values should be copied in and out using the two utility functions `array2Vector` and `vector2Array`. The two vectors `lx` and `ly` are local buffers with the right size prepared for this purpose; they are members of `ARInterfaceFrame` and are ready to use. Thus, the input array `x` is first copied into the local vector `lx`, then the matrix-vector product Sx is computed by the function `multMatrixVector` and stored into the local vector `Sx`. Then comes the resolution of the linear system $My = Sx$ by the function `ldltSolve` which uses the precomputed Cholesky factorization through the pointer `fact_p`. At last, the result is copied from the local vector `ly` into the output array `y`.

The following action is to use this user class to create an `ArpackProb` intermediate object which will set the computational mode to be used by ARPACK. For this purpose, five constructors are available. In their list of arguments, **usrcl** denotes the user class, which bears the kind of problem to be solved, standard or generalized, and **nev** is the number of desired eigenvalues:

- Constructors for *regular* mode (for standard or generalized eigenvalue problems)

The argument **which** defines the part of the spectrum to be scanned. The possible values are described in a previous section (see optional parameter **_which**).

1. Real case

```
ArpackProb(const ARInterfaceFrame<Real>& usrcl, int nev, const char* which, bool sym = true);
```

The last argument **sym** specifies by default to use the algorithm designed for a symmetric operator; if it takes the value `false`, then the algorithm designed for a nonsymmetric operator will be used.

2. Complex case

```
ArpackProb(const ARInterfaceFrame<Complex>& usrcl, int nev, const char* which);
```

- Constructors for *shifted* computational mode (for standard or generalized problems)

1. • real symmetric case:

- for standard problems: shift and invert mode (default)
- for generalized problems: shift and invert mode (default), buckling and Cayley mode

• real nonsymmetric case:

- for standard or generalized problems: (real) shift and invert mode

```
ArpackProb(const ARInterfaceFrame<Real>& usrc1, int nev, bool sym, double sigma, char cMode = 'S');
```

As above, the argument **sym** tells if the algorithm designed for the symmetric case (true) or non-symmetric case (false) should be used. The argument **sigma** is the value of the shift (real number here). The buckling and Cayley modes can be selected by giving the argument **cMode** the character value 'B' or 'C' respectively.

*Note: for standard eigenvalue problems, this last argument (computational mode **cMode**) is irrelevant and thus has not to be specified.*

2. Real nonsymmetric case, for generalized problems only: complex shift and invert mode

```
ArpackProb(const ARInterfaceFrame<Real>& usrc1, int nev, double sigmaR, double sigmaI, char cMode = 'R');
```

The shift is given by both its real part, **sigmaR**, and its imaginary part, **sigmaI**. The argument **cMode** should be set to 'R' to select $\Re((A - \sigma B)^{-1})$; it should be set to 'I' to select $\Im((A - \sigma B)^{-1})$ (for more explanations, see the description of the parameter **_mode** in the previous section).

3. Complex case, for standard or generalized problems: shift and invert mode

```
ArpackProb(const ARInterfaceFrame<Complex>& usrc1, int nev, double sigmaR, double sigmaI = 0.0);
```

The shift is given by both its real part, **sigmaR**, and its imaginary part, **sigmaI**.

In order to terminate this illustration, the last thing to do is to call the solver. Technically, we can reuse the program shown at the end of the previous section and called *A full example*. and do the following:

1. Copy the declaration of the user class `StdNonSym`, followed by its implementation as given above, just before the `main` function,
2. replace the call to `arpackSolve`:

```
EigenElements areigs = arpackSolve(S,M, _nev=nev, _which="SM");
```

by the three lines:

```
StdNonSym usrc1(S,M);
ArpackProb Arpb(usrc1,nev,"SM",false); // false means "use the nonsymmetric algorithm"
EigenElements areigs = arpackSolve(Arpb);
```

The first line creates an object called `usrc1` by calling the constructor of the user class to which the stiffness and mass matrices are passed. Then, the intermediate object `Arpb` is created using the first constructor in the list just above. This completely defines the ARPACK problem: the user class derives from `ARStdFrame<real_t>`, so it is a real standard problem; the eigenvalues of smallest magnitude are requested and the nonsymmetric algorithm is chosen. Indeed, the operator $A = M^{-1}S$ is not symmetric, so we should select the corresponding computational mode (this justifies the name given to the user class).

3. Print the eigenvalues as complex numbers by removing the call to `real` in the last line of the program:

```
for (Number i = 0; i < nconv; i++) { theCout << std::setprecision(17) << areigs.value(i+1) << eol; }
```

The output produced by this new program is the following:

```
Interpolation degree = 60
computing FE term intg_Omega grad(u) | grad(v), using 1 threads : done
computing FE term intg_Omega u * v, using 1 threads : done
```

```

Number of eigenvalues (requested / converged): 8 / 8
Computational mode: regular mode (standard problem)
Part of the spectrum requested: SM
Problem size = 61, Tolerance = 1.11022e-16
Nb_iter / Nb_iter_Max = 266 / 800, Number of Arnoldi vectors = 17
Eigenvalues :
(-3.9936942641816131e-12,0)
(0.99999999998896483,0)
(3.9999999999884972,0)
(8.999999999974278,0)
(15.99999999996687,0)
(25.000000000000899,0)
(35.99999999997002,0)
(63.999999992827938,0)

```

We can observe that the last eigenvalue is close to 64 instead of 49 which has been missed. Inserting the line

```
Arpb.ChangeTol(1.e-15);
```

between the declaration of `Arpb` and the call to `arpackSolve` sets a slightly relaxed value of the tolerance that suffices to obtain the expected result:

```

Interpolation degree = 60
computing FE term intg_Omega grad(u) | grad(v), using 1 threads : done
computing FE term intg_Omega u * v, using 1 threads : done

Number of eigenvalues (requested / converged): 8 / 8
Computational mode: regular mode (standard problem)
Part of the spectrum requested: SM
Problem size = 61, Tolerance = 1e-15
Nb_iter / Nb_iter_Max = 252 / 800, Number of Arnoldi vectors = 17
Eigenvalues :
(-3.9815928332131989e-12,0)
(0.99999999998896794,0)
(3.9999999999885101,0)
(8.999999999974225,0)
(15.99999999996653,0)
(25.000000000000909,0)
(35.99999999996525,0)
(48.999999999971514,0)

```

♠ Other tuning functions

This gives the opportunity to mention that the parameters governing the computation can be set using exactly the same function names as the ones defined in ARPACK++. Besides the function `ChangeTol` just seen, we can use the following functions:

- `ChangeMaxit(int)` to change the maximum number of iterations,
- `ChangeNcv(int)` to change the number of Arnoldi vectors to be computed.
- `Trace` to activate the output of statistics related to the computation.

For more information, see the description of the parameters `_maxIt`, `_ncv` and `_verbose` in the previous section.

♠ User class example 2.

As a second example, we can use the complex algorithm to solve the same problem. The operator $A = M^{-1}S$ should be complex ; for this, we choose to convert the matrix S to complex. The corresponding user class `StdComp` is a slight modification of the class `StdNonSym`:

```

class StdComp: public ARStdFrame<Complex> {
public:
    /// constructor
    StdComp(TermMatrix& S, TermMatrix& M);

    /// destructor
    ~StdComp() { delete fact_p; }

    /// matrix-vector product required : y <- inv(M)*S * x
    void MultOPx(Complex *x, Complex *y);

private:
    /// pointers to internal data objects
    const LargeMatrix<Complex> *matS_p;
    const LargeMatrix<Real> *matM_p;
    /// pointer to temporary factorized matrix M
    LargeMatrix<Real>* fact_p;
}; // end of Class StdComp =====

```

The modifications concern the type of S and the operands x and y changed to complex. The implementation is thus quite similar to the `StdNonSym` one:

```

/*!
Assumptions (not checked) :
  S complex
  M real symmetric positive definite
*/
StdComp::StdComp(TermMatrix& S, TermMatrix& M)
: ARStdFrame(S), matS_p(&S.matrixData()->getLargeMatrix<Complex>()),
  matM_p(&M.matrixData()->getLargeMatrix<Real>()) {

    fact_p = newSkyline(matM_p);
    ldltFactorize(*fact_p);
}

/// Matrix-vector product y <- inv(M)*S * x
void StdComp::MultOPx(Complex *x, Complex *y) {
    array2Vector(x, lx);
    std::vector<Complex> Sx(GetN());
    multMatrixVector(*matS_p, lx, Sx);
    // Solve linear system. Matlab equivalent: ly = matM_p \ Sx;
    (fact_p->ldltSolve)(Sx, ly); // store the solution into ly
    vector2Array(ly, y);
}

```

One can just mention the initialization of the pointer `matS_p` to the complex data values. The factorization of M is unchanged, and it should be noticed that here the Cholesky solver handles complex data.

The final step consists in modifying the initial program (A *full example* above) by inserting the declaration and the implementation of the user class `StdComp` as given above before the `main` function, and replace the call to `arpackSolve` by the three lines:

```

TermMatrix Sc = toComplex(S);
StdComp usrc1(Sc,M);
ArpackProb Arpb(usrc1,nev,"SM");

```

The first statement converts the matrix S to the complex one Sc . Then the object corresponding to the user class `usrc1` is created from the complex stiffness matrix and the real mass matrix. The intermediate object `Arpb` is created using the second constructor in the list given above. This completely defines the ARPACK problem: the user class derives from `ARStdFrame<complex_t>`, so it is a complex standard problem; the eigenvalues of smallest magnitude are requested. All the other parameters are the default ones.

The output produced by this last program is the following:

```

Interpolation degree = 60

```

```
computing FE term intg_Omega grad(u) | grad(v), using 1 threads : done
computing FE term intg_Omega u * v, using 1 threads : done
```

```
Number of eigenvalues (requested / converged): 8 / 8
Computational mode: regular mode (standard problem)
Part of the spectrum requested: SM
Problem size = 61, Tolerance = 1.11022e-16
Nb_iter / Nb_iter_Max = 235 / 800, Number of Arnoldi vectors = 17
Eigenvalues :
(1.6895427007126359e-10,-5.3921458890663075e-11)
(1.00000000000208538,-1.1338949016552641e-13)
(4.00000000000304183,7.7808203477527148e-12)
(9.00000000000377973,1.1273274779629001e-11)
(16.0000000000012292,2.7943890983902115e-11)
(24.999999999985345,1.3070479010254708e-11)
(36.000000000008869,-3.2309836334379703e-11)
(49.0000000000591157,-2.8194647537903334e-10)
```

♠ User class example 3.

At last, we can create a user class defining a generalized problem, what we were starting from and thus redoing in fact what is already done internally when the first calling sequence of the function `arpackSolve` presented in the previous section is used. The corresponding user class `GenSym` is the following:

```
class GenSym: public ARGenFrame<Real> {
public:
    /// constructor
    GenSym(TermMatrix& S, TermMatrix& M);

    /// destructor
    ~GenSym() { delete fact_p; }

    /// matrix-vector products required : y <- inv(M)*S * x and x <- S * x
    void MultOPx(Real *x, Real *y);

    /// matrix-vector product y <- M * x
    void MultBx(Real *x, Real *y);

private:
    /// pointers to internal data objects
    const LargeMatrix<Real> *matS_p, *matM_p;
    /// pointer to temporary factorized matrix M
    LargeMatrix<Real>* fact_p;
}; // end of Class GenSym =====
```

Take notice that this class derives from `ARGenFrame` and in accordance with ARPACK's requirements for a real symmetric generalized problem (see the table above), this class provides the two matrix-vector products `MultOPx` and `MultBx`. The implementation is very similar to the `StdNonSym`'s one:

```
/*
Assumptions (not checked) :
    S real symmetric
    M real symmetric positive definite
*/
GenSym::GenSym(TermMatrix& S, TermMatrix& M)
: ARGenFrame(S), matS_p(&S.matrixData()->getLargeMatrix<Real>()),
  matM_p(&M.matrixData()->getLargeMatrix<Real>()) {

    fact_p = newSkyline(matM_p);
    ldltFactorize(*fact_p);
}

/// Matrix-vector products y <- inv(M)*S * x and x <- S * x
void GenSym::MultOPx(Real *x, Real *y) {
```

```

array2Vector(x, lx);
std::vector<Real> Sx(GetN());
multMatrixVector(*matS_p, lx, Sx);
vector2Array(Sx, x);
// Solve linear system. Matlab equivalent: ly = matM_p \ Sx;
(fact_p->ldltSolve)(Sx, ly); // store the solution into ly
vector2Array(ly, y);
}
/// Matrix-vector product y <- M * x
void GenSym::MultBx(Real *x, Real *y) {
    array2Vector(x, lx);
    multMatrixVector(*matM_p, lx, ly);
    vector2Array(ly, y);
}

```

The constructor's code is nearly identical to the one of `StdNonSym`. The function `MultOPx` computes the same product $M^{-1}S$; it additionally stores Sx in `x` which is here both an input and an output argument as required by ARPACK. The function `MultBx` simply computes the product Mx .

Again, the initial program (A full example above) can be modified by inserting the declaration and the implementation of the user class `GenSym` before the `main` function and replace the call to `arpackSolve` by:

```

GenSym usrc1(S,M);
ArpackProb Arpb(usrc1,nev, "SM");
EigenElements areigs = arpackSolve(Arpb);

```

The first line creates an object called `usrc1` by calling the constructor of the user class to which the stiffness and mass matrices are passed. Then, the intermediate object `Arpb` is created using the first of the constructors of the class `ArpackProb` given above. This completely defines the ARPACK problem: the user class derives from `ARGenFrame<real_t>`, so it is a real generalized problem; the eigenvalues of smallest magnitude are requested, and the symmetric algorithm is chosen (since this is the default).

The output produced by this new program is the following:

```

Interpolation degree = 60
computing FE term intg_Omega grad(u) | grad(v), using 1 threads : done
computing FE term intg_Omega u * v, using 1 threads : done

Number of eigenvalues (requested / converged): 8 / 8
Computational mode: regular inverse mode (generalized problem)
Part of the spectrum requested: SM
Problem size = 61, Tolerance = 1.11022e-16
Nb_iter / Nb_iter_Max = 443 / 800, Number of Arnoldi vectors = 17
Eigenvalues :
1.6569854567517169e-10
0.99999999999869593
4.0000000000087512
9.0000000000560245
16.000000000016872
25.000000000006708
36.000000000077279
48.999999999728566

```

Once problem is solved, some particular tools may be applied to solution, for instance integral representation, export to files for graphic visualization, ... This chapter is devoted to various post-processing of solutions provided by XLiFE++.

9.1 Integral representation

In the context of integral equation, the solution of IE is a potential on the boundary (Γ). This potential is not easy to interpret, so the final step of a BEM is often the reconstruction of the field outside Γ . For instance, the Helmholtz diffraction Dirichlet problem may be solved using a single layer potential $q = [\partial_n u] \Gamma$ and the diffracted field outside the boundary Γ is given by

$$u(x) = \int_{\Gamma} G(x, y) q(y) dy.$$

XLiFE++ addresses the general form of integral representation :

$$u(x) = \int_{\Gamma} \text{opk}(G(x, y)) \otimes \text{opu}(q(y)) dy.$$

where opk is an operator on kernel, opu an operator on unknown and $\otimes$ one of the operation $*$, $|$, $\wedge$ or $\%$. The previous example corresponds to $\text{opk} = id$, $\text{opu} = id$ and $\otimes = *$. To deal with such integral representation, the user has to define a linear form from `intg` constructor:

```
LinearForm ri=intg(Gamma, G*q); //default integration method

LinearForm ri=intg(Gamma, G*q, Gauss_Legendre,3); //specifying quadrature rule

IntegrationMethods ims(Gauss_Legendre,10, 1., Gauss_Legendre, 3);
LinearForm ri=intg(Gamma, G*q, ims); //specifying 2 quadrature rules
```

In these expressions, `Gamma` is a `Domain` object, `G` a `Kernel` object and `q` an `Unknown` object. Singular integration method is required if you intend to evaluate the integral representation at points close to the boundary Γ .

The linear form may be a linear combination of `intg`:

```
IntegrationMethods ims(Gauss_Legendre,10, 1., Gauss_Legendre, 3);
LinearForm ri=intg(Gamma, G*q, ims) + intg(Gamma, (grad_x(G)|_nx)*q, ims)
```

There are several methods to compute the integral representation.

9.1.1 Direct method

To effectively compute integral representation you have to specify the vector representing the numerical potential, a `TermVector` object (say `Q`) and the points where to evaluate it. There are many way to give points:

- compute at one point `x`:

```
LinearForm ri=intg(Gamma, G*q, Gauss_Legendre,3);
Complex val;
Point x(0,0,2);
IntegralRepresentation(x, ri, Q, val);
```

- compute at an explicit list of points:

```
LinearForm ri=intg(Gamma, G*q, Gauss_Legendre,3);
Vector<Point> xs(10);
xs(1)= Point(0,0,2); \ldots
Vector<Complex> val(10);
integralRepresentation(xs, ri, Q, val);
```

- compute at an implicit list of points of a `Domain` object (say `omega`):

```
LinearForm ri=intg(Gamma, G*q, Gauss_Legendre,3);
Vector<Point> xs;
Vector<Complex> val;
integralRepresentation(omega, ri, Q, val, xs); //val and xs are filled by function
```

- compute at an implicit list of node points of an interpolation on a `Domain`:

```
LinearForm ri=intg(Gamma, G*q, Gauss_Legendre,3);
TermVector U=integralRepresentation(u, omega, ri, Q); //u unknown on a Lagrange space
```



In the previous syntaxes the type of output `val` has to be consistent with data. For instance, `val` is of complex type if `G` or `Q` is of complex type. The last syntax is more robust because the type is determined by the function. Besides, this syntax returns a `TermVector` that may be straight exported to a file for visualization.

Note that, integral representations may return a vector of vectors but not a vector of matrices. For instance, if you want to compute the gradient of the integral representation (scalar), write:

```
Vector<Vector<Complex> > gsl;
integralRepresentation(xs, intg(Gamma, grad_x(K)*u,ims), dnU, gsl);
```

or

```
Unknown us(V, "us", 2); //vector unknown !
TermVector gsl=integralRepresentation(us, omega, intg(Gamma, grad_x(K)*u,ims), dnU);
```

In this last form, attach to your `TermVector` a vector unknown with the dimension of the result.

9.1.2 Matrix method

There exists another way to deal with integral representations. It consists in computing the matrix

$$R_{ij} = \int_{\Gamma} \text{opk}(G(x_i, y)) \otimes \text{opu}(\tau_j(y)) dy.$$

Special functions will produce such matrices embedded in a `TermMatrix` object:

```
TermMatrix integralRepresentation(const Unknown&, const GeomDomain&,
                                   const LinearForm&);
TermMatrix integralRepresentation(const GeomDomain&, const LinearForm&);
TermMatrix integralRepresentation(const std::vector<Point>&,
                                   const LinearForm&);
```

When no domain is explicitly passed, one shadow `PointsDomain` object will be created from the list of points given. When no unknown is explicitly passed, one (minimal) space and related shadow unknown will be created to represent the row unknown.

The following example (2D diffraction problem) shows how to use this method of integral representation:

```

Number nmesh=25;
Disk disk_int(_center=Point(0.,0.,0.),_radius=1.,
              _nnodes=nmesh,_side_names="Gamma");
Disk disk_ext(_center=Point(0.,0.,0.),_radius=2.,_nnodes=2*nmesh,
              _domain_name="Omega",_side_names="Sigma");
Mesh mesh(disk_ext-disk_int,_triangle, 1, _gmsh);
Domain Gamma = mesh.domain("Gamma"), Sigma = mesh.domain("Sigma"), Omega=mesh.domain("Omega");
// define spaces, unknown and testfunction
Space V0(_domain=Gamma, _interpolation=P0, _name="V0", _notOptimizeNumbering);
Unknown u0(V0,"u0"); TestFunction v0(u0,"v0");
Space V1(_domain=Omega, _interpolation=P1, _name="V1", _notOptimizeNumbering);
Unknown u(V1,"u");
//define Kernel and integration method
Kernel H=Helmholtz3dKernel(k);
IntegrationMethods ims(Duffy,8,0., Gauss_Legendre,6,2., Gauss_Legendre,3);
//define forms
LinearForm lf = intg(Gamma,g*v0); //rhs linear form
BilinearForm aSL=intg(Gamma,Gamma,u0*H*v0,ims); //single layer bilinear form
LinearForm ISL(intg(Gamma,H*u0,Gauss_Legendre,6)); //intg. rep. linear form
//build system and solve it
TermVector rhs(lf);
TermMatrix ASL(aSL);
TermVector uSL = gmresSolve(ASL, rhs, _tolerance=1.0e-6, _maxIt=500);
//intg rep on Omega producing a TermMatrix
TermMatrix R=integralRepresentation(u,Omega,ISL);
TermVector U=R*uSL;

```

This method is a little more time expansive than computing directly the integral representation. Thus, if there are a lot of integral representations to do with different data, it may be of interest. Obviously, it is memory consuming.

9.1.3 Kernel interpolation method

When points x are far from boundary Γ , an alternate method consists in computing IR by interpolation method. Let Ω the domain where IR is evaluated and V_Ω a Lagrange finite element space of interpolation defined on Ω . Denote $(w_i)_i$ the basis functions associated to V_Ω space. Let W_Γ a Lagrange finite element space defined on Γ and $(\tau_j)_j$ the basis functions associated to it. Interpolated the kernel at nodes $x_i \in \Omega$ and $y_j \in \Gamma$, IR is approximated by

$$u(x_i) \approx \int_{\Gamma} \sum_i \sum_j G(x_i, y_j) w_i(x) \tau_j(y) q(y) dy dx.$$

If q has the following decomposition $q(y) = \sum_k q_k \sigma_k(y)$ we have :

$$u(x_i) \approx \sum_i \sum_j \sum_k G(x_i, y_j) w_i(x) q_k \int_{\Gamma} \tau_j(y) \sigma_k(y) dy dx$$

that reads in vector form ($U = (u(x_i)_i)$, $Q = (q_k)_k$) :

$$U = \mathbb{G} * \mathbb{M} * Q$$

with $\mathbb{G}$ the matrix $(G(x_i, y_j))_{ij}$ and $\mathbb{M}$ the mass matrix :

$$\mathbb{M}_{jk} = \int_{\Gamma} \tau_j \sigma_k.$$

This example shows how it is done with XLIFE++:

```

Space Vq(_domain=Omega, _interpolation=P0); Unknown q(Vq, "q");
computation of Q \ldots
Space Vo(_domain=Omega, _interpolation=P1); Unknown u(Vo, "u");
Space Vg(_domain=Gamma, _interpolation=P1); Unknown v(Vg, "v");
TermMatrix Gi(u, Omega, v, Gamma, G, "Gi"); //G(xi, yj)
TermMatrix M(intg (Gamma, q*v) , "M"); compute(M);
TermVector U=Gi*(M*Q);

```

Because kernel is interpolated, the mesh of Ω does not be too coarse. V_g may be chosen equal to V_q . This method is generally faster than previous ones because computation of the mass matrix is a fast process, but interpolation method fails at points x_j too close to the boundary *Gamma*.

9.2 Output functions

9.2.1 Print objects

Most of the objects appearing in the user main program may be printed in a simple way to the screen or into a file, using the output operator `<<`.

```

BilinearForm a=intg (omega, u*v);
TermMatrix A(a, "A");
compute(A);
TermVector Un(omega, u, 1, "U");
TermVector X=A*Un;
theCout << "A*un = " << X << eol; //print to screen and to the file print.txt
thePrintStream << "A*un=" << X << eol; //print to the file print.txt

```

`thePrintStream` is a `XLIFE++` predefined object allowing to print into the file `print.txt` created in the current directory. `theCout` is an `XLIFE++` object allowing to print both to the screen and file `print.txt`.

See chapter 5 to learn how to manage the verbosity.

In order to print into a specific file, first create an *ofstream* object, then print to it:

```

std::ofstream out("myfile.dat"); // out is an ofstream object associated
// with the file myfile.dat
out << "A*un=" << X << eol; // print into this file
out.close();

```

9.2.2 Export TermMatrix and TermVector

We want to exploit easily the data contained in the objects produced during the computation. The objects concerned are mainly `TermVector` objects since `TermVector` is the type of nearly all the computation results of interest to the user. This may also concern `TermMatrix` objects if further postprocessing is envisaged.

As mentioned just above, printing objects using the `<<` operator may produce big files containing a lot of information, generally used to control the different steps of the computation. But we often need to handle the data values outside `XLIFE++`, either in a raw format or in a specific one corresponding to some particular software.

The `saveToFile` commands have been designed for that purpose. They exist in two main forms:

- member function : `Object.saveToFile("FileName", options);`
- external function : `saveToFile("FileName", Object, options);`

They behave slightly differently according to the kind of object they act on. Details follow:

TermMatrix object:

```

BilinearForm a=intg(omega, u*v);
TermMatrix A(a, "A"); compute(A);
A.saveToFile("A.dat", _dense);           // dense format
A.saveToFile("A.coo", _coo, true);       // coordinate format
saveToFile("As.coo", A, _coo, true);     // works also (external function form)

```

Only two formats are available:

- Dense format (*_dense* option) : all the matrix coefficients are written, line by line;
- Coordinate format (*_coo* option), which corresponds to the MATLAB/OCTAVE sparse format: only nonzero matrix coefficients are written in the form $i \ j \ a_{ij}$.

When the last argument is set to true (false by default), structure information are added to the file name. In the previous example, the file name looks like `As(30_30_coo_real_scalar).coo`.

TermVector object:

```

TermVector U1, U2;
\ldots computation of U1 and U2 \ldots
U1.saveToFile("U1.dat");                 // raw format only
U1.saveToFile("U1.dat", true);           // raw format, structure added to name

```

With the member function form, the only available output format is raw. To select another format, the external function form should be used:

```

saveToFile("U1.dat", U1, _raw, true); // idem previous via external function

saveToFile("U.dat", U1, U2, _raw);    // two TermVectors in the same file
saveToFile("U.vtk", U1, U2, _vtk);    // idem, export in vtk format
saveToFile("U.vtu", U1, U2, _vtu);    // idem, export in vtu format
saveToFile("U.msh", U1, U2, _msh);    // idem, export in msh format
saveToFile("U.m", U1, U2, _matlab);   // idem, export in Matlab/Octave format
saveToFile("U.dat", U1, U2, _xyzv);   // idem, export nodes and values

```

Except the *raw* format which outputs only data values, all formats embed mesh information. The corresponding files are intended to be read by visualization software programs:

- *vtk* and *vtu* formats are compatible with PARAVIEW,
- *msh* format is compatible with GMSH,
- *matlab* format is compatible with MATLAB and OCTAVE,
- *xyzv* format produces ASCII files with $x \ y \ z \ v1 \ v2 \dots$ on each line.



Because of the geometrical information involved, different TermVectors which are exported using one of those formats must be defined on the same space in order to be compared.



A mesh can also be exported in *vtk*, *msh* or *mel* format using a command bearing the same name, `saveToFile`. This can be useful for conversion from one format to another, or for visualization purpose.

```
Mesh demo = \ldots;
demo.printInfo(); // prints general information about the mesh to the screen

demo.saveToFile("demo.vtk", _vtk, true); // export the mesh in vtk format
demo.saveToFile("demo.msh", _msh);      // export the mesh in msh format
demo.saveToFile("demo.mel", _mel);      // export the mesh in melina format

// Idem with the external function form:
saveToFile("demo.vtk", demo, _vtk, true);
saveToFile("demo.msh", demo, _msh);
saveToFile("demo.mel", demo, _mel);
```

The last argument is optional ; its default value is false. For the *vtk* and the *msh* formats, if this argument is true, an individual file is created for each subdomain or boundary subdomain. In this case, each filename contains the name of the corresponding subdomain.

9.3 Graphical exploitation

By itself, XLIFE++ is a finite element library and as such does not own any graphical possibilities. At present, three main software programs are targeted through the output formats mentioned in the previous section.

From a practical point of view, in order to obtain a graphical representation of the computation result, one has to process the output file produced by the `saveToFile` command, by the corresponding software. Minimal knowledge is required in order to use GMSH and PARAVIEW. We invite the user to refer to the documentation of these software programs. Most of the computation results shown in this documentation are produced by PARAVIEW and most of the meshes are displayed using GMSH.

The MATLAB/OCTAVE format is intended to be (easily) used as follows. We assume we have a `.m` script file, say `V_1_Omega.m` (produced by `saveToFile`, see above), containing the first vector computed and related to the domain Ω (maybe an eigenvector or the solution to a linear system, stored as a `TermVector` object in both cases). One has to launch MATLAB or OCTAVE, eventually change to the directory containing the `.m` file and type in

```
>> V_1_Omega
```

at the prompt (the execution of the script can also be achieved using the menus if the GUI is available). We thus automatically get one or several figures (one for each component of each unknown). The user is then free to make further computations using the data present in memory (see below) or modify the attributes of the figures.

The curves gathered on the figure 8.9 are obtained via this procedure, by typing successively `Sy_1_Omega`, ... `Sy_8_Omega`. The corresponding mesh, based on the interpolation nodes, is shown on figure 9.1. It is obtained by typing

```
>> opts=['mesh']; Sy_1_Omega
```

Notice that in this case, only the mesh is drawn and that the result would be the same with any of the other files `Sy_i_Omega.m`.




Figure 9.1: (A full example.) Computational domain: segment $[0, \pi]$.

Another example with a 2D geometry is shown on figure 9.2.




Figure 9.2: A 2D example.

The script is not interactive except for volumic data: the visualization is made by slicing the 3D domain with a plane and the user is invited to choose the cutting plane defined by a point and a vector normal to the plane, shown by a red thick line on the mesh figure. The position of the cutting plane is updated on this figure as its definition changes and the corresponding slices are displayed in other figures.

Let's show what the command window looks like in such a case, here with OCTAVE:

```
GNU Octave, version 4.0.3
Copyright (C) 2016 John W. Eaton and others.
This is free software; see the source code for copying conditions.
\ldots

>> what
M-files in directory /tmp/demo/xlifepp:

    eigs_1_Omega.m
>>
>> eigs_1_Omega
The intersection plane is defined by the point P and the orthogonal vector V.

Current value of P = 12.566      12.566      12.566
Current value of V = 1   -1    0
 1 : change P and draw
 2 : change V and draw
 3 : draw without change
 0 : quit
```

```

Your choice (other value = no change) : 3
Value range for unknown 1 : Real part = [-8.9881e-20      0.10878]   Imag part = [0  0]

Current value of P = 12.566      12.566      12.566
Current value of V = 1  -1   0
  1 : change P and draw
  2 : change V and draw
  3 : draw without change
  0 : quit
Your choice (other value = no change) : 0
Tuning suggestions:
figure(N)
subplot(2,2,k)
rotate3d,  grid,  box
view(2),  view(3),  view([Nx Ny Nz])
shading faceted
axis equal,  axis normal
set(gca,'xtick',[...])      or  set(gca,'xtick',[...])
caxis([...])
xlabel(...), ylabel(...), title(...)
print('-dpng',eigs_1_OmegaFig2.png)
>>

```

Before the user types in 3 to answer the first question, the figure 9.3 has been displayed, showing the domain mesh and an initial cutting plane. By choosing the value 3, the user accepts the current settings and the figure 9.4 is drawn. The user then terminates by answering 0, and some hints to modify the aspect of the figures are displayed.




Figure 9.3: Computational domain Omega.




Figure 9.4: Data representation corresponding to the selected slice.

When the script has terminated, we can observe the variables present in the workspace:

```
>> whos
Variables in the current scope:

  Attr Name          Size          Bytes   Class
  ----
  coord             5859x3          140616  double
  domaindim          1x1              8      double
  domainname         1x5              5      char
  elem               4832x8          309248  double
  elemtype           4832x1          38656   double
  interpDeg          1x1              8      double
  opts                0x0              0      char
  spacedim            1x1              8      double
  unknown             1x8              8      char
  val                5859x1          46872   double

Total is 66940 elements using 535429 bytes

>> quit
```

This allows the user to make any processing of his own with these data. The definitions of the variables are the following:

- **coord (real)**
Coordinates of the interpolation nodes, one node per row. The nodes are implicitly numbered from 1 to `size(coord,1)`.
- **domaindim (integer)**
Dimension of the domain (1, 2 or 3).
- **domainname (string)**
Name of the domain.

- `elem` (integer)
Array containing the lists of elements: `elem(i, :)` is an element of type `elemtype(i)`. Format of the array: one element per row, column `i` holds the `i`-th interpolation node, given by its number in the array `coord` above.
- `elemtype` (integer)
Vector containing the type of each element present in the mesh, in the same order as the array `elem` above. Each type is a code number in XLife++'s internal codification:
2 = point, 3 = segment, 4 = triangle, 5 = quadrangle,
6 = tetrahedron, 7 = hexahedron, 8 = prism, 9 = pyramid.
- `interpDeg` (integer)
Interpolation degree used during the computation.
- `opts` (string)
1-column array containing options given as keywords, one keyword per row. This allows to relaunch a script file, and thus get a new figure according to the chosen options. Available options are:
 - `'chsign'` : allows drawing values with opposite sign
 - `'mesh'` : draws only the mesh (no other graph is drawn)
 - `'silent'` : suppresses display of graphical tuning hints
- `spacedim` (integer)
Dimension of the space (1, 2 or 3).
- `unknown` (string)
1-column array containing the name of the unknowns, or their components in the vector case, one name per row.
- `val` (real or complex)
Values corresponding to the unknowns, stored column-wise, one column per component unknown. Each row contains the value at a node, or in an element if the interpolation degree is 0, in the same order as the array `coord` or `elem` respectively. Indeed, the graphical function `'patch'` used, makes the correspondence according to the number of rows of this array, which should be `size(coord, 1)` or `size(elem, 1)` respectively.

The variables `domaindim`, `domainname`, `interpDeg` and `spacedim` are defined for information or consistency check purpose. Indeed, `spacedim` should equal `size(coord,2)` and `domaindim` should be less or equal `spacedim` and be consistent with the element types.



External libraries

A.1 How to install BLAS and LAPACK libraries

Using UMFPACK or ARPACK means using BLAS and LAPACK libraries. XLiFE++ offers the ability to choose your BLAS/LAPACK installation:

- Using BLAS/LAPACK installed with UMFPACK or ARPACK
- Using default BLAS/LAPACK installed on your computer
- Using standard BLAS/LAPACK libraries, such as OPENBLAS.



On MAC OS, you may rely on the distribution provided by your favorite package manager (brew, port, ...)



On LINUX, you may rely on the distribution provided by your favorite package manager (apt-get, yum, rpm, ...)



On WINDOWS, It is very tricky to install BLAS and LAPACK by yourself, we highly recommend you to download binary files on the [XLiFE++ website](#) to avoid this annoying step

A.2 How to install UMFPACK library

UMFPACK is provided by SUITESPARSE (<http://faculty.cse.tamu.edu/davis/suitesparse.html>). When looking how UMFPACK is compiled, it seems that it can depend (maybe in the same way as BLAS/LAPACK) on other libraries provided by SUITESPARSE.

In the same way, XLiFE++ offers you the ability to choose your UMFPACK installation:

- An old installation of UMFPACK alone (from FORTRAN sources);
- An installation of UMFPACK or SUITESPARSE from your favorite package manager;



On MAC OS, main package managers are brew and port



On LINUX, main package managers are apt-get, yum, rpm, ...

- An installation of SUITESPARSE sources by yourself. We highly recommend you to choose the release relying on CMAKE to be build.



On WINDOWS, we recommend you to download binary files on the [XLiFE++ website](#) to avoid this step.



Theoretically, UMFPACK does not need to use BLAS/LAPACK, but as it is highly recommended by UMFPACK (for accuracy reasons), XLiFE++ demand that you use BLAS/LAPACK. See above.

A.3 How to install ARPACK library

ARPACK library can be obtained from the following URL: <http://www.caam.rice.edu/software/ARPACK/>. It requires BLAS and LAPACK routines. See above.



XLiFE++ uses the wrapper ARPACK++. Because of its deprecation, a patch at <http://reuter.mit.edu/index.php/software/arpackpatch/> needs to be applied to ensure a correct compilation. With the evolution of compilers, this patch is often not enough now. This is the reason why XLiFE++ contains its own patched release of ARPACK++, used by default.



On MAC OS, you may rely on the distribution provided by your favorite package manager (brew, port, ...)



If you use brew, and depending either on your OS or on the version of your compiler (g++ or clang++), installing ARPACK requires to use it with BLAS and LAPACK libraries also provided by brew (OPENBLAS distribution), as default BLAS and LAPACK libraries found by CMAKE are the one provided by MAC OS. The same problem may occur if you use the ARPACK library provided by XLiFE++



On LINUX, you may rely on the distribution provided by your favorite package manager (apt-get, yum, rpm, ...)



On WINDOWS, we recommend you to download binary files on the [XLiFE++ website](#) to avoid this step.

A.4 How to install MinGW 64 bits on WINDOWS

When you download CodeBlocks, the default compiler is MinGW 32bits. To use the full capabilities of XLiFE++, you may want to use a 64 bits compiler.

The easiest and safest way to install MinGW-W64 is to avoid the use of an installer and to download the binaries directly from the url from the <https://sourceforge.net/projects/mingw-w64/files/Toolchains%20targetting%20Win64/Personal%20Builds/mingw-builds/>. You select the version you need, for instance 7.3.0. You click on "threads-posix" directory, on one of the directories (sjlj, seh, ...). Personally, I would choose the directory having the best download rate per week. Finally, you click on the archive to download it.

The *utils* library collects all the general classes and functionalities required by the code : extended string capabilities, *Point*, *Vector* and *Matrix* (dense storage) objects, *Parameters* and *Function* objects to deal with user functions, *Timer* providing time computation tools and more internal useful classes intended mainly to developers (messages and traces management).

B.1 String, Strings

String is a nice class allowing to deal with char of arrays without managing the memory. *String* is no more than an alias to the string class of the STL which is either standard string (utf8, by default) or wide string (utf16); this choice is made in the *config.hpp* header file by setting the macro *WIDE_STRING*. When this macro changes, all the library has to be rebuilt!

As a string or wstring class of the STL, *String* proposes all the functionalities of `std::string`. Mainly, you can create, concatenate string, access to char and find string in string:

```
String s1("a string");           // create a String
String s2="another string";      // create a String using =
String s12=s1+" and "+s2;        // concatenate String, s3="a"+"b" does not work!
s1+=" and "+s2;                  // concatenate String, now s1 is the same as s12
int l=s1.size();                 // number of char of s1, s1.length() gives the same
char a=s1[3];                    // char a='t' (the fourth character)
s1[3]=p;                          // now s1="a spring and another string";
int p=s1.find("string",0);        // find first position of "string" from beginning (if p=-1 not
    found)
s1.replace(p,5,"spring");         // replace "string" by "spring"
s2=s1.substr(p,5);                // extract string of length 5 from position p
s1.compare(s2);                   // alphanumeric comparison, return 0 if equal,
                                // a negative (positive) value if s1<s2 (s1>s2)
char * c=s1.c_str();              // return pointer to the char array of the string
```

There is a lot of variations of these string functions and other functions; see the STL documentation.

Some additional functions that may be useful have been introduced:

```
template<typename T_>
String tostring(const T_& t);    // 'anything' to String
template<typename T_>
T_ stringto(const String& s);    // String to 'anything'
// returns String converted to lowercase
String lowercase(const String&);
// returns String converted to uppercase
String uppercase(const String&);
// returns String with initial converted to uppercase
String capitalize(const String&);
// trims leading white space from String
String trimLeading(const String&);
// trims trailing white space from String
String trimTrailing(const String&);
// trims leading and trailing white space from String
```

```
String trimSpace(const String&);
// delete all white space from String
String delSpace(const String& s);
// search capabilities
int findString(const String, const std::vector<String>&);
```

Be cautious with template conversion functions. The template T_type has to be clarified when invoking *stringto*.

```
// examples of conversion stringto
String s="1 2 3";
int i=stringto<int>(s);           // i=1
Real r=stringto<Real>(s);         // r=1.
Complex c=stringto<Complex>(s);   // c=(1.,0)
void * p=stringto<void*>(s);       // p=0x1
String ss=stringto<String>(s);    // ss="1"
s="(0,1)";
c=stringto<Complex>(s);           // c=(0.,1.)
```

Besides, lists of strings are available using Strings:

```
// list of strings
Strings ss("x=0","x=1","y=0","z=0"); //initialize list (up to 5 elements)
Strings ls(10); //10 empty strings
ls(1)="x=0";    //access to first string of list
String s=ss(3);
cout<<ss;       //output list
```

Strings inherits from `std::vector<String>`.

B.2 Int, Dimen, Number, Numbers

Int is a nice datatype allowing to deal with signed integers properly, whatever the OS (Windows, Unix/Linux, macOS) and the architecture (32/64 bits), so that an **Int** is 32 bits on 32 bits architectures and 64 bits on 64 bits architectures. **Number** is defined in the same way as **Int**, but for unsigned integers. **Dimen** is defined in the same way as **Int** and **Number**, but for short unsigned integers.

In fact, **Int** is no more than an alias to `long int` on 32 bits architectures and `long long int` on 64 bits architectures. **Dimen** is an alias of `unsigned short int`, and **Number** is an alias of `size_t`. As a result, **Int** and **Number** follows both the architecture.

This choice is made in the *config.hpp* header file automatically.

Number datatype is the most often used for the user, so that we defined **Numbers** to manage lists of **Number**, facilitating geometries definitions for instance:

```
// list of numbers
Numbers ns(10,11,12,13); //initialize list (up to 20 elements)
ns(1)=11; //access to first number of list
Number n=ns(3);
cout<<ns; //output list
```

Numbers inherits from `std::vector<Number>`

B.3 Real, Complex and Reals

Real is a nice datatype allowing to deal with floats, whatever the precision. **Real** is no more than an alias to `float`, `double` or `long double`; this choice is made in the *config.hpp* header file by setting the corresponding

macro: `STD_TYPES`, `LONG_TYPES` or `LONG_LONG_TYPES`. When you change the macro, all the library has to be rebuilt!

`Complex` is no more than an alias to `std::complex<Real>`.

To facilitate geometries definitions, `Reals` manages lists of `Real`:

```
// list of strings
Reals rs(2.5, -3., 0.1); // initialize list (up to 10 elements)
Reals ls(10);           // 10 reals equal to zero
ls(1)=3.7;              // access to first real of list
Real r=rs(3);
cout<<rs;               // output list
```

`Reals` inherits from `std::vector<Real>`.

B.4 Angle unit

XLiFE++ uses radian as reference angle unit. As a consequence, you have to give angles expressed in radian unit and angles are also returned or printed in radian unit. However, it is possible to pass angles in degree unit using the following syntax processing the degree to radian conversion:

```
Real angle = 45*deg_; // angle contains pi/4 !
```

B.5 Point

A finite element library deals obviously with points. The purpose of the `Point` class is to deal with points in any dimension and providing some algebraic operations on points and comparison capabilities. This class is used by the `Function` class encapsulating user functions.

There are mainly four ways to construct a point:

```
Point p4(4, 0.); // dimension(4) and value(0) p1=(0,0,0,0)
Point p1(2.);   // a 1D point p1=(2);
Point p2(1., 0.); // a 2D point p1=(1,0);
Point p3(1., 0., 1.); // a 3D point p1=(1,0,1);
Real v[]={1,2,3}; // array of real_t
Point p4(3, v); // dimension and real_t array
std::vector<Real> w(3,0); // the std::vector (0,0,0)
Point p5(w); // stl vector
```

To access to:

- the dimension n of a point `p`: `p.size`,
- to the i -th coordinate ($1 \leq i \leq n$) of a point `p`: `p(i)` or `p[i-1]`
- to the x, y or z coordinate (restricted to $n \leq 3$): `p.x`, `p.y` or `p.z`
- the vector storing the point: `p.toVect`;

You can use the coordinate accessors in reading or writing mode. A simple example:

```
Point p(1., 0., 1.); // a 3D point p=(1,0,1);
p(1)=2;             // modify the first coordinate
p.y()=3.;           // modify the second coordinate
std::vector<Real> v=p.toVect(); // convert point to vector
```

Using standard operators (+, -, *, /), it is possible to perform algebraic computations on points up to linear combinations:

```
Point p(1.,0.,1.),q(0.,0.,1.),r(1.,2.,3.); // some 3D points
Point g=(p+q+r)/3; // compute the barycenter of p,q,r
(p+=q)/=2; // p contains the middle of p and q
```

Besides, there are some functions to compute the distance or the square of distance between two points:

```
Point p(1.,0.,1.),q(0.,0.,1.),r(1.,2.,3.); // some 3D points
real_t d=p.distance(q); // compute distance between p and q
d=pointDistance(p,q); // alternative syntax
d=p.squareDistance(q); // square of the distance between p and q
d=squareDistance(p,q); // alternative syntax
```

Finally, comparing points is possible using standard operators ==, !=, <, >, <= or >=. The comparison uses a tolerance factor τ defined by the variable `Point::tolerance` (p, q being points of $\mathbb{R}^n$):

$$p == q \text{ if } |p - q| \leq \tau$$

$$p < q \text{ if } \exists i \leq n, \forall j < i, |p_j - q_j| \leq \tau \text{ and } p_j < q_j - \tau.$$

The other comparison operators !=, >, <= or >= are naturally defined from == and < operators. By default, the tolerance is set to 0. Below is an example:

```
Point p(1.,0.,1.),q(0.,0.,1.); // some 3D points
bool r=(p==q); // r=false
r=(p!=q); // r=true
r=(p<q); // r=false
Real eps=.00001;
Point::tolerance=eps; // change the tolerance factor to eps
r=(p==(p+eps/2)); // r=true
```

Geometrical transformations on points work as on geometries. Please see section 6.2 for definition and use of transformations routines.

Then, if you want to create a new `Point` by applying a transformation on a `Point`, you should use one of the following functions instead:

```
/// apply a geometrical transformation on a Point (external)
Point transform(const Point& p, const Transformation& t);
/// apply a translation on a Point (external)
Point translate(const Point& p, std::vector<Real> u = std::vector<Real>(3,0.));
Point translate(const Point& p, Real ux, Real uy = 0., Real uz = 0.);
/// apply a rotation 2d on a Point (external)
Point rotate2d(const Point& p, const Point& c = Point(0.,0.), Real angle = 0.);
/// apply a rotation 3d on a Point (external)
Point rotate3d(const Point& p, const Point& c = Point(0.,0.,0.), std::vector<Real> u =
    std::vector<Real>(3,0.), Real angle = 0.);
Point rotate3d(const Point& p, Real ux, Real uy, Real angle);
Point rotate3d(const Point& p, Real ux, Real uy, Real uz, Real angle);
Point rotate3d(const Point& p, const Point& c, Real ux, Real uy, Real angle);
Point rotate3d(const Point& p, const Point& c, Real ux, Real uy, Real uz, Real angle);
/// apply a homothety on a Point (external)
Point homothetize(const Point& p, const Point& c = Point(0.,0.,0.), Real factor = 1.);
Point homothetize(const Point& p, Real factor);
/// apply a point reflection on a Point (external)
Point pointReflect(const Point& p, const Point& c = Point(0.,0.,0.));
/// apply a reflection2d on a Point (external)
Point reflect2d(const Point& p, const Point& c = Point(0.,0.), std::vector<Real> u =
    std::vector<Real>(2,0.));
```

```

Point reflect2d(const Point& p, const Point& c, Real ux, Real uy = 0.);
/// apply a reflection3d on a Point (external)
Point reflect3d(const Point& p, const Point& c = Point(0.,0.,0.), std::vector<Real> u =
    std::vector<Real>(3,0.));
Point reflect3d(const Point& p, const Point& c, Real ux, Real uy, Real uz = 0.);

```

For instance:

```

Point p1;
Point p2=translate(p1, 0.,0.,1.);

```

B.6 Vector

The purpose of the **Vector** class is mainly to deal with complex or real vector. In particular, this class is used in the definition of the user functions (see the section Function). It is a template class mainly used as a real or complex vector:

```

Vector<Real> u;           // u=[0.]
Vector<Real> v(3);         // v=[0. 0. 0.]
Vector<Real> w(3,2.5);     // w=[2.5 2.5 2.5]
Vector<Complex> cu;        // cu=[(0.,0.)]
Vector<Complex> cv(3);     // cv=[(0.,0.) [(0.,0.) (0.,0.)]
Complex i(0,1);          // the complex i
Vector<Complex> cw(3,i);   // cw=[(0.,1.) [(0.,1.) (0.,1.)]

```

It is also possible to deal with vector of vectors, for instance:

```

Vector<Real> ones(3,1); // ones=[1. 1. 1.]
Vector<Vector<Real> > U(4,ones);
// U=[[1. 1. 1.] [1. 1. 1.] [1. 1. 1.] [1. 1. 1.]]

```

To access to a vector component (both read and write access) use the operator () with index from 1 to the vector length:

```

Vector<Real> v(3);         // v=[0. 0. 0.]
v(1)=1.;v(2)=2.;v(3)=3.; // v=[1. 2. 3.]
Vector<Complex> cv(3);     // cv=[(0.,0.) [(0.,0.) (0.,0.)]
cv(2)=Complex(1,1);       // cv=[(0.,0.) [(1.,1.) (0.,0.)]

```

Note that access using operator [] with index from 0 to the vector length -1, is also possible. Advanced users can use member functions **begin** and **end** returning respectively iterators (or const iterators) to the beginning and the end of the vector.

It is also possible to extract some vector components in a new vector or to set some vector components by specifying a set of indices either given by lower and upper indices or given by a vector of indices:

```

Vector<Real> v(5);         // v =[0. 0. 0. 0. 0.]
for (Number i=1;i<=5;i++)
    v(i)=i*i;              // v =[1. 5. 9. 16. 25.]
Vector<Real> w=v(3,5);      // w =[9. 16. 25.]
Vector<Number> is(3);
is(1)=1;is(2)=3;is(3)=5;  // is=[1 3 5]
w=v(is);                  // w =[1. 9. 25.]
v.set(1,3,w);             // v =[1. 9. 25. 16. 25.]
Vector<Real> z(3,0.);       // w =[0. 0. 0.]
v.set(is,z);              // v =[0. 9. 0. 16. 0.]

```

Standard algebraic operations (+, -, *, /, +, -, *, /) are supported by the Vector. Some shortcuts are also possible, for instance a vector plus a scalar, a scalar plus a vector, ... Here are a few examples:

```
Vector<Real> u(3,1); // u=[1. 1. 1.]
Vector<Real> v(3); // v=[0. 0. 0.]
v=2.; // v=[2. 2. 2.]
Vector<Real> w=u+v; // v=[3. 3. 3.]
w=2.*v; // v=[4. 4. 4.]
w=-2.; // v=[2. 2. 2.]
Complex i(0,1); // complex number
Vector<Complex> cv(3,i); // cv=[(0.,1.) [(0.,1.) (0.,1.)]
cv=cv*i; // cv=[(-1.,0.) [(-1.,0.) (-1.,0.)]
cv/=2.; // cv=[(-0.5,0.) [(0.5.,0.) (0.5.,0.)]
```

For algebraic operations involving two vectors, the compatibility of the size of vectors is checked. All the algebraic operations involving a real vector (resp. a complex vector) and a real scalar (resp. a complex scalar) are supported. Be cautious, as an integer value is not always certainly cast to a real value, some operations may be failed during the compiling process. For instance, the addition between a real vector and an integer does not work, cast explicitly to a real!

```
Vector<Real> u(3,1); // u=[1. 1. 1.]
Vector<Real> v(3); // v=[0. 0. 0.]
v=u+2; // DOES NOT WORK
v=u+2.; // v=[3. 3. 3.]
```

Automatic cast from real vector to complex vector is supported. For instance, the following instructions are legal:

```
Complex i(0,1); // complex number i
Vector<Real> u(3,1); // u=[1. 1. 1.]
Vector<Complex> cv(3); // cv=[(0.,0.) [(0.,0.) (0.,0.)]
cv=u+2.*i; // cv=[(1.,2.) [(1.,2.) (1.,2.)]
cv*=3.; // cv=[(3.,6.) [(3.,6.) (3.,6.)]
```

Be cautious, automatic cast is not supported for vector of vectors.

The class also provides some various functionalities:

```
Vector<Real> u(3,1); // u=[1. 1. 1.]
u.norminfy(); // the sup norm of u
u.norm2squared(); // squared quadratic norm of u
u.norm2(); // quadratic norm of u
cout<<u; // output the vector u: [1 1 1]
Vector<Complex> cv(3,i); // cv=[(0.,1.) [(0.,1.) (0.,1.)]
conj(u); // conjugate of cv
cv=cplx(u); // transform a real vector in a complex one
u=real(cv); // take the real parts
u=imag(cv); // take the imaginary parts
```

Contrary to the `Point` class, the `Vector` class offers no comparison function. Note also that there is no link between these two classes except that a `Point` may be automatically constructed from a `Vector`:

```
Vector<Real> u(3,1);
Point P=u;
```

To avoid explicit templates in user program, the following aliases are provided:

- `Reals` or `RealVector` stands for `Vector<Real>`,
- `Complexes` or `ComplexVector` stands for `Vector<Complex>`,
- `RealVectors` stands for `Vector<Vector<Real> >`,
- `ComplexVectors` stands for `Vector<Vector<Complex> >`.

B.7 Matrix

The purpose of the `Matrix` class is mainly to deal with complex or real **dense** matrices. In particular, this class is used in the definition of the user functions (see the section Function). This class is compliant with the `Vector` class. Although, it can deal with matrices of anything, it is only fully functional for real or complex matrices:

```
Matrix<Real> rA;           // an empty matrix
Matrix<Real> rB(3,2);      // a 3x2 zeros matrix
Matrix<Real> rC(3,2,1);    // a 3x2 ones matrix
Vector<Real> w(3,2.5);     // w=[2.5 2.5 2.5]
Complex i(0,1);           // the complex i
Matrix<Real> cA(3,2,i);    // a 3x2 i matrix
```

It is possible to construct diagonal matrix from a `Vector` or a matrix from a `Vector` of `Vector`, to load (and save) a matrix from a file and to construct particular matrices (`_zeroMatrix`, `_onesMatrix`, `_idMatrix`, `_hilbertMatrix`):

```
Vector<Real> u(3,2.);      // vector [2. 2. 2.]
Matrix<Real> rA(u);        // 3x3 matrix with u as diagonal
Matrix<Real> rB("mat.dat"); // matrix loaded from "mat.dat" file
Matrix<Real> rO(3,_zeroMatrix); // a 3x3 zeros matrix
Matrix<Real> rI(3,_onesMatrix); // a 3x3 ones matrix
Matrix<Real> rI(3,_idMatrix); // a 3x3 identity matrix
Matrix<Real> rH(3,_hilbertMatrix); // the 3x3 Hilbert matrix
```

Construction of complex matrix from real data are allowed (automatic cast). But the contrary is not.

There are some functions to access to the matrix properties:

```
numberOfRows(), numberOfColumns()
isSymmetric(), isSkewSymmetric(), isSelfAdjoint(), isSkewAdjoint()
```

and some utilities to access to a coefficient, a row or a column or the diagonal of the matrix :

```
Matrix<Real> A(2,2,1);     //a 2x2 ones matrix
A(1,1)=2;                  //change the coefficient A11
Vector<Real> r=A.row(1);   //first row of A
r=A.column(2);             //second column of A
r=A.diag();                //diagonal of A
A.column(1,r);              //assign a vector to the first column
A.row(2,r);                 //assign a vector to the second row
A.diag(r);                  //assign a vector to the diagonal
```

All these functions support automatic cast from real to complex but not the contrary.

Advanced users can use member functions `begin` and `end` returning respectively iterators (or const iterators) to the beginning and the end of the Matrix. The data values of the matrix are stored according to the C convention, i.e. row-wise.

There are also generalized access tools either to extract submatrix (`get` or `operator`) or to set submatrix of matrix (`set`):

```
Matrix<Real> M(3,3);
for (Number i=1; i<=3; i++)
    for (Number j=1; j<=3; j++)
        M(i,j)=i+j;           //M=[2 3 4; 3 4 5; 4 5 6]
```

```

Matrix<Real> N= M.get(2,3,2,3); //N=[4 5; 5 6]
//N=M(2,3,2,3) gives the same
Vector<Number> is(2);
is(1)=1; is(2)=3;
N= M.get(is, is); //N=[2 4; 4 6]
//N=M(is, is) gives the same
Matrix<Real> Z(2,2,0); //Z=[0 0; 0 0]
M.set(1,2,1,2,Z); //M=[0 0 4; 0 0 5; 4 5 6]
Matrix<Real> U(2,2,1); //U=[1 1; 1 1]
M.set(is, is, Z); //M=[1 0 1; 0 0 5; 1 5 1]

```

Other syntaxes are proposed, see the developer's documentation.

Besides, the **Matrix** class proposes some transformations either as internal functions or external functions:

```

Matrix<Real> A(2,2,1),B;
Matrix<Complex> C(2,2,i),D;
A.transpose(); // self transposition of A
B=transpose(A); // transposition of A, A not changed
C.adjoint(); // self transposition and conjugate C
D=adjoint(A); // transpose and conjugate, C not changed
B=diag(A); // from diagonal of A to a diagonal matrix
A=real(C); // real part of C
B=imag(C); // imaginary part of C
D=conj(C); // conjugate of C
D=cmplx(A); // forced casting from real to complex
Real n2=norm2(A); //Frobenius norm
Real ninf=norminf(A); //infinite norm

```

Standard algebraic operations (+, -, *, /, +, -, *, /) are supported by the **Matrix** class. Some shortcuts are also possible, for instance a matrix plus a scalar, a scalar plus a matrix, ... Automatic cast from real to complex is supported. There is no comparison operator.

The **Matrix** proposes some solvers:

```

Matrix<Real> A
RealVector B;
\ldots
// solve AX=B or AXs=Bxs using Gauss reduction
gaussSolver(A, B, piv, row);
gaussMultipleSolver(A, B, nbrhs, piv, row);
//inverse of a square matrix
RealMatrix invA=inverse(A);
// QR factorization
RealMatrix Q,R;
qr(A,Q,R);
// SVD factorization A= U S V*, if A a (m,n)-matrix, U is a (m,r)-matrix, V a (n,r)-matrix and S
a r-vector where r=min(m,n)
RealMatrix U, V;
RealVector S; //singular values
svdMat(A, U, S, V);

```



QR and SVD are available only if EIGEN library is set on.



It is also possible to deal with matrix of matrices, for instance:

```
Matrix<Real> ones(2,2,1);           //a 2x2 ones matrix
Matrix<Matrix<Real>> > A(2,2,ones); //a 2x2 matrix of 2x2 ones matrix
```

but all operations are not supported for such matrices!

To avoid explicit templates in user program, the following aliases are provided:

`RealMatrix` stands for `Matrix<Real>`,
`ComplexMatrix` stands for `Matrix<Complex>`.
`RealMatrices` stands for `Matrix<Matrix<Real>>>`,
`ComplexMatrices` stands for `Matrix<Matrix<Complex>>>`.

B.8 Parameters

In order to attach some user's data to anything (in particular functions), two classes (`Parameter` and `Parameters`) are proposed. The `Parameter` class handles a single data of type *integer*, *real*, *complex*, *string*, *real/complex vector/matrix* or *void ** with the possibility to name the parameter. The `Parameters` class handles a list of `Parameter` objects.

B.8.1 The Parameter object

It is easy to define a parameter by its constructor or the assignment operation:

```
Parameter p(value,[name]);
Parameter p=value;
```

where *value* is of type integer, real, complex, string (or char*), `RealVector`, `ComplexVector`, `RealMatrix`, `ComplexMatrix` or `void *` and *name* is an optional string defining the parameter name.

Once a parameter is set, it is possible to get its name (if defined), its type, its value and print it:

```
Parameter k(1., "frequency");
cout<<"parameter "<<k.name()<<" type "<<k.type()<<" value="<<real(k);
k.print(); // print name and value
cout<<k;   // print only its value
RealMatrix H(5,_hilbertMatrix); // hilbert matrix 5x5
Parameter mat(H, "Hilbert matrix"); // H as parameter
```

The use of type *void ** allows the user to deal with data of any kind. This nice possibility is for advanced users because a *void ** variable is unsafe in C++:

```
list<String> lst;           // a list of string
lst.push_back("Helmholtz"); lst.push_back("Laplace");
Parameter par(&lst, "problem list"); //void * parameter
cout<<par;                 // print the pointer not the list
list<String> >& rlst=static_cast<list<String>>&(*pointer(par)); // be sure !!!
//or
list<String> >& rlst=static_cast<list<String>>&(*par.get_p()); // be sure !!!
cout<<rlst;                // print the list not the pointer
```

The functions to get the value are `integer`, `real`, `cmplx`, `string` and `pointer`. Be cautious, the user must invoke the "get" function compatible with the parameter type. In case of misfit call, an error may occur or not if a logical cast is possible (only integer to real and real to complex).

```

Parameter k(1., "frequency"); // a real parameter
Real r=real(k);               // compatible get
Complex c=cplx(k);            // no compatible get, but cast real to complex
String s=string(k);           // no compatible get, error
void * q=pointer(k);          // no compatible get, error

```

A `Parameter` object can be automatically cast to its right value:

```

Parameter k(1., "frequency"); // a real parameter
Parameter i(complex_t(0,1), "i"); // a complex parameter
Parameter mat(RealMatrix(5, _hilbertMatrix), "Hilbert matrix"); // a matrix parameter
Real r=k; // auto cast to real
r=k; // auto cast to real
Complex c=k; // auto cast to complex
c=i; // does not work !!! cannot resolve ambiguity of complex class
c=k; // complex->complex, double -> complex
String s=string(k); // error, incompatible types
void * q=pointer(k); // error, incompatible types
RealMatrix H=mat; // ok

```

For numerical type parameters (integer, real or complex), it is possible to apply algebraic operations (+, -, *, /, /=, +, -, *, /), comparison operations (==, !=, >, >=, <, <=). The result is a `Parameter`. These operations do not yet work on vectors and matrices.

```

Parameter k(1., "frequency");
Parameter k2=k*k;

```

B.8.2 The Parameters object: list of `Parameter`

The `Parameter` object is a brick of the more interesting class `Parameters` which handles a list of `Parameter`. With this class, the user is able to deal with lists of anything of the type of numerics (integer, real, complex, vector, matrix) or string type or pointer type. In particular, these parameters lists can be attached to functions as `Parameters` object of the function (see the class `Function` documentation).

A `Parameters` object is simply defined by constructors taking one explicit data of type supported by the `Parameter` class or one `Parameter` object:

```

Parameters ps(value, [name]);

```

where *value* is of type integer, real, complex, real/complex vector/matrix, string (or char*) or void * and *name* is an optional string defining the parameter name. When *value* is a `Parameter` object, *name* is not required.

The main operations on the list are the insertion and the extraction of parameter values. To insert a parameter in the list, you can use the `push` function or the stream operator << :

```

Parameters ps;
ps.push(param);
ps<<value;

```

where *value* is of type integer, real, complex, string (or char*), void * or is a `Parameter` object.

For instance :

```

Parameters params(2., "k"); // initialize from one data
params<<Parameter(1., "rho")<<Parameter(3., "eps"); // insert 2 real
params<<3.1415926; // insert a real with no name get it by its index (4)
params<<Parameter(RealVector(5,1.), "v"); // insert a vector
params<<Parameter(RealMatrix(5, _hilbertMatrix), "H"); // insert a matrix

```

To extract a parameter from the list, you have to use the direct access operator () specifying its rank (from 1) in the parameters list or its parameter name or the parameter itself:

```
Parameter p=ps(i);    // i is an integer index
Parameter p=ps(name); // name is a string
Parameter p=ps(q);    // q is a parameter
```

If a parameter has no name (case of a value insertion with no name) a default name is given (*parameterx* with x its rank in the list)! To get the value of the parameter, capabilities of the **Parameter** class may be used. It is also possible to use the assignment operator = :

```
Parameters params;
Real k=params("k").get_r(); //use get with name
Real rho=params("rho");    //work also
Real pi=params(4);         //no name available
RealVector v=params("v"); //get vector
RealMatrix H=params("H"); //get matrix
```

where *value_type* is the type of the parameter (be cautious with type compatibility).

This class provides print facilities of a list of parameters:

```
Parameters params;
params.print();           // print on a default print file
params.print(out);        // out is an output stream
out << params;
```

Finally, the class provides a void list of parameters: *Parameters::default_Parameters*.

An example:

```
Parameter height=3;
Parameters data;
data << height << Parameter(4, "width") << "case 1" << 1.5;
// String "case 1" has default name "parameter3"
// Real_t "1.5" has default name "parameter4"
Parameter a=data("height"); // acces by name, contains height
Parameter c=data(4);        // acces by rank, contains 1.5
data(1)=2;                   // replace the value 3 by 2
data("height")=2;           // same effect, height is thereafter modified
data(height)=2;             // same effect
double x=data(4);           // x contains 1.5
x=data("width");            // x contains 4
```

Note that there is no possibility to delete a parameter of the list and, contrary to the **Parameter** class, no algebraic operations may be performed on list of parameters.

B.9 Function

In order to deal with functions with parameters of any kind it is necessary to use an object function which is related to a **Parameters** object (a list of parameters, see **Parameters** documentation). This approach allows passing friendly, at low level of the code, some user's functions, say functions defined in the main program.

B.9.1 User function and object function

When you want to deal with the integral term:

$$\int_{\Omega} e^{ikx} u(x, y, z) v(x, y, z) d\Omega,$$

where the loop of finite element computation requires the computation of the function $f(x) = e^{ikx}$ on quadrature points, it is necessary to pass the function f to the low-level code where the finite element loop is implemented. Most functions are function of a point or a list of points. So, only four kinds of function are concerned:

- Function of an n-dimensional point (see B.5 for the class `Point`);
- function of two n-dimensional points, usually named kernel;
- function of a vector of n-dimensional point;
- function of two vectors of n-dimensional points.

The functions may also have a `Parameters` as input argument if necessary (default value); for example, the real k in the previous example. The output argument may be of any type (real, complex, vector, matrix, ...), but has to be compatible with the type required in computation.

The way to define such a function is the following. First, define a standard C++ function, for instance:

```
Complex f(const Point & P, Parameters& pa = default_Parameters)
{
  Real k=pa(1);    // k is the first parameter of the parameter's list pa
  // Real k=pa("k"); is available if you have a parameter with name "k"
  Real x=P(1);     // x is the first coordinate of the point P
  return exp(i*k*x); // return a complex value result,
  //return exp(i*pa(1)*P(1)); is also possible
}
```

Then create in your main program a `Parameters` object, a `Function` object from C++ function and you `Parameters` object:

```
{
  Parameters pars(1, "k");
  Function F(f, pars);
}
```

If you have to deal with the integral term involving a real value matrix (with no parameter involved in this example):

$$\int_{\Omega} A \nabla u \cdot \nabla v \, d\Omega,$$

you may define:

```
Matrix<Real> A(const Point & P, Parameters& pa = default_Parameters)
{
  Matrix<Real> vA(3,3);
  \ldots
  return vA;
}
```



Note that even if your function does not involve some parameters, the second argument of type `Parameters` is mandatory in the function definition.

For a kernel type function, it is quite similar. You have to specify two points as input arguments:

```

Complex Green_Helmholtz_3D(const Point& M,const Point& P, Parameters& pa = default_Parameters)
{
    Real r=distance(M,P); // we assume a distance function exists
    Real k=pa(1);
    Real eps=pa(2);
    if(r>eps) return exp(i*k*r)/r;
    else \ldots
}

```

The vector form of a **Function** is a function working with a vector of points and returning a vector of results (values on each point). It may be useful when computing n values together is really faster than computing n times a single value. Such a function should be declared, for instance, as follows:

```

Vector<Complex> vf(const Vector<Point>& vP, Parameters& pa = default_Parameters)
{
    Real k=pa(1); //k is the first parameter of the parameter's list pa
    uint n=vP.size();
    Vector<Complex> res(n);
    for(int j=1;j<=n;j++) res(j)=exp(i*k*vP(j)(1));
    return res;
}

```

Note that the function has to return a **Vector** object. For a function involving a couple of vectors of points, the syntax of the declaration of the function is:

```

Vector<Complex> vf(const Vector<Point>& vP,const Vector<Point>& vQ, Parameters& pa =
    default_Parameters)

```

The functions defined by the user may be used directly as argument of some functions of the library. But in most cases it is necessary to define explicitly the object **Function** associated to the user function. This is the way to do this:

```

Parameters par;
par<<2.<<.000001; //k and eps values, inserted in a parameter list
Function funcf(f,par); //define a scalar function object using parameters
Function funcA(A); //define a matrix function object
Function funcG(Green_Hemholtz_3D, par); //define a scalar kernel
Function funcvf(vf,par); //define a scalar function in its vector form

```

Do not confuse the vector form of a **Function** and a function which returns a vector! The vector form means a function which computes a quantity (scalar, vector, matrix) on a set of points or bipoints, the result being a vector of scalars, vectors or matrices. For most applications, scalar form of **Function** are sufficient. Vector form is an extension allowing the user to compute the function more efficiently in the case of multiple evaluations.

When the user wants to associate some parameters to his function, it is mandatory to define the object **Function** because it stores the list of parameters. To understand the role of the object **Function**, note that if P is a **Point**, the two instructions

```

r=f(P,par); // call directly the user function f
funcf(P,r); // call the user function f using the object function funcf

```

are allowed and give the same result. In other words, the object **Function** shadows the **Parameters** object. In this example, using an object function seems to be artificial. The object function has a real interest when internal computational routines requires user's functions, because it is easier to send one type of object encapsulating various type of function rather than many different objects.

When you have to pass an object `Function` to a function which requires such an object, it is possible to use the constructor syntax `Function(f, param)`, avoiding the explicit creation of the object `Function`:

```
Parameters par;
par<<2.<<.000001;           // value of k and eps
compute(Function(f,par));    // compute requiring an object function
```



When using a function returning a vector or a matrix, because XLIFF++ checks the dimension(s) of the returned object by using a fake point or a normal vector, it may occur some consistency problems with the dimension of points or normals that is set to 3 by default. You can change it by specifying explicitly the dimension of the function when building it:

```
Function f(dnuinc, pars);
f.dimPoint=2;           //change the point dimension
//or
Function f(dnuinc,2, pars); // specifying the point dimension when building
```

It works in the same way for kernels.

Dealing with normal vectors

Sometimes, user functions have to deal with some normal vectors and obviously the normal vectors will depend on the point where the function is evaluated. For instance, a function computing the normal derivative of a given incident field (e.g. a plane wave e^{ikx}), will look like:

```
Complex dnuinc(const Point& P, Parameters& pa = default_Parameters)
{
    Real x=P(1), k=pa("k"); // get k from parameters
    Reals n=getN();          // get the normal vector at P
    return i_*k*exp(i_*k*x)*n(1);
}
```

When this function is passed to FE computation routines, the normal vector will be evaluated and transmitted to the function only if the `Function` object associated to the function, has declared to use the normal vector. It is done by the following instructions in the main program:

```
Parameters pars(1,"k"); // declare k in the parameters
Function f(dnuinc, pars); // associate parameters to Function object
f.require(_n);           // tell the function will use the normal
TermVector B(intg(Sigma, f*v)); // use function f
```

The normal vector refers to the domain on which the linear or bilinear form (involving the function) acts. The orientation of normal vector is described in section 6.10.2.

If you want to call a function involving a normal vector out of the context of FE computations, you have to "transmit" explicitly the normal vectors required by your function. The following code shows how to do this:

```
real_t f(const Point& x, Parameters& pa = defaultParameters)
{ Vector<real_t>& n=getVector(_n); // get the normal vector
  return n(1); }
\dots
Function F(f); F.require(_n); //say the function is using normal vector
Point P(1.,0.);              //point belonging to gamma
```

```

Vector<Real> n1=gamma.getNormal(P); //get the normal vector to gamma at P
setNx(n1);                          //pass the normal vector to the context
Real r = F(P, r);                  //compute F at P using n1

```

Note that the normal vector returned by the `getNormal` function, is not interpolated. As a consequence, normal vector on an edge of the mesh is the normal vector of one of the elements supporting the edge!

The `setNx` is thread dependant, so it can be used in a multithreading context.



Other data are available in user function, depending on the computation context : the y-normal vector (`getNy`), the current element (`getElement`), the current Dof (`getDof`) or FEDof (`getFEDof`), the domains (`getDomain`, `getDomainx`, `getDomainy`). All this data are returned as references.

Dealing with spectral family

A spectral family is defined either from a XLIFF++ function or from a collection of `TermVector`. When it is defined from a function, the function has to propose the computation for each basis index, say n . This basis index is managed by the XLIFF++ computation algorithms and transmitted either to the `Parameters` attached to the function or to a global data structure (thread safe) . To retry it as a `Number`, users have to call either the function `Parameters::basisIndex()` or the global function `getBasisIndex`:

```

Real cosny(const Point& P, Parameters& pa = defaultParameters)
{
    Real y=P(2);
    Real h=pa("h"); //get the parameter h (user definition)
    Number n=pa.basisIndex() -1; //get the index using the Parameters
    Number n=getBasisIndex() -1; //get the index using the global function
    if (n==0) return std::sqrt(1./h);
    else return std::sqrt(2./h)*std::cos(n*pi*(y+h*0.5)/h);
}

```



Note that basis index set by internal algorithms, starts from 1!



Because it is safer, it is advised to use the global function `getBasisIndex` except if two functions are involved at the same time with different indexes (case not handled for the moment). Do not use the direct access to the parameter `pa("basis index")` which is not secured.

The basis index is automatically set by internal algorithms in their computation loops. But, in user context, it may be set by calling either `pa.set("basis index", i)` or the global function `setBasisIndex(Number)` if you are using the `getBasisIndex` function.

```

Function cos(cosny, params);
TermVectors cos_int(N);
for (Number n=1; n<=N; n++)
{
    setBasisIndex(n); // update the basis index
    cos_int(n)=TermVector(u, sigmaP, cos, "c"+tostring(n-1));
}

```



Do not mix the `Parameters` way and the global way!

Sum up

- To define a function of one point returning a value of type T and its associated object *Function*:

```
T namefunction(const Point& P, Parameters& pa=default_Parameters)
Function nameofobjectfunction(namefunction, [param]);
```

- to define a function of two points (a kernel) returning a value of type T and its associated object *Function*:

```
T namefunction(const Point& P, const Point& Q, Parameters& pa=default_Parameters)
Function nameofobjectfunction(namefunction, [param]);
```

- to define a vector function of one point returning a vector of value of type T and its associated object *Function*:

```
Vector<T> namefunction(const Vector<Point>& P, Parameters& pa=default_Parameters)
Function nameofobjectfunction(namefunction, [param]);
```

- to define a vector function of two points (a vector kernel) returning a vector of value of type T and its associated object *Function*:

```
Vector<T> namefunction(const Vector<Point> &, const Vector<Point> &, Parameters&
    pa=default_Parameters)
Function nameofobjectfunction(namefunction, [param]);
```

- to avoid the explicit construction of the object function (useful when you have to pass the function as an argument):

```
Function(namefunction, [param]);
```

- to declare that the object function uses the normal vector:

```
Function nameofobjectfunction(namefunction, [param]);
nameofobjectfunction.require(_n);
```



For the people who used MELINA Fortran, this approach replaces the famous *fctrm.f* and the *tbasso* vector machinery.

B.9.2 Advanced user

Delaying computations

It may occur that the function you plan to use is a very complex one, involving some heavy computations that you want to compute only once by storing some intermediate results somewhere. In order to allow flexibility to the user, it is advised to use the capabilities of *Parameters* object to store void pointers. For instance, the first time the function is called, you can compute some reusable quantities and store them in any structure with dynamic memory allocation and store the pointer of this structure in the *Parameters* object. The next time the function is called, as you have access to this void pointer (do not forget to recast it), you can recover your data.

Calling a Function object

If you have to compute the values of the function via the object `Function`, there are mainly two ways to do it:

- using an alias to the pointer function (requires that you know the type of function and arguments)

```
Point P=Point(0,0) , Q=Point(1,1);
Complex c=funcf.funSC(P);      //a function returning a complex scalar (funSC)
Complex g=funcG.kerSC(P,Q);    //a kernel returning a complex scalar (kerSC)
Matrix<Real> m=funcA.funMR(P); //a function returning a real matrix scalar (funMR)
```

As this method uses a recasting of a void pointer with no checking, it can cause segmentation errors if there is a misfit between the type of function required and the real function stored in the void pointer! It is possible to check the type of arguments by using the utility functions `typeReturned`, `structReturned`, `typeFunction` and `typeArg`. This direct method is offered to developers in order to have the best performance.

- Using the safe overloaded operator `()`, allowing to deal with point or vector of points

```
Point P=Point(0,0) , Q=Point(1,1);
Complex c;          // complex to store the result
funcf.checkTypeOn(); // activate checking mode
funcf(P,c);          // compute a complex scalar function at point P
                    // checking mode is disabled after the computation
Vector<Point> pts;   // a vector of points
pts(1)=P; pts(2)=Q;
vector<Complex> vc;  // vector to store the result
funcf.checkTypeOn(); // activate the checking mode
funcf(Pts,vc);       // compute function at a vector of points
```

This method does not require the knowledge of the exact type of the function (the output argument must be compatible !). It allows scalar or vector form independently of the form of the user function. Note that, contrary to the first method, this method uses a reference to return the values, so you have to manage its memory allocation. When the function is called with a vector of points as input, the vector result is resized if it is too small. Using the `checkTypeOn` function, it is possible to activate the checking of the type of argument. After computation, the `checkType` variable is reset to *false* in order to avoid unnecessary rechecking. As the checking process invokes RTTI functions (expensive in time), activate wisely this option. So, if you have to evaluate many times the function, activate the checking only for the first evaluation. Note that when the checking process is deactivated, this method is still slightly more expensive than the first one.

B.10 Kernel

B.10.1 User kernels

The `Function` class allows defining kernel type function, say function of two points. But, to deal with integral equation, more information are required. It is the role of the `Kernel` class. A `Kernel` object manages mainly:

```
Function kernel;          // kernel function
Function gradx;           // x derivative
Function grady;           // y derivative
Function gradxy;          // x,y derivative
Function ndotgradx;       // nx.gradx if available
Function ndotgrady;       // ny.grady if available
Function curlx;           // curl_x if available
Function curly;           // curl_y if available
Function curlxy;          // curl_x curl_y if available
Function divx;            // div_x if available
Function divy;            // div_y if available
```

```

Function divxy;           // div_x div_y if available
Function dx1;             // d_x1 if available
Function dx2;             // d_x2 if available
Function dx3;             // d_x3 if available
Kernel* singPart;         // singular part of kernel
Kernel* regPart;          // regular part of kernel

Dimen dimPoint;          // dimension of points
SingularityType singularityType; // singularity (_notsingular, _r, _logr, _loglogr)
Real singularOrder;       // order of singularity
Complex singularCoefficient; // coefficient of singularity
SymType symmetry;        // kernel symmetry :_noSymmetry, _symmetric, ...
String name;             // kernel name
Parameters userData;     // to store some additional information

```

When dealing with a matrix kernel it may be useful to give `d_x1`, `d_x2`, `d_x3` because it is not possible to define the gradient of a matrix kernel as a `Function`.

So when defining a new one, you have to provide such information. To understand how it works, this is the example of Helmholtz3d kernel.

First define all the functions as ordinary c++ functions:

```

// kernel G(k; x, y)=exp(i*k*r)/(4*pi*r)
Complex Helmholtz3d(const Point& x, const Point& y, Parameters& pa)
{
    Real k = real(pa("k"));
    Real r = x.distance(y);
    Complex ikr = Complex(0., 1.) * k * r;
    return over4pi * std::exp(ikr) / r;
}

Vector<Complex> Helmholtz3dGradx(const Point& x, const Point& y, Parameters& pa)
{
    Real k = real(pa("k"));
    Real r2 = x.squareDistance(y);
    Real r = std::sqrt(r2);
    Complex ikr = Complex(0., 1.) * k * r;
    Complex dr = (ikr - 1.) / r2;
    Vector<Complex> g1(3);
    scaledVectorTpl(over4pi * exp(ikr)*dr / r, x.begin(), x.end(), y.begin(), g1.begin());
    return g1;
}

Vector<Complex> Helmholtz3dGrady(const Point& x, const Point& y, Parameters& pa)
{
    Real k = real(pa("k"));
    Real r2 = x.squareDistance(y);
    Real r = std::sqrt(r2);
    Complex ikr = Complex(0., 1.) * k * r;
    Complex dr = (ikr - 1.) / r2;
    Vector<Complex> g1(3);
    scaledVectorTpl(-over4pi * exp(ikr)*dr / r, x.begin(), x.end(), y.begin(), g1.begin());
    return g1;
}

```

Define regular part functions:

```

// regular part: G_reg(k; x, y)=(exp(i*k*r)-1)/(4*pi*r)
Complex Helmholtz3dReg(const Point& x, const Point& y, Parameters& pa)
{

```

```

Complex g;
Real k = real(pa("k"));
Real kr = k * x.distance(y);
Complex ikr = Complex(0., kr);
if (std::abs(kr) < 1.e-04)
{
    int n=4; // for abs(kr)<1.e-4 this is a good choice for n (checked)
    g = 1 + ikr / n--;
    while (n > 1) {g = 1 + g * ikr / n--;}
    return g == Complex(0., over4pi * k);
}
else return over4pi * k * (std::exp(ikr) - 1.) / kr;
}

Vector<Complex> Helmholtz3dGradxReg(const Point& x, const Point& y, Parameters& pa)
{
    Real k = real(pa("k"));
    Real r = x.distance(y);
    Complex ikr = Complex(0., k*r);
    Complex t = over4pi * (1. + std::exp(ikr)*(ikr - 1.))/ r;
    Vector<Complex> g(3);
    scaledVectorTpl(t/ r, x.begin(), x.end(), y.begin(), g.begin());
    return g;
}

Vector<Complex> Helmholtz3dGradyReg(const Point& x, const Point& y, Parameters& pa)
{
    Real k = real(pa("k"));
    Real r = x.distance(y);
    Complex ikr = Complex(0., k*r);
    Complex t = - over4pi * (1. + std::exp(ikr)*(ikr - 1.))/ r;
    Vector<Complex> g(3);
    scaledVectorTpl(t/ r, x.begin(), x.end(), y.begin(), g.begin());
    return g;
}

```

Define singular part functions:

```

//construct Helmholtz3d Kernel singular part: G_sing(k; x, y)=1/(4*pi*r)
Complex Helmholtz3dSing(const Point& x, const Point& y, Parameters& pa)
{
    Real r = x.distance(y);
    return over4pi/r;
}

Vector<Complex> Helmholtz3dGradxSing(const Point& x, const Point& y, Parameters& pa)
{
    Real r = x.distance(y);
    return -over4pi / (r*r);
    Complex t = -over4pi / (r*r);
    Vector<Complex> g(3);
    scaledVectorTpl(t, x.begin(), x.end(), y.begin(), g.begin());
    return g;
}

Vector<Complex> Helmholtz3dGradySing(const Point& x, const Point& y, Parameters& pa)
{
    Real r = x.distance(y);
    Complex t = over4pi / (r*r);
    Vector<Complex> g(3);
    scaledVectorTpl(t, x.begin(), x.end(), y.begin(), g.begin());
    return g;
}

```

Now construct `Kernel` objects:

```
Parameters pars;
pars<<Parameter(1., "k");

Kernel H3Dreg;    //regular part
H3Dreg.name="Helmholtz 3D kernel regular part";
H3Dreg.singularType = _notsingular;
H3Dreg.singularOrder = 0;
H3Dreg.singularCoefficient = over4pi;
H3Dreg.symmetry=_symmetric;
H3Dreg.userData = pars;
H3Dreg.dimPoint = 3;
H3Dreg.kernel = Function(Helmholtz3dReg, pars);
H3Dreg.gradx = Function(Helmholtz3dGradxReg, pars);
H3Dreg.grady = Function(Helmholtz3dGradyReg, pars);

Kernel H3Dsing;    //singular part
H3Dsing.name="Helmholtz 3D kernel, singular part";
H3Dsing.singularType = _r;
H3Dsing.singularOrder = -1;
H3Dsing.singularCoefficient = over4pi;
H3Dsing.symmetry=_symmetric;
H3Dsing.userData = pars;
H3Dsing.dimPoint = 3;
H3Dsing.kernel = Function(Helmholtz3dSing, pars);
H3Dsing.gradx = Function(Helmholtz3dGradxSing, pars);
H3Dsing.grady = Function(Helmholtz3dGradySing, pars);

Kernel H3D;    //kernel
H3D.name="Helmholtz 3D kernel";
H3D.singularType = _r;
H3D.singularOrder = -1;
H3D.singularCoefficient = over4pi;
H3D.symmetry=_symmetric;
H3D.userData = pars;
H3D.dimPoint = 3;
H3D.kernel = Function(Helmholtz3d, pars);
H3D.gradx = Function(Helmholtz3dGradx, pars);
H3D.grady = Function(Helmholtz3dGrady, pars);
H3D.regPart = &H3Dreg;
H3D.singPart = &H3Dsing;
```



If you do not define singular and regular part kernels, some computations will not be available.

In fact the Helmholtz kernels are defined in [mathsResources](#) library of XLIFE++. To load it, use the following code:

```
Parameters pars;
pars<<Parameter(1., "k");
Kernel H3D = Helmholtz3dKernel(pars);
```

B.10.2 Dealing with normal vectors

For `Kernel` objects, one can pass to some kernel functions either `_nx` vector or `_ny` vector or both using the same method as one used for `Function`:

```
Complex G(const Point& P, const Point& Q, Parameters& pa = default_Parameters)
{
  Reals nx= getNx(); // get the normal vector at P
  Reals ny= getNy(); // get the normal vector at Q
  ...
}
...
Parameters pars(1,"k"); // declare k in the parameters
Kernel K(g, pars);       // associate parameters to Kernel object
K.require(_nx);          // declare that kernel uses x-normal
K.require(_ny);          // declare that kernel uses y-normal
TermMatrix B(intg(Sigma, Sigma, u*K*v)); // use kernel K
```

Kernel functions defined in XLiFE++ managed the normal vectors, so the user has not to deal with.



By default, the dimension of points of a Kernel is 3. When you define a 2D kernel, it may happen some troubles with point dimensions, in particular if the kernel function involves some operations sensitive to the point dimension. You can cure this problem by testing point dimensions in the kernel function or by specifying the point dimension when building Kernel:

```
Real ker(const Point& x, const Point& x, Parameters& pa=defaultParameters)
{...}
...
Kernel K(ker); K.dimPoint=2;
// or
Kernel K(ker, 2);
```



If you develop a new kernel for your own use, contact the administrators. Maybe they will be happy to integrate your work in XLiFE++.

B.10.3 Tensor kernel

Tensor kernels are kernels of the following form:

$$K(x, y) = \sum_{1 \leq m \leq M} \sum_{1 \leq n \leq N} \psi_m(x) \mathbb{A}_{mn} \phi_n(y)$$

with $\mathbb{A}$ an $M \times N$ matrix. Such kernel is involved, for instance, in Dirichlet to Neumann method using spectral expansion. In many cases, the matrix is a diagonal one:

$$K(x, y) = \sum_{1 \leq n \leq N} \psi_n(x) \lambda_n \phi_n(y).$$

In the meaning of XLiFE++, the families $(\psi_m)_{1 \leq m \leq M}$ and $(\phi_n)_{1 \leq n \leq N}$ may be considered as some basis of spectral space, say `SpectralBasis` object. To define a `TensorKernel`, you have to specify either one or two `Function` defining the spectral families, one or two `SpectralBasis`, one or two `Unknown` defined on a spectral `Space` or one or two `TermVectors` handling numerical spectral family. The matrix $\mathbb{A}$ must be also given as a `Matrix` or a `Vector` if $\mathbb{A}$ is diagonal.

```
Real cosny(const Point& P, Parameters& pa = defaultParameters)
{
  Real y=P(2);
```

```

Real h=pa("h"); //get the parameter h (user definition)
int_t n=basis_index(); //get the index of function to compute
if(n==0) return sqrt(1./h);
else return sqrt(2./h)*std::cos(n*pi_*(y+h*0.5)/h);
}
...
Real k=2.; Number N=10;
Parameters params(1., "h");
Vector<Complex> A(N);
for(Number n=0; n<N; n++) A[n]=sqrt(Complex(k*k-n*n*pi_*pi_/(h*h))); // matrix A
Function cosN(cosny, params); // spectral Function's
TensorKernel tkp(cosN,A); // define TensorKernel

```

In an alternate way, you can also construct the `TensorKernel` as follows:

```

Space Sp(_domain=sigma, _basis=cosN, _dim=N, _name="vect{cos(n*pi*y)}");
Unknown phi(Sp, "phi"); // spectral unknown
TensorKernel tkp(phi,A);

```

Doing this, a spectral unknown is available to deal with problem involving such unknown. All the following constructors are available:

```

template<typename T>
TensorKernel(SpectralBasis&, vector<T>&, bool conj = false);
TensorKernel(SpectralBasis&, Matrix<T>&, bool conj = false);
TensorKernel(SpectralBasis&, vector<T>&, SpectralBasis&);
TensorKernel(SpectralBasis&, Matrix<T>&, SpectralBasis&);
TensorKernel(Function, vector<T>&, bool conj = false);
TensorKernel(Function, Matrix<T>&, bool conj = false);
TensorKernel(Function, vector<T>&, Function);
TensorKernel(Function, Matrix<T>&, Function);
TensorKernel(Unknown&, vector<T>&, bool conj = false);
TensorKernel(Unknown&, Matrix<T>&, bool conj = false);
TensorKernel(Unknown&, vector<T>&, Unknown&);
TensorKernel(Unknown&, Matrix<T>&, Unknown&);
TensorKernel(vector<TermVector>&, vector<T>&, bool conj = false);
TensorKernel(vector<TermVector>&, Matrix<T>&, bool conj = false);
TensorKernel(vector<TermVector>&, vector<T>&, vector<TermVector>&);
TensorKernel(vector<TermVector>&, Matrix<T>&, vector<TermVector>&);

```

By default, the second family (may be same as the first one) is not conjugated in computation. By activating the option `conj` to `true`, the second family will be conjugated in computation.

It is possible to associate some geometric maps (f, g) to a tensor kernel:

$$K(x, y) = \sum_{1 \leq m \leq M} \sum_{1 \leq n \leq N} \psi_m(f(x)) \mathbb{A}_{mn} \phi_n(g(y))$$

```

Vector<Real> f(const Point& P, Parameters& pa = defaultParameters) {...}
Vector<Real> g(const Point& P, Parameters& pa = defaultParameters) {...}
...
TensorKernel tkp(cosN,A);
tkp.xmap=Function(f);
tkp.ymap=Function(g);

```

When `TensorKernel` is defined from vector spectral families (i.e. ϕ_n is a vector function), the vector tensor kernel reads

$$\mathbb{K}(x, y) = \sum_{1 \leq m \leq M} \sum_{1 \leq n \leq N} \phi_n(y) \mathbb{A}_{mn} \psi_m^t(x)$$

with $\mathbb{K}$ a matrix $\dim(\phi_n) \times \dim(\psi_m)$. This vector kernel can be used in bilinear form as follows:

$$\int_{\Gamma} \int_{\Sigma} \mathbf{u}(y) | (K(x, y) * \mathbf{v}(x)) = \sum_{1 \leq m \leq M} \sum_{1 \leq n \leq N} \mathbb{A}_{mn} \int_{\Gamma} (\mathbf{u} | \phi_n) \int_{\Sigma} (\mathbf{v} | \psi_m)$$

with $\dim(\mathbf{u})=\dim(\boldsymbol{\phi}_n)$ and $\dim(\mathbf{v})=\dim(\boldsymbol{\psi}_m)$ and $(\cdot|\cdot)$ the inner product. In terms of FE ($\mathbf{w}_j$ and $\boldsymbol{\tau}_i$ basis functions related respectively to u and v), XLiFE++ produces the matrix

$$\mathbb{T}_{ij} = \sum_{1 \leq m \leq M} \sum_{1 \leq n \leq N} \mathbb{A}_{mn} \int_{\Gamma} (\mathbf{w}_j | \boldsymbol{\phi}_n) \int_{\Sigma} (\boldsymbol{\tau}_i | \boldsymbol{\psi}_m)$$

B.11 Tabular

The `Tabular` class allows managing tabulated values of a function. More precisely, it handles the values of a function on a uniform grid of any dimension, mainly providing some tools to create the table, to save the table to a file, to load a table from a file, and to evaluate the values of the function at some points by interpolating from the values on the grid.

Up to now, only scalar (T is Real or Complex) functions of 1,2 or 3 real coordinates, may be with a `Parameters`, are handled:

```
T f1 (Real);
T f1p (Real, Parameters&);
T f2 (Real, Real);
T f2p (Real, Real, Parameters&);
T f3 (Real, Real, Real);
T f3p (Real, Real, Real, Parameters&);
```

To create a `Tabular` define your function and give the grid parameters (the starting coordinate x0, the step dx, the number of steps nbx, an optional name) along each coordinate:

```
Real f1 (Real x) {return sin(x);}
\dots
Tabular<Real> t1 (0.,0.01,100,f1);
```

Now, you can print the `Tabular`, save the `Tabular` to a file and evaluate the tabulated function at any point inside the grid domain:

```
theCout<<t1;
t1.saveToFile("f1.tab", "my optional comment");
Real y=t1(0.5);
```

If you saved a `Tabular` to a file, you can load it in a new `Tabular` of the same type:

```
Tabular<Real> t1("f1.tab");
```

To deal with a 2D or 3D grid, it is quite similar:

```
Real f2 (Real x, Real y) {return sin(x*y);}
\dots
Tabular<Real> t2 (0.,0.01,100,0.,0.005,50,f2);
theCout<<t2;
t2.saveToFile("f2.tab", "my optional comment");
Real y=t2(0.5,0.5);
```



If you need a grid of dimension greater than 3, contact the developers. But be care, a 4D grid with 100 steps in each direction requires storing 10^8 values, almost 1 Go of memory for double values.

Tabulated Function

In order to use tabulated function in FE computation, it is possible to associate a `Tabular` to a `Function`:

```
Real f(Real x, Real y){return sin(x*y);}
\dots
Tabular<Real> tab(0.,0.01,100, 0.,0.005,50, f);
Function F(tab, 2); // 2 is the dimension of Point in the function!
```

To be consistent, the dimension of the input `Point` of the function has to be specified to the dimension of the `Tabular`! Up to now, `Tabular` dimension is limited to 3.

It may be of interest to use a `Tabular` with a dimension less than the `Point` dimension; for instance a `Tabular` defined only for the radial coordinate. In that case, a `Function` relating `Point` to radial coordinates must be defined:

```
Real f(Real x, Real y){return sin(x*y);}
Real radial(const Point& X, Parameters& pars=defaultParameters) {return norm(X);}
\dots
Tabular<Real> tab(0.,0.01,100,0.,0.005,50,f);
Function R(radial); // create R function from radial function
Function F(tab, 2, R); // 2 is the dimension of Point in the function!
```

Note that it is also possible to associate a `Tabular` to the function itself:

```
Real f(const Point& X, Parameters& pars=defaultParameters){return sin(x*y);}
\dots
Tabular<Real> tab(0.,0.01,100,0.,0.005,50,f);
Function F(f, 2); // 2 is the dimension of Point in the function!
F.createTabular(0.,0.01,100,0.,0.005,50); // F is now tabulated
```

Once a `Tabular` is handled by a `Function`, it will be used in any circumstances!



Tabulated `Function` works only for **scalar** functions !

B.12 SymbolicFunction

Some finite element constructions require passing as argument a `SymbolicFunction` object, that is a symbolic expression of a function. Such object is built in by writing any expression involving

- some constants (real or complex)
- some variables: `x_1`, `x_2`, `x_3`, `r_`, `theta_`, `phi_`
- some algebraic operators: `+` `-` `*` `/` `^` (power)
- some boolean operators: `&&` `||` `<` `<=` `>` `>=` `==` `!=` `!` (not)
- some mathematical functions: `abs`, `realPart`, `imagPart`, `sqrt`, `squared`, `sin`, `cos`, `tan`, `asin`, `acos`, `a`

The result of a boolean expression is either 0 (false) or 1 (true).



The functions `asinh`, `acosh`, `atanh` are only available when compiling with C++ 2011 standard.

To deal with a symbolic function is very easy. For instance consider the function

$$f(x_1, x_2) = [1 - x_1 + \cos(x_2)]^3.$$

To define it as a symbolic function, write:

```
SymbolicFunction fs = (1-x_1+cos(x_2))^3;
```

To evaluate it, write:

```
Real r = fs(-1,0);
Complex c = fs(i_,0);
```

When evaluating a symbolic function involving polar or spherical variables (say $r_$, θ or ϕ), cartesian coordinates (x, y, z) must be passed; r , θ and ϕ being evaluated as follows:

$$r = |(x, y, z)|, \quad \theta = \text{atan2}(y, x), \quad \phi = \text{asin}(z/r).$$

```
SymbolicFunction fs= (1-r_*cos(2.*theta_))^3;
cout<<fs(0.5,0.5); // gives 1 (r=0.5 and theta=pi/4)
```

You can mix algebraic and boolean expressions. Consider the following function:

$$f(x_1) = \begin{cases} e^{x_1} & x_1 \leq 0 \\ 1 & x_1 > 0 \end{cases}$$

To define it, write:

```
SymbolicFunction fs = (x_1<=0)*exp(x_1)+(x_1>0);
```

B.13 Parametrization

Besides canonical geometries, XLiFE++ proposes to define geometries from parametrization of its boundaries or a mapping of a canonical domain. This is the purpose of the `Parametrization` object that deals with function f :

$$\left| \begin{array}{ll} \hat{\Omega} \subset \mathbb{R}^p & \longrightarrow \Omega \subset \mathbb{R}^n \\ x & \longrightarrow f(x) \end{array} \right.$$

where x is the parameter (say t , or (u, v)) and $p \leq n$. When $p = 1$, parametrizations concern curves, when $p = 2$ parametrizations concerns surfaces. Note that p can be equal to n . In that case, f is a mapping (for instance the polar mapping). In practice, interesting situations correspond to 2D/3D curve or 3D surface.

There exist two ways to construct a `Parametrization` object, either by giving an explicit C++ function or using symbolic functions.

The explicit C++ function must be of the form:

```
RealVector f(const Point& x, Parameters& pars, DiffOpType d)
```

where x is the parameter vector, pars a list of additional parameters (do not confuse with the parameter vector) and d a differential operator (one of `_id`, `_d1`, `_d2`, `_d11`, `\ldots`) telling which derivative is requested.

As a first example, consider the circle arc

$$\Omega = \left\{ (R \cos t, R \sin t), t \in \hat{\Omega} = \left[-\frac{\pi}{4}, \frac{\pi}{4}\right] \right\}.$$

The XLiFE++ code looks like:

```

RealVector fc(const Point& x, Parameters& pars, DiffOpType d)
{
    Real R=pars("R"), t=x(1);
    if(d==_id) return RealVector(R*cos(t), R*sin(t));
    parfun_error("fc",d);
}

\dots
Parameters pars(1., "R");
Parametrization pc(-pi_/4, pi_/4, fc, pars, "arc");

```

The parametrization name (here "arc") is not mandatory.

When functions are quite simple, symbolic functions may be used:

```

Real R=1.;
Parametrization pc(-pi_/4, pi_/4, R*cos(x_1), R*sin(x_1), Parameters(), "arc");

```

In that case, an empty parameter is passed to the parametrization and R is passed to the symbolic functions.

To construct parametrizations, the following syntaxes are available:

```

//1D parametrization on segment [a,b]
Parametrization pa(a,b,c++_fun,parameters,name);
Parametrization pa(a,b,symb_fun,symb_fun,parameters,name);
Parametrization pa(a,b,symb_fun,symb_fun,symb_fun,parameters,name);
//2D parametrization on rectangle[a,b]x[c,d]
Parametrization pa(a,b,c,d,c++_fun,parameters,name);
Parametrization pa(a,b,c,d,symb_fun,symb_fun,symb_fun,parameters,name);
//general constructors
Parametrization pa(geometry,c++_fun,parameters,name);
Parametrization pa(geometry,symb_fun,symb_fun,parameters,name);
Parametrization pa(geometry,symb_fun,symb_fun,symb_fun,parameters,name);

```

Once constructed, the `Parametrization` can compute the point at a parameter:

```

Parametrization pc(-pi_/4, pi_/4, cos(x_1), sin(x_1), Parameters(), "arc");
Point P=pc(pi_/8);
Parametrization ps(-pi_/2, pi_/2, -pi_, pi_, cos(x_1)*cos(x_2), cos(x_1)*sin(x_2), sin(x_1),
    Parameters(), "unit sphere");
Point Q=ps(0,0);

```

If derivatives are available, it is also possible to compute some important geometrical quantities at parameter : the local lengths (ds), the curvilinear abscissas (s), the normal vector (N), the binormal vector (bN, only for 3D curve), the tangent vector (T), the bitangent vector (b, only for 3D surface), the curvatures (principal curvatures in 3D)¹:

```

RealVector Parametrization.lengths(x1,[x2])
Real Parametrization.length(x1,[x2])
Real Parametrization.bilength(x1,x2) //only 2D parametrization
RealVector Parametrization.curabcs(x1,[x2])
Real Parametrization.curabc(x1,[x2])
Real Parametrization.bicurabc(x1,x2) //only 2D parametrization
RealVector Parametrization.normals(x1,[x2])
RealVector Parametrization.normal(x1,[x2])
RealVector Parametrization.binormal(x1) //only 3D curve
RealVector Parametrization.tangents(x1,[x2])
RealVector Parametrization.tangent(x1,[x2])

```

¹Mathematical definitions are available in the developer documentation

```

RealVector Parametrization.bitangent(x1,x2)    //only 3D surface
RealVector Parametrization.curvatures(x1,[x2])
Real Parametrization.curvature(x1,[x2])
Real Parametrization.bicurvature(x1,x2)       //only 3D surface
Real Parametrization.gaussCurvature(x1,x2)    //only 3D surface
Real Parametrization.meanCurvature(x1,x2)     //only 3D surface
real_t normalCurvature(x1,x2,d)               //normal curvature relatively to d (3D surface)
RealVector curvatures((x1,x2,d))              //Gauss, mean and normal curvature (3D surface)
Real Parametrization.torsion(x1)               //only 3D curve
RealMatrix weingarten(x1,x2)                  //only 3D surface
RealMatrix jacobian(x1,[x2])                  //jacobian matrix
RealVector metricTensor(x1,[x2])              //metric tensor
RealVector christoffel(x1,[x2])               //Christoffel symbols (3D surface)

```

Computations of most of these geometrical quantities require first and second derivatives of the parametrization. Only the computation of the torsion requires third derivatives. These derivatives are available when using symbolic functions but have to be given when using a C++ function, for instance:

```

RealVector fc(const Point& x, Parameters& pars, DiffOpType d)
{
  Real R=pars("R"), t=x(1);
  switch (d)
  {
    case _id : return RealVector(R*cos(t), R*sin(t)); //no derivative
    case _d1 : return RealVector(-R*sin(t), R*cos(t)); //first derivative
    case _d11 : return RealVector(-R*cos(t), -R*sin(t)); //second derivative
    case _d111 : return RealVector(R*sin(t), -R*cos(t)); //third derivative
    default : parfun_error("fc",d);
  }
  return RealVector();
}

```

Note that curvilinear abscissas are integrals. In XLIFE++, these integrals are approximated using a trapeze method with 1000 points and a linear interpolation. This number of points may be changed using:

```

Parametrization pc(-pi_/4, pi_/4, cos(x_1), sin(x_1), Parameters(), "arc");
pc.np = 500; // change the number of points of trapeze method

```

Note that it is also possible to associate C++ functions or symbolic functions to the lengths, the curvilinear abscissas, the normals, the tangents, the curvatures using the `setlength`, `setcurabc`, `setnormal`, `settangential` and `setcurvature` function. The inverse of the parametrization may be called if the user has given it either in C++ form or in symbolic form:

```

\dots
RealVector invfc(const Point& p, Parameters& pars, DiffOpType d)
{
  if(d!=_id) parfun_error("invfc",d);
  return RealVector(1, atan2(tp(2), tp(1)));
}
\dots
Parametrization pc(-pi_/4, pi_/4, fc, pars, "arc");
pc.setinvParametrization(invfc);
Real t=pc.toRealParameter(Point(0.,0.)); //get parameter related to (0,0)

```

All canonical geometries have an internal parametrization defined either on $[0, 1]$ or $[0, 1] \times [0, 1]$ or $[0, 1] \times [0, 1] \times [0, 1]$. See the developer documentation for the expression of the canonical parametrizations.

When geometry is composite, the parametrization is managed by the `PiecewiseParametrization` class inheriting from `Parametrization` class. The piecewise parametrization is the collection of "local" parametrizations related to canonical geometries that compose the composite geometry. It is not globally C0, but it is possible to

travel through with the help of an additional map that handles the neighbor parametrizations (see the developer documentation for details). Most of geometrical functions are available.

B.14 Splines


Generally speaking, a spline is a piecewise polynomial curve that approaches, in a sense to be specified, an ordered list of points. The simplest one is the spline of degree 1 (linear spline) which connects the points by segments. XLiFE++ provides the Hermite cubic spline (C2), the Catmull-Row spline (C1), the B-spline and rational B-Spline (Ck) and the Bézier curve (Ck). The two first ones are interpolation splines while the last ones are approximation spline. Combining two rational B-splines in two directions gives a surface approximation, named NURBS acronym of Non-Uniform Rational B-Spline.

B.14.1 C2 spline


Let $(t_i)_{0 \leq i \leq n}$ and $(y_i)_{0 \leq i \leq n}$. There exists a unique C^2 piecewise cubic polynomial such that $q(t_i) = y_i$ for $0 \leq i \leq n$ and $q'(t_0) = y'_0$, $q'(t_n) = y'_n$. Each cubic polynomial may be constructed from the knowledge of $b_i = q'(t_i)$, $0 \leq i \leq n$ which is the solution of the following linear system ($h_i = t_i - t_{i-1}$, $h_{i,j} = 2(h_i + h_j)$):

$$\begin{bmatrix} 1 & 0 & & & & & \\ h_2 & h_{1,2} & h_1 & & & & \\ & \ddots & \ddots & \ddots & & & \\ & & h_{i+1} & h_{i,i+1} & h_i & & \\ & & & \ddots & \ddots & \ddots & \\ & & & & h_n & h_{n-1,n} & h_{n-1} \\ & & & & & 0 & 1 \end{bmatrix} \cdot \begin{bmatrix} b_0 \\ b_1 \\ \vdots \\ b_i \\ \vdots \\ b_{n-1} \\ b_n \end{bmatrix} = \begin{bmatrix} y'_0 \\ \frac{3}{h_1 h_2} (h_1^2 (y_2 - y_1) + h_2^2 (y_1 - y_0)) \\ \vdots \\ \frac{3}{h_i h_{i+1}} (h_i^2 (y_{i+1} - y_i) + h_{i+1}^2 (y_i - y_{i-1})) \\ \vdots \\ \frac{3}{h_{n-1} h_n} (h_{n-1}^2 (y_n - y_{n-1}) + h_n^2 (y_{n-1} - y_{n-2})) \\ y'_n \end{bmatrix}$$


The spline is said to be **clamped** because derivatives at ends are imposed.



Other boundary conditions are usual : $q''_1(t_0) = q''_n(t_n) = 0$ leading to **natural** spline



or periodicity conditions : $q_1'(t_0) = q_n'(t_n)$ and $q_1''(t_0) = q_n''(t_n)$ leading to **periodic** spline.



To interpolate any set of points $(P_i)_{0 \leq i \leq n}$ in $\mathbb{R}^2$ or $\mathbb{R}^3$, the previous method is extended as following. Let $T = (t_i)_{0 \leq i \leq n}$ a set of parameters (knots) and a set of scalar values $Y = (y_i)_{0 \leq i \leq n}$, we denote $\mathcal{S}_{T,Y}$ the spline function related to the sets T, Y . The C2 spline related to the set of points (P_i) is defined as:

$$Q(t) = (\mathcal{S}_{T,P^1}(t), \mathcal{S}_{T,P^2}(t), \mathcal{S}_{T,P^3}(t))$$

where $P^k = (P_i^k)_{i=0,n}$ with P_i^k the k^{th} coordinate of the point P_i .

The usual choices of parametrization are

- The x-parametrization: $t_i = P_i^1$, $0 \leq i \leq n$ (gives the original C2 spline);
- The uniform parametrization: $t_i = i$, $0 \leq i \leq n$;
- The chordal parametrization: $t_0 = 0$, $t_i = t_{i-1} + \|P_i - P_{i-1}\|$, $1 \leq i \leq n$;
- The centripetal parametrization: $t_0 = 0$, $t_i = t_{i-1} + \|P_i - P_{i-1}\|^{1/2}$, $1 \leq i \leq n$.




To make the user life easier, the parameter is pullback to the interval $[0, 1]$. In other words, user addresses the spline parametrization using $s \in [0, 1]$ that is mapped to $t = t_0 + (1 - s)t_n$ where t_0, t_n are the spline parameter bounds. All splines work in the same way.

XLIFE++ provides the `C2Spline` class. There are two ways to construct a C2 spline, either by giving two vectors of reals (T, Y) (classical C2 spline) or giving a vector of points P (extended C2 spline). The following optional parameters may be given at construction:

- the type of parametrization : one of `_xParametrization`, `_uniformParametrization`, `_chordalParametrization`, `_centripetalParametrization`
- the boundary conditions : two of `_naturalBC`, `_clampedBC`, `_periodicBC`
- the derivatives at end points (vector of reals) required when using clamped conditions

```
Number n=5;
Real x=0, dx=pi/n;
vector<Point> points(n+1);
for (Number i=0; i<=n; i++, x+=dx) points[i]=Point(x, sin(x));
C2Spline csn(points, _xParametrization); //natural spline
C2Spline csc(points, _xParametrization, _clampedBC, _clampedBC,
             Reals(1., 1.), Reals(1., -1.)); //clamped spline
C2Spline csp(points, _xParametrization, _periodicBC); //periodic spline
```



When `_xParametrization` is selected, the curve is regarded as $x \rightarrow y(x)$ curve and the returned "values" are 1D points. In contrast, when another parametrization is selected, the curve is regarded as $t \rightarrow (x(t), y(t))$ and the returned "values" are 2D points.



Be cautious with periodic conditions. For a periodic open curve (e.g. $\sin x$ on $[0, 2\pi]$) use only the `_xParametrization` mode and for a closed periodic curve use other parametrization mode.

Once a `C2Spline` object is constructed, using either the function `evaluate` or the operator `()`, it can be evaluated at any parameter $t \in [0, 1]$.

```
...
C2Spline csnc(points, _xParametrization);
Real t=0.5; //middle parameter
Point P=csnc(t); //value
Point dP=csnc(t, _dt); //first derivative (vector as a point)
Point d2P=csnc(t, _dt2); //second derivative (vector as a point)
```

`C2Spline` allocates also a `Parametrization` object related to the spline parametrization. Using this object, other quantities such as curvilinear abscissa, normal or tangent vector, curvatures are available (see `Parametrization` class):

```
...
C2Spline csnc(points, _xParametrization);
Real t=0.5; //middle parameter
const Parametrization& pa=csnc.parametrization();
Real c=pa.curvature(t);
Real s=pa.curabc(t);
Reals no=pa.normal(t);
Reals ta=pa.tangent(t);
```

B.14.2 Catmull-Rom spline

Another way to construct interpolation spline consists in imposing also the tangent vectors (T_i) at control points P_i . Several methods have been proposed and the Catmull-Rom method is one of them. On the interval $[t_i, t_{i+1}]$ the spline Q is defined by

$$Q(t) = \begin{bmatrix} 1 & t & t^2 & t^3 \end{bmatrix} \begin{bmatrix} 0 & 1 & 0 & 0 \\ -\alpha & 0 & \alpha & 0 \\ 2\alpha & \alpha-3 & 3-2\alpha & -\alpha \\ -\alpha & 2-\alpha & \alpha-2 & \alpha \end{bmatrix} \begin{bmatrix} P_{i-1} \\ P_i \\ P_{i+1} \\ P_{i+2} \end{bmatrix}$$

where α is a tension parameter which is related to the underlying parametrization. The standard choices of α are:

- $\alpha = 0$: the standard Catmull-Rom spline,
- $\alpha = 1$: the chordal Catmull-Rom spline,
- $\alpha = \frac{1}{2}$: the centripetal Catmull-Rom spline.


The Catmull-Rom spline are local (moving a point modifies only the curve in the neighborhood of the point), the approximation is C^1 but not C^2 , the computation is fast. The centripetal Catmull-Rom spline has additional properties : there is no self-intersection, cusp will never occur, and it follows the control points in a better way.

Note that to close a curve, it is sufficient to add the two last points at the beginning and the two first points at the end:

$$(P_1 P_2 P_3 \dots P_{n-2} P_{n-1} P_n) \longrightarrow (P_{n-1} P_n P_1 P_2 P_3 \dots P_{n-2} P_{n-1} P_n P_1 P_2)$$

and build Catmull-Rom spline on segments $[P_n, P_1]$, $[P_1, P_2]$, $\dots$, $[P_{n-2}, P_{n-1}]$, $[P_{n-1}, P_n]$.

On the next figure, the influence of the parameter α may be observed; the value $\alpha = 0.5$ giving the best result.



XLiFE++ provides the `CatmullRomSpline` class. It has only one constructor from a vector of points P and optional parameters are available:


- the type of parametrization : one of `_xParametrization`, `_uniformParametrization`, **`_chordalParametrization`**, `_centripetalParametrization`
- the tension parameter α (default value : 0.5)
- the boundary conditions : two of `_undefBC`, **`_naturalBC`**, `_clampedBC`, `_periodicBC`
- the tangent vectors at end points (vector of reals) required when using clamped conditions

```

Number n=6;
vector<Point> pts(ns+1);
Real s=0, ds=2*pi_/ns;
for (Number i=0; i<=ns; i++, s+=ds) pts[i]=Point(2*cos(s), sin(s)); //points on ellipse
CatmullRomSpline cat(pts);

```

In this example, as the last point is the same as the first point, the curve will be automatically closed.



Once a `CatmullRomSpline` object is constructed, using either the function `evaluate` or the operator `()`, it can be evaluated at any parameter t in $[0, 1]$.

```

\dots
CatmullRomSpline cat(pts);
Real t=0.5 //middle parameter
Point P=cat(t); //value
Point dP=cat(t, _dt); //first derivative (vector as a point)
Point d2P=cat(t, _dt2); //second derivative (vector as a point)

```

`CatmullRomSpline` allocates also a `Parametrization` object related to the spline parametrization. Using this object, other quantities such as curvilinear abscissa, normal or tangent vector, curvatures are available (see `Parametrization` class):

```

\dots
CatmullRomSpline cat(pts);
Real t=0.5 //middle parameter
const Parametrization& pa=cat.parametrization();
Real c=pa.curvature(t);
Real s=pa.curabc(t);
Reals no=pa.normal(t);
Reals ta=pa.tangent(t);

```

B.14.3 Bézier curve


For the set of control points $(P_i)_{0 \leq i \leq n}$, the **Bézier curve** is defined by

$$Q(t) = \sum_{i=0}^n B_i^n(t) P_i \text{ for } t \in [0, 1]$$

where $B_i^n = C_n^i t^i (1-t)^{n-i}$ are the Bernstein polynomials ($\sum_{i=0}^n B_i^n = 1$). Note that the degree of polynomials is equal to the number of points minus 1. There are the following properties

- $Q(0) = P_0$ and $Q(1) = P_n$, but the curve does not interpolate the interior points $(P_1, \dots, P_{n-1})$,


- $\overrightarrow{P_0P_1}$ (resp. $\overrightarrow{P_{n-1}P_n}$) is a tangent vector to the curve at P_0 (resp. P_n),
- the curve is inside the convex hull of the control points,
- the curve is C^∞ .



XLiFE++ provides the `BezierSpline` class with only one simple constructor from a vector of points P :

```
Number n=5;
vector<Point> points(n+1);
Real x=0, dx=pi_/n;
for (Number i=0; i<=n; i++, x+=dx) points[i]=Point(x, sin(x));
BezierSpline bz(points);
```

The parameter t lives always in the interval $[0, 1]$.



Once a `BezierSpline` object is constructed, using either the function `evaluate` or the operator `()`, it can be evaluated at any parameter $t \in [0, 1]$:

```
\ldots
BezierSpline bz(points);
Real t=0.5;           //middle parameter
Point P=bz(t);        //value
Point dP=bz(t,_dt);   //first derivative (vector as a point)
Point d2P=bz(t,_dt2); //second derivative (vector as a point)
```

`BezierSpline` allocates also a `Parametrization` object related to the spline parametrization. Using this object, other quantities such as curvilinear abscissa, normal or tangent vector, curvatures are available (see `Parametrization` class):

```

\ldots
BezierSpline bz(points);
Real t=0.5;
const Parametrization& pa=bz.parametrization();
Real c=pa.curvature(t);
Real s=pa.curabc(t);
Reals no=pa.normal(t);
Reals ta=pa.tangent(t);

```

B.14.4 B-Spline

The **B-spline** curve is a generalization of the Bézier curve. Let $t_0 \leq t_1 \leq \dots \leq t_m$ a set of $m+1$ knots and the B-spline functions of degree k defined by recurrence:

$$\begin{aligned}
 &\text{for } 0 \leq i \leq m-1 \quad B_{i,0}(t) = \begin{cases} 1 & t_i \leq t < t_{i+1} \\ 0 & \text{else} \end{cases} \\
 &\text{for } k \geq 1, 0 \leq i \leq m-k-1 \quad B_{i,k}(t) = \frac{t-t_i}{t_{i+k}-t_i} B_{i,k-1}(t) + \frac{t_{i+k+1}-t}{t_{i+k+1}-t_{i+1}} B_{i+1,k-1}(t)
 \end{aligned}$$

with the convention $\frac{\bullet}{0} = 0$.

The B-spline functions have a lot of properties, in particular

- $B_{i,k}$ is a polynomial of order k on intervals $[t_j, t_{j+1}]$ with support $[t_i, t_{i+k+1}]$,
- $0 < B_{i,k}(t) < 1$ for $t \in]t_i, t_{i+k+1}[$,
- $B_{i,k}$ is C^∞ at right and is C^{k-r} at knots of multiplicity r


For the set of $n+1$ control points $P_0, P_1, \dots, P_n$ and the set of knots $t_0 \leq t_1 \leq \dots \leq t_m$ with $m \geq n+k+1$, the B-spline curve is defined by

$$Q(t) = \sum_{i=0}^n B_{i,k}(t) P_i \quad \text{for } t_k \leq t \leq t_{n+1}.$$

The B-spline curve is inside the convex hull of the control points, it is C^{k-1} if all the knots are of multiplicity 1, moving a point P_i induces a modification of the points related to the interval $[t_i, t_{i+k}]$. A Bézier curve is a B-Spline with a knots vector of the form $[0, 0, \dots, 0, 1, 1, \dots, 1]$.

To clamp the curve at P_0 choose $t_0 = t_1 = \dots = t_k < t_{k+1}$ and to close the curve duplicate the $k+1$ first points at the end of the set of points.


- Clamped B-spline of degree 3 with 6 control points and knots $[0, 0, 0, 0, 1, 2, 3, 3, 3, 3]$ plotted on $[0, 3]$:



A rational B-spline is defined as following:

$$Q(t) = \frac{\sum_{i=0}^n \omega_i B_{i,k}(t) P_i}{\sum_{i=0}^n \omega_i B_{i,k}(t)} \quad \text{for } t_k \leq t \leq t_{n+1}$$

where $(\omega_i)_{i=0,n}$ are some weights. When the weight ω_i is large, the curve goes to the control point P_i . When all the weights are equal to 1, the rational B-spline coincides with the B-spline.



If $t_0 = t_1 = \dots = t_k < t_{k+1}$ and $P_0 \neq P_1$ then

$$\begin{aligned} Q(t_k) &= P_0, \\ Q'(t_k) &= \frac{k}{t_{k+1} - t_k} \frac{w_1}{w_0} (P_1 - P_0), \\ Q'(t_k) \times Q''(t_k) &= \frac{k^2(k-1)}{(t_{k+1} - t_k)^2(t_{k+2} - t_k)} \frac{w_1 w_2}{w_0^2} (P_1 - P_0) \times (P_2 - P_0), \\ \kappa &= \frac{k-1}{k} \frac{t_{k+1} - t_k}{t_{k+2} - t_k} \frac{w_1 w_2}{w_0^2} \frac{2A}{c^3} \quad (\text{curvature}) \end{aligned}$$

with A the surface of the triangle (P_0, P_1, P_2) and $c = \|P_1 - P_0\|$. That gives a way to match the rational B-spline to another curve up to C^2 .

By solving a linear inverse problem, the control points may be calculated in order to interpolate a given set of points. In that case, the spline is named interpolation B-spline. For such spline, it is possible to impose the derivative vectors at the endpoints when the spline is clamped.

XLiFE++ provides the `BSpline` class with constructors that takes a vector of points P and some optional data:

- the type of B-spline, either `_splineApproximation` or `_splineInterpolation`
- the degree of B-spline, default value 3
- the type of parametrization : one of `_uniformParametrization`, `_chordalParametrization`, `_centripetalParametrization`
- the boundary conditions : two of `_undefBC`, `_naturalBC`, `_clampedBC`, `_periodicBC`
- derivative vectors at end points when clamped B-spline is selected
- the vector of weights (default 1)

The given vector of points is either the list of control points (approximation B-spline) or the list of interpolation points (interpolation B-spline). When the type of B-spline is not given, it is assumed to be an approximation B-spline:


```
Number n=6;
vector<Point> pts(n+1);
Real s=0, ds=2*pi_/n;
for(Number i=0;i<=n;i++,s+=ds) pts[i]=Point(2*cos(s),sin(s)); //points on ellipse
BSpline bs(pts,3,_periodicBC);
```

Specifying a periodic condition at starting point stands obviously for periodic condition at ending point!

To use some weights, define a vector of weights of the size of vector of control points:

```
vector<real_t> we(pts.size(),1.);
for(Number k=0;k<we.size();k+=2) we[k]=0.5;
BSpline bsw(pts,3,_periodicBC,_periodicBC,we);
```

Because of the signature of the constructor, both boundary conditions have to be specified even they are redundant!



Once a `BSpline` object is constructed, using either the function `evaluate` or the operator `()`, it can be evaluated at any parameter $t \in [0, 1]$:


```
\ldots
BSpline bs(pts,3,_periodicBC);
Real t=0.5; //middle parameter
Point P=bs(t); //value
Point dP=bs(t,_dt); //first derivative (vector as a point)
Point d2P=bs(t,_dt2); //second derivative (vector as a point)
```

`BSpline` allocates also a `Parametrization` object related to the spline parametrization. Using this object, other quantities such as curvilinear abscissa, normal or tangent vector, curvatures are available (see `Parametrization` class):

```
\ldots
BSpline bs(pts,3,_periodicBC);
Real t=0.5; //middle parameter
const Parametrization& pa=bs.parametrization();
Real c=pa.curvature(t);
Real s=pa.curabc(t);
Reals no=pa.normal(t);
Reals ta=pa.tangent(t);
```

The following example shows how to build a clamped interpolation B-spline with a uniform parametrization from 5 points located on the sine curve:

```
\ldots
vector<Point> pts(5,Point(0.,0.));
pts[1]=Point(pi_/4,sqrt(2)/2.);pts[2]=Point(pi_/2,1.);
pts[3]=Point(3*pi_/4,sqrt(2)/2.);pts[4]=Point(pi_,0.);
Reals d0(2,1.),d1=d0; d1[1]=-1.; //derivatives at end points
BSpline bs(_SplineInterpolation, pts, 3,_uniformParametrization,
_clampedBC,_clampedBC,d0,d1);
```



When specifying only `_splineInterpolation` and a set of points in constructor, the B-spline will be a natural interpolation B-spline of degree 3 with a uniform parametrization (not rational).

B.14.5 Spline surface (nurbs)

The most common method to approximate surface are NURBS (non-uniform rational B-spline) that are no more than the cross-product of two rational B-splines. Let

- a set of $(m+1) \times (n+1)$ control points P_{ij} , $0 \leq i \leq m$ and $0 \leq j \leq n$
- a knot vector in u -direction and v -direction: $U = [u_0, u_1, \dots, u_k]$ and $V = [v_0, v_1, \dots, v_\ell]$,
- the degree p in u -direction and the degree q in v -direction
- $k = m + p + 1$ and $\ell = n + q + 1$

The NURBS surface is defined by

$$(u, v) \longrightarrow Q(u, v) = \frac{\sum_{i=0}^m \sum_{j=0}^n \omega_{ij} B_{i,p}(u) B_{j,q}(v) P_{ij}}{\sum_{i=0}^m \sum_{j=0}^n \omega_{ij} B_{i,p}(u) B_{j,q}(v)}.$$


To deal with nurbs, XLIFE++ provides the `Nurbs` class. There is only one constructor from a vector of vectors of points (control points) and optional parameters:

- the degrees of B-spline along u / v parameter (default is 3)
- the boundary conditions along u / v parameter, for each parameter, two of `_naturalBC`, `_clampedBC`, `_periodicBC`
- the vector of vectors of weights (default no weight)

```

Number n=4;
Real ds=pi/(2*n), u=-pi/2, v=0;
PointMatrix pts(2*n+1, Points(n+1));
for (Number i=0; i<=2*n; i++, u+=ds) // points on the quarter of unit sphere
{
    v=0;
    for (Number j=0; j<=n; j++, v+=ds) pts[i][j]=Point(cos(u)*cos(v), cos(u)*sin(v), sin(u));
}
NURBS nuA(_splineApproximation, pts); //create approximation nurbs
NURBS nuI(_splineInterpolation, pts); //create interpolation nurbs

```



NURBS approximation and NURBS interpolation

Once a **Nurbs** object is constructed, using either the function `evaluate` or the operator `()`, it can be evaluated at any parameter $(u, v) \in [0, 1] \times [0, 1]$:

```

\dots
Point P=nu(0.5,0.5); //value
Point duP=nu(0.5,0.5,_d1); //first derivative (vector as a point)
Point dvP=nu(0.5,0.5,_d2); //first derivative (vector as a point)

```

Nurbs allocates also a **Parametrization** object related to the spline parametrization. Using this object, other quantities such as curvilinear abscissa, normal or tangent vector, curvatures are available (see **Parametrization** class):

```

\dots
const Parametrization& pa=nu.parametrization();
real_t u=0.5, v=0.5;
Reals cu=pa.curvatures(u,v); //two main curvatures
Reals no=pa.normal(u,v); //normal vector
Reals ta=pa.tangents(u,v); //two orthogonal tangent vectors in a same vector

```

B.15 Timer

The `Timer` class is a utility class to perform computational time analysis (CPU time and elapsed time) and manage dates. For a user, only a few functions are useful. They do not involve explicitly some `Timer` objects. There are some functions to get date in various forms :

```
String theTime();           // returns current time
String theDate();           // returns current date as dd.mm.yyyy
String theShortDate();      // returns current date as mm/dd/yyyy or dd/mm/yyyy
String theLongDate();       // returns current date as Month Day, Year or Day Month Year
String theIsoDate();        // returns ISO8601 format of current date (yyyy-mm-dd)
String theIsoTime();        // returns ISO8601 format of current time (hh-mi-ss)
```

and others to get CPU or elapsed time :

```
double cpuTime();           // user time ("cputime") in sec. since last call
double cpuTime(const String&); // same and prints it with comment
double totalCpuTime();      // elapsed time in sec. since first call
double totalCpuTime(const String&); // same and prints it with comment
double elapsedTime();       // elapsed time in sec. since last call
double elapsedTime(const String&); // same and prints it with comment
double totalElapsedTime();  // elapsed time in sec. since first runtime call
double totalElapsedTime(const String&); // same with comment
```

Using these functions, it is easy to perform time computation analysis. For instance :

```
#include "xlife++.h"
using namespace xlifepp;
int main()
{
    init(fr); // initializes timers
    // task 1
    \ldots
    cpuTime("CPU time for task 1");
    elapsedTime("elapsed time for task 1");
    // task 2
    \ldots
    cpuTime("CPU time for task 2");
    elapsedTime("elapsed time for task 2");
    // end of tasks
    totalCpuTime("total CPU time");
    totalElapsedTime("total elapsed time");
}
```

B.16 Memory

Using the `Memory`, the memory usage can be inspected using the following functions:

```
Real phyMem = Memory::physicalMem(); //physical memory
Real freeMem = Memory::physicalFreeMem(); //free physical memory
Real procMem = Memory::processPhysicalMem(); //physical memory used by the process
```

The default unit is the MegaBytes (Mo), but you can change the unit by specifying one of the following units in the argument of memory functions:

```
enum MemoryUnit { _byte, _kilobyte, _megabyte, _gigabyte, _terabyte};
```

B.17 Mathematical resources

Mathematical resources are defined in [mathsResources](#) library of XLIFE++. Classical kernels excepted (for Laplace, Helmholtz and Maxwell 2d or 3d problems), it contains a lot of stuff shown here.

B.17.1 Random generators

XLIFE++ offers a uniform distribution generator and a normal distribution generator. As C++11 now provides a lot of random generators, contrary to C98 that proposes only a uniform distribution generator, the front end user functions will use prior the C++11 generators if C++11 is available (default behavior from gcc 6.1). These front end functions are the following:

```
Real uniformDistribution(Real a=0., Real b=1.); //real from uniform distribution on [a,b[
Real normalDistribution(Real mu=0., Real sigma=1.); //real from normal distribution (mu,sigma)
```

`a`, `b`, `mu`, `sigma` have the specified default values if they are not given. For instance to build a vector of random values of size 100:

```
Reals us(100), ns(100);
for(Number i=1; i<=100; i++) us(i) = uniformDistribution();
for(Number i=1; i<=100; i++) ns(i) = normalDistribution(2.,5.); // normal mu=2, sigma=5
```

Random vectors or random matrices can be constructed in a direct way :

```
Reals us = uniformDistribution<Real>(100); // uniform on [0,1[
Reals ns = normalDistribution<Real>(100,2.,5.); // normal distribution mu=2, sigma=5
RealMatrix mn = normalDistribution<Real>(10,10); // normal distribution mu=0, sigma=1 (default)
```



Works also with complex vectors or complex matrices.



Because of multiple random functions proposed, do not omit the dot in distribution parameters (`Real`) when they are passed explicitly.



There exist also functions addressing directly double or complex pointers to deal with C vectors, for instance:

```
Reals us(100);
uniformDistribution(&us[0], -1.,1.,100); //fill us using uniform distribution on [-1,1[
```

If you want to address the C98 random generators when C++11 is on, you have to use the "C" version of previous functions:

```
Real uniformDistributionC(Real a=0., Real b=1.); //C-style uniform distribution on [a,b[
Real normalDistributionC(Real mu=0., Real sigma=1.); //C-style normal distribution (mu,sigma)
```

In C-style, two normal distribution generators are available : the Marsaglia generator (default) and the Box-Muller generator. You can specify it by using keyword (`_MarsagliaGenerator` or `_BoxMullerGenerator`) after normal distribution parameters:

```
Reals us(100);
normalDistributionC(&us[0], 0., 1., _BoxMullerGenerator, 100);
```



Random generators are automatically initialized when starting XLIFE++ applications. Initialization value (the seed) is based on current time. It is possible to re-initialize random engines them with your own seed :

```
int myseed=1000;
initRandomGenerators(myseed);
```

B.17.2 Gauss formulae

You can use:

- the Gauss-Legendre formula

```
void gaussLegendreRule(Number n, Reals& points, Reals& weights);
```

- the Gauss-Lobatto formula

```
void gaussLobattoRule(Number n, Reals& points, Reals& weights);
```

- the Gauss-Jacobi formula

```
void gaussJacobiRule(Number n, Real a, Real b, Reals& points, Reals& weights);
```

The $(n+1)/2$ first positive points in ascending order only are returned.

B.17.3 Exact solutions

The field scattered by a solid sphere of radius R of an incoming field $\Phi_w = e^{ikx}$ with Neumann or Dirichlet boundary conditions on the sphere are available with the following functions:

```
Complex scatteredFieldSphereNeumann(const Point& x, Parameters& param);
Complex scatteredFieldSphereDirichlet(const Point& x, Parameters& param);
```

The field scattered by a solid disk of radius R of an incoming field $\Phi_w = \exp^{ikx}$ with Neumann or Dirichlet boundary conditions on the disk are available with the following functions:

```
Complex scatteredFieldDiskDirichlet(const Point& x, Parameters& param);
Complex scatteredFieldDiskNeumann(const Point& x, Parameters& param);
```

These four functions require an associated `Parameters` as second argument with

- a `Parameter` bearing the name "k" and holding the value of the wave number k.
- a `Parameter` bearing the name "radius" and holding the value of the sphere radius.

The field scattered by a solid sphere of radius R of an incoming field $\Phi_w = e^{ikz}$ with tangential boundary condition $E \times n = 0$ (electric field) on the sphere is available with the following function:

```
Complexes scatteredFieldMaxwellExn(const Point& x, Parameters& param);
```

This function requires an associated `Parameters` as second argument with a `Parameter` bearing the name "k" and holding the value of the wave number k.

At last, the spherical harmonics Y_l^m up to order n on the unit sphere and their gradient are available with the following functions:

```
void sphericalHarmonics(const Point& x, std::vector<Complexes>& Yml);
void sphericalHarmonicsSurfaceGrad(const Point& x, std::vector<std::vector<Complexes>>& gradYlm);
```

B.17.4 Special functions

Bessel and Hankel functions

Bessel and Hankel functions are available at any order (and also for real orders) for real or complex argument (through a wrapper to the AMOS library).

- Bessel functions of the first kind $J_N(x)$

```
Real bessellJ(Real x, Number N);  
Complex bessellJ(const Complex& z, Real N);  
Real bessellJ0(Real x); // shortcut for order 0 and real case  
Complex bessellJ0(const Complex& z); // shortcut for order 0 and complex case  
Real bessellJ1(Real x); // shortcut for order 1 and real case  
Complex bessellJ1(const Complex& z); // shortcut for order 1 and complex case  
Reals bessellJ0N(Real x, Number N); // shortcut for orders 0 to N and real case
```

- Bessel functions of the second kind $Y_N(x)$

```
Real bessellY(Real x, Number N);  
Complex bessellY(const Complex& z, Real N);  
Real bessellY0(Real x); // shortcut for order 0 and real case  
Complex bessellY0(const Complex& z); // shortcut for order 0 and complex case  
Real bessellY1(Real x); // shortcut for order 1 and real case  
Complex bessellY1(const Complex& z); // shortcut for order 1 and complex case  
Reals bessellY0N(Real x, Number N); // shortcut for orders 0 to N and real case
```

- Modified Bessel functions of the first kind $I_N(x)$

```
Real bessellI(Real x, Number N);  
Complex bessellI(const Complex& z, Real N);  
Real bessellI0(Real x); // shortcut for order 0 and real case  
Complex bessellI0(const Complex& z); // shortcut for order 0 and complex case  
Real bessellI1(Real x); // shortcut for order 1 and real case  
Complex bessellI1(const Complex& z); // shortcut for order 1 and complex case  
Reals bessellI0N(Real x, Number N); // shortcut for orders 0 to N and real case
```

- Modified Bessel functions of the second kind $K_N(x)$

```
Real bessellK(Real x, Number N);  
Complex bessellK(const Complex& z, Real N);  
Real bessellK0(Real x); // shortcut for order 0 and real case  
Complex bessellK0(const Complex& z); // shortcut for order 0 and complex case  
Real bessellK1(Real x); // shortcut for order 1 and real case  
Complex bessellK1(const Complex& z); // shortcut for order 1 and complex case  
Reals bessellK0N(Real x, Number N); // shortcut for orders 0 to N and real case
```

- Hankel functions of the first kind $H1_N(x)$

```
Complex hankelH1(Real x, Number N); // general routine for real case  
Complex hankelH1(const Complex& z, Real N); // general routine for complex case and real order  
Complex hankelH10(Real x); // shortcut for order 0 and real case  
Complex hankelH10(const Complex& z); // shortcut for order 0 and complex case  
Complex hankelH11(Real x); // shortcut for order 1 and real case  
Complex hankelH11(const Complex& z); // shortcut for order 1 and complex case  
Complexes hankelH10N(Real x, Number N); // shortcut for orders 0 to N and real case
```

- Hankel functions of the second kind $H_{2N}(x)$

```
Complex hankelH2(Real x, Number N); // general routine for real case
Complex hankelH2(const Complex& z, Real N); // general routine for complex case and real order
Complex hankelH20(Real x); // shortcut for order 0 and real case
Complex hankelH20(const Complex& z); // shortcut for order 0 and complex case
Complex hankelH21(Real x); // shortcut for order 1 and real case
Complex hankelH21(const Complex& z); // shortcut for order 1 and complex case
Complexes hankelH20N(Real x, Number N); // shortcut for orders 0 to N and real case
```

- Airy and Biry functions

```
Complex airy(Real x, DiffOpType d=_id); // general function for real case
Complex airy(const Complex& z, DiffOpType d=_id); // general function for complex case
Complex biry(Real x, DiffOpType d=_id); // general function for real case
Complex biry(const Complex& z, DiffOpType d=_id); // general function for complex case
```

Gamma and exponential integral functions

The gamma function and related functions are available with the following routines:

```
Real gammaFunction(Int n);
Real gammaFunction(Real x);
Complex gammaFunction(const Complex& z);
Real logGamma(Real x);
Complex logGamma(const Complex& z);
Complex logGamma(const Complex& z);
Real diGamma(Int n);
Real diGamma(Real x);
Complex diGamma(const Complex& z);
```

The exponential integrals functions and related stuff are provided by the following functions:

```
Complex e1z(const Complex& z); // return E1(z)
Complex e1nz(const Complex& z); // return E1(z) + gamma + log(z) = \sum_{n>0} (-z)^n / n n!
Complex expzE1z(const Complex& z); // return exp(z)*E1(z)
Complex zexpzE1z(const Complex& z); // return z*exp(z)*E1(z)
Complex ascendingSeriesOfE1(const Complex& z); // ascending series in E1 formula (used for
'small' z)
Complex continuedFractionOfE1(const Complex& z); // continued fraction in E1 formula (used for
'large' z)
```

The erf function

$$\operatorname{erf} z = \frac{2}{\sqrt{\pi}} \int_0^z e^{-t^2} dt$$

is also available from

```
complex_t erf(complex_t z);
```

Orthogonal polynomials

Chebyshev, Gegenbauer, Jacobi and Legendre polynomials up to order n are available using the following functions:

```
void chebyshevPolynomials(Real x, Reals& val);
void gegenbauerPolynomials(Real lambda, Real x, Reals& val);
void jacobiPolynomials(real_t a, real_t b, real_t x, Reals& val);
void jacobiPolynomials01(Real a, Real b, Real x, Reals& val); // Jacobi polynomials on [0, 1]
void legendrePolynomials(Real x, Reals& val);
void legendrePolynomialsDerivative(Real x, Reals& val);
void legendreFunctions(Real x, std::vector<Reals>& Plm);
void legendreFunctionsDerivative(Real x, const std::vector<Reals>& Plm, std::vector<Reals>& dPlm);
```

B.17.5 Computation of polynomial roots

You can use:

- the quadratic method for degree 2 polynomials

```
Complexes quadratic(Real a, Real b, Real c);  
Complexes quadratic(Complex a, Complex b, Complex c);
```

- the Cardan method for degree 3 polynomials

```
Complexes cardan(Real a, Real b, Real c, Real d);  
Complexes cardan(Complex a, Complex b, Complex c, Complex d);
```

- the Ferrari method for degree 4 polynomials

```
Complexes ferrari(Real a, Real b, Real c, Real d, Real e);
```

B.17.6 Basic quadrature methods and FFT

XLiFE++ proposes some useful basic quadrature methods (rectangle, trapeze, Simpson, Laguerre, adaptive trapeze) to compute 1D integrals ($h = \frac{b-a}{n}$):

$$\text{rectangle} : \int_a^b f(t) dt \sim h \sum_{i=0, n-1} f(a + ih)$$

$$\text{trapeze} : \int_a^b f(t) dt \sim \frac{h}{2} \left(f(a) + 4 \sum_{i=1, n/2} f(a + (2i-1)h) + 2 \sum_{i=1, n/2-1} f(a + 2ih) + f(b) \right) \quad (n \text{ even})$$

$$\text{Simpson} : \int_a^b f(t) dt \sim \frac{h}{3} \left(f(a) + 2 \sum_{i=1, n-1} f(a + ih) + f(b) \right)$$

with f a real or complex function. They respectively integrate exactly P0 polynomials, P1 polynomials and P3 polynomials and approximate the integral with order 1, 2 and 3.

They compute integrals of real/complex function either given by a C++ function of the form (T being a real value (float, double, ...) type or a complex type (complex<float>, complex<double>, ...))

```
T f(real_t){\ldots}  
T f(real_t, Parameters&){\ldots}
```

or by a vector of values given by an explicit vector or an iterator. So, all the methods are templated by the type T of function values and possibly by a generic iterator (say Iterator).

```
T rectangle(number_t n, real_t h, Iterator itb, T& intg);  
T rectangle(const vector<T>& f, real_t h);  
T rectangle(T(*f)(real_t), real_t a, real_t b, number_t n);  
T rectangle(T(*f)(real_t, Parameters&), Parameters& pars, real_t a, real_t b, number_t n);  
  
T trapz(number_t n, real_t h, Iterator itb, T& intg);  
T trapz(const vector<T>& f, real_t h);  
T trapz(T(*f)(real_t), real_t a, real_t b, number_t n);  
T trapz(T(*f)(real_t, Parameters&), Parameters& pars, real_t a, real_t b, number_t n);  
  
T simpson(number_t n, real_t h, Iterator itb, T& intg);  
T simpson(const vector<T>& f, real_t h);  
T simpson(T(*f)(real_t), real_t a, real_t b, number_t n);  
T simpson(T(*f)(real_t, Parameters&), Parameters& pars, real_t a, real_t b, number_t n);  
  
T laguerre(T(*f)(real_t), real_t t0, real_t a, number_t nq, vector<real_t>& points,  
           vector<real_t>& weights);
```

```
T laguerre(T(*f)(real_t,Parameters&), Parameters& pars, real_t t0, real_t a, number_t nq,
    vector<real_t>& points, vector<real_t>& weights);

T adaptiveTrapz(T(*f)(real_t), real_t a, real_t b, real_t eps=1E-6)
T adaptiveTrapz(T(*f)(real_t,Parameters&), Parameters& pars, real_t a, real_t b, real_t eps=1E-6)
```

For instance, to compute

$$I = \int_0^{\pi} \sin x \, dx$$

```
Real f(Real x){return sin(x);}
\dots
Real ir=rectangle(f, 0., pi_, 20);
Real it=trapz(f, 0., pi_, 20);
Real is=simpson(f, 0., pi_, 20);
Real ia=adaptiveTrapz(f, 0., pi_, 0.00001);
```

XLiFE++ provides also the standard 1D discrete fast Fourier transform with 2^n values:

$$g_k = \sum_{j=0, n-1} f_j e^{-2i\pi \frac{jk}{n}}.$$

FFT and inverse FFT are computed using some functions addressing real or complex vectors of size 2^n :

```
Number ln=6, n=64;
Vector<Complex> f(n), g(n), f2(n);
for(Number i=0; i<n; i++) f[i]=std::sin(2*i*pi/(n-1));
fft(f,g); ifft(g,f2); // f2 should be close to f
// or
Vector<Complex> fhat=fft(f), fihat=ifft(f);
```



If the vector you give is not of 2^n length, **fft/ifft** computation will use only the first 2^n values with 2^n the greater value less than the vector size. Remember that even the input vector is a real vector the output is always a complex vector.

Advanced users can also use some functions **fft/ifft** addressing iterators that can handle any collection of real or complex values :

```
template<typename IterA, typename IterB>
void ffta(IterA ita, IterB itb, number_t log2n, real_t q)
void fft(IterA ita, IterB itb, number_t log2n)
void ifft(IterA ita, IterB itb, number_t log2n)

template<typename T>
vector<complex_t> fft(const vector<T>& f);
vector<complex_t>& fft(const vector<T>& f, vector<complex_t>& g);
vector<complex_t> ifft(const std::vector<T>& f);
vector<complex_t>& ifft(const std::vector<T>& f, std::vector<complex_t>& g);
```

B.17.7 ODE solvers

XLiFE++ provides some ODE solvers : Euler, Runge-Kutta 4 and Runge-Kutta 45 that is an adaptive step time solver based on the Dormand-Prince method (see http://en.wikipedia.org/wiki/Dormand-Prince_method). All solvers are templated by the type of the state $y \in V$ involved in the first order differential equation:

$$\begin{cases} y'(t) = f(t, y(t)) & t \in]t_0, t_f[\\ y(t_0) = y_0 \end{cases}$$

with $f:]t_0, t_f[\times V \rightarrow V$ a non-stiff function.

The user function f may be any C++ function of the form (T any scalar/vector/matrix type):

```

T& f(real_t t, const T& y, T& fty); //fty the returned value
// for instance, with XLife++ common types
Real f(Real t, const Real& y, Real& fty){\ldots; return fty;} // real scalar ODE
Complex& f(Real t, const Complex& y, Complex& fty){\ldots; return fty;} // complex scalar
ODE
Reals& f(Real t, const Reals& y, Reals& fty){\ldots; return fty;} // real vector ODE
Complexes& f(Real t, const Complexes& y, Complexes& fty){\ldots; return fty;} // complex vector
ODE

```

ODE solvers are objects of template classes `EulerT`, `RK4T` and `Ode45T`, but they can also be invoked by simple functions

```

template <typename T>
Vector<T> euler(T& (*f)(Real, const Real& y, Real& fty), Real a, Real b, Real dt, const T& y0);
Vector<T> rk4(T& (*f)(Real, const Real& y, Real& fty), Real a, Real b, Real dt, const T& y0);
pair<Vector<Real>, Vector<T>> ode45(T& (*f)(Real, const Real& y, Real& fty), Real a, Real b, Real
dt, const T& y0, Real prec);

```

In adaptive RK45 method, the time step may grow to become very large. To still get a meaningful number of times step, the time step is limited by the initial guess `dt`. Even if the initial guess `dt` is very large, the method should be convergent if the problem is not stiff.

The following example deals with the linear pendulum (ODE of order 2):

```

Real omg=1., th0=pi_/4, thp0=0.;
Reals& f(Real t, const Reals& y, Reals& fyt)
{ fyt.resize(2);
  fyt[0]=y[1]; fyt[1]=-omg*omg*y[0];
  return fyt;}
Reals yex(Real t) //exact solution
{ Reals yy(2,0.);
  yex[0] = thp0*sin(omg*t)/omg + th0*cos(omg*t);
  yex[1] = thp0*cos(omg*t) - th0*omg*sin(omg*t);
  return yex;}
...
Real t0=0,tf=1,dt=0.01, t=t0, errsup=0;
Reals y0(2,0.);y0[0]=th0; y0[1]=thp0;
Vector<Reals> sol = euler(f,t0,tf,dt,y0);
for(Number i=0;i<sol.size(); i++, t+=dt)
  errsup=max(errsup,norm(sol[i]-yex(t)));
theCout<<"euler : nb dt="<<sol.size()<<" error sup = "<<errsup<<eol;

t=t0; errsup=0;
sol = rk4(f,t0,tf,dt,y0);
for(Number i=0;i<sol.size(); i++, t+=dt)
  errsup=max(errsup,norm(sol[i]-yex(t)));
theCout<<"rk4 : nb dt="<<sol.size()<<" error sup = "<<errsup<<eol;

t=t0; errsup=0;
pair<Reals,Vector<Reals>> solp = ode45(f,t0,tf,0.1,y0,1E-6);
Number n=solp.first.size();
for(Number i=0;i<n; i++)
  errsup=std::max(errsup,norm(solp.second[i]-yex(solp.first[i])));
theCout<<"ode45 : nb dt="<<n<<" error sup = "<<errsup<<eol;

```

Because, `ode45` is an adaptive method, the time step is not constant. So the `ode45` function return times and state values as a pair of vectors. The previous code gives

```

euler : nb dt=101 error sup = 0.00393671
rk4 : nb dt=101 error sup = 6.54499e-11
ode45 : nb dt=12 error sup = 5.25629e-08

```

showing the advantage to use Ode45!



Contrary to Euler and RK4 method, Ode45 handles some internal parameters : `nbtry_` the maximum number of tries (12) when adapting the time step, `minscale_`(0.125) and `maxscale_`(4) to limit the variation of the time step at each iteration. If you want to modify these internal parameters, you have to use an object of the `Ode45T` class; see the dev documentation.



CMAKE tutorial

CMAKE (<http://cmake.org>), as a cross-platform builder, only needs a configuration file named `CMakeLists.txt`, at the root directory of the software you develop, so-called *Source directory*. This configuration file is independent of the compiler and the platform. In order to generate native makefiles or workspaces of your favorite IDE (Visual Studio, Xcode, Eclipse, CodeBlocks, ...), CMAKE needs another directory, so-called *build directory*, in which files generated during the build process will be written.

The *build directory* is recommended not to be the *source directory*. For XLIFE++ compilation, we suggest you to set the *build directory* as a subdirectory of XLIFE++ install directory, with the name *build* for instance.

C.1 On the command line

On LINUX and MAC OS, you can use the `cmake` command or its default GUI `ccmake`. On WINDOWS, you can use the `cmake.exe` command.




Figure C.1: `ccmake` (macOS, Linux)

As it was said during introduction, a CMAKE call needs 2 directories : the *source directory* (command-line option `-S`) and the *build directory* (command-line option `-B`), but there is an easier way to call CMAKE: by calling it from the *build directory* and giving only the *source directory*, as in the following :

```
cmake relative/path/to/CMakeLists.txt [options]
ccmake [options] relative/path/to/CMakeLists.txt
```

C.2 Through GUI applications

When running CMAKE GUI application, you have to set the *source directory* and the *build directory*. Then, you click the *Configure* button. It will ask you the generator and the compiler you want. Then, you click the *Generate* button, to generate your IDE project file or your Makefile.




Figure C.2: CMAKE application (macOS on the left and Windows on the right)

C.3 CMAKE options and cache entries

C.3.1 On the command line

The CMAKE help will give you the full list of command-line options. Only 2 are eventually useful:

-G to define the generator. By default, the cmake command generates a `Makefile`. This is the "Unix Makefiles" generator on LINUX and MAC OS or "MinGW Makefiles" generator on WINDOWS. But you can use other generators to have IDE files for your favorite IDE, such as Eclipse, CodeBlocks, Xcode, Visual Studio, ...:

```
cmake relative/path/to/CMakeLists.txt -G <generator_name> [options]
```

The following command chooses for instance to use codeblocks on unix platform:

```
cmake relative/path/to/CMakeLists.txt -G "CodeBlocks - Unix Makefiles" [options]
```

Please read the cmake command help to know the potential list of available generators on your computer.

-D to define cache entries. Cache entries can be shown as dedicated configuration options for the software you want to build.

```
cmake relative/path/to/CMakeLists.txt [-G <generator_name>] -DKEY1=value1 -DKEY2=value2
-DKEY3=value3 \ldots
```



Please notice that the key is always sticked to the `-D` option, and that the equal sign is sticked to both key and value

C.3.2 Through GUI applications

Available cache entries appears in the main frame after the first click on configure. You can organise them by grouping (cache entries beginning with the same prefix are in the same group whose name is the prefix in common) or by showing/hiding advanced cache entries.

Each time you change the value of one or several cache entries, you have to click on the *Configure* button again, before clicking on *Generate*